PRELIMINARIES

PRELIMINARY PARTICULARS

A PARTIES

The "Employer" is :

Kenya Power & Lighting Co. Ltd P.O. Box 30099 - 00100 NAIROBI Shs.

The "Project Manager" is :

Kenya Power & Lighting Co. Ltd P.O. Box 30099 - 00100 NAIROBI

B <u>SITE</u>

The site is located at lodwar town, Turkana County imediately after the Turkwel bridge towards the county headquarters and next to existing Lodwar Kenya power generation station

The Contractor shall obtain the Project Manager's approval for the siting of all temporary buildings, spoil heaps, temporary paths and storage areas for materials.

The Contractor shall visit the Site to acquaint himself with its nature and position, the nature of the ground, substrata and other local conditions, position of power and water supplies, access roads or any other limitations, and no claims for extras will be considered on account of lack of knowledge in this respect.

The Contractor must obtain the Project Manager's approval and directions regarding the use of any materials found on the site.

C ACCESS TO SITE

Access to site shall be as directed by the Project Manager. The Contractor shall strictly observe police regulations regarding traffic movement.

Preliminaries

Carried to collection

		Shs.
A	WORKING AND STORAGE SPACE	
	Working and storage space will be confined to the area designated by the Project Manager within the plot boundary.	
В	WORKING HOURS	
	The Work must be carried out to cause the minimum inconvenience to the occupants of the adjoining premises. In particular, no hammering, mechanical drilling or other unduly noisy work may be commenced before 8.00 a.m. or continued after 6.00 p.m. without prior approval of the Project Manager.	
С	DESCRIPTION OF THE WORKS	
	The Works comprise erection of a new office block	
	a) Construction shall generally consist of substructures,	
	b) Superstructures reinforced concerete.	
	c) Walls are generally in masonry.	
	 d) Finishes include granito floor tiles, terrazzo floor finish, keying, plastered and painted walls and several other finishes. 	
	e) Windows shall largelly be mild steel.	
	f) Mild steel gutters	
	Services	
	 a) The services include installation of Electrical, internal drainage & plumbing, fire fighting, airconditioning and Mechanical Installations. 	
	External Works	
	Including but not limited to pcc slabs laid on murram blinding on well compacted base and kerbs and landscaping	
	Preliminaries Carried to collection KShs.	

Π			Shs.
	GENERAL MATTERS		
	SUFFICIENCY OF TE	NDER	
А	as to the correctness a rates and prices stated shall cover all his oblig	be deemed to have satisfied himself before tendering and sufficiency of his Tender for the Works and of the d in the Priced Bills of Quantities, which rates and prices gations under the Contract and all matters and things ber completion and maintenance of the Works.	
в	STAMP CHARGES		
		llow for the payment of all Stamp Charges in arety and Contract Agreement.	
С	DEFINITIONS AND A	BBREVIATIONS	
	Terms used in these E	Bills of Quantities shall be interpreted as follows:	
	"Approved"	Shall mean approved by the Project Manager.	
	"as directed"	Shall mean as directed by the Project Manager.	
	"B.S."	Shall mean the current British Standard specifications published by the British Standards Institution, 2 Park Street, London W.I., England.	
	"C.M."	Shall mean Cubic Metres.	
	"S.M."	Shall mean Square Metres.	
	"L.M."	Shall mean Linear Metres.	
	"MM"	Shall mean Millimetres.	
	"Kg."	Shall mean Kilogramme.	
	"No."	Shall mean Number.	
	"M.S" or M/S	Shall mean Measured Separately	
	Ditto or Do	Shall mean the whole of the preceding description except as qualified in the description in which it occurs.	
	Preliminaries	Carried to collection KShs.	

Π		Shs.
А	PROGRESS SCHEDULE	
	The Contractor shall, upon receiving instructions to proceed with the Work, draw up a time and progress Schedule setting out the order in which the Works are to be carried out with the appropriate dates thereof. This Time and Progress schedule is to be agreed with the Project Manager and no deviation from the order set out in this Schedule will be permitted without the written consent of the Project Manager. The Main Contractor will be responsible for arranging the above programme with all Sub-Contractors including the Nominated Sub-Contractors and Nominated Suppliers.	
в	FIGURED DIMENSIONS	
	Figured dimensions are to be followed in preference to dimensions scaled from the Drawings; but wherever possible dimensions are to be taken on the Site or from the Buildings. Before any Work is commenced by Sub- Contractors or Specialist Firms, dimensions must be checked on the Site and/or buildings and agreed with the Contractor, irrespective of the comparable dimensions shown on the Drawings. The Contractor shall be responsible for the accuracy of such dimensions.	
С	PROVISIONAL WORK	
	All "Provisional" and other work liable to adjustment under this Contract shall be left uncovered for a reasonable time to allow all measurements needed for such adjustment to be taken by the Quantity Surveyor. Immediately the work is ready for measurement, the Contractor shall give notice to the Quantity Surveyor.	
	If the Contractor makes default in these respects he shall, if the Project Manager so directs, uncover the work at his own expense to enable the measurements to be taken.	
D	EXISTING SERVICES	
	Prior to commencement of any work the Contractor is to ascertain from the relevant Authorities the exact position, depth and level of all existing electric cables, water pipes or other services in the area and he shall make whatever provisions may be required by the Authorities concerned for the support and protection of such services. Any damage or disturbance caused to any services shall be reported immediately to the Project Manager and the relevant Authority and shall be made good to their satisfaction at the Contractor's expense.	
Е	TRANSPORT TO AND FROM THE SITE	
	The Contractor shall include in his prices for the transport of materials workmen, etc., to and from the Site of the Proposed Works, at such hours and by such routes and vehicles as are permitted by the Authorities and in particular by the Transport Licensing Board	
	Preliminaries Carried to collection KShs.	
Ш		

		Shs.
А	PUBLIC AND PRIVATE ROADS, PAVEMENTS, ETC	
	The Contractor will be required to make good, at his own expense any damage he may cause to the present road surfaces and pavements within or beyond the boundary of the Site, during the period of the Works. In particular, all existing trees, shrubs, plants. etc., which may be destroyed or damaged during the progress of the Works are to be made good by the Contractor to the approval of the Project Manager.	
в	POLICE REGULATIONS	
	The Contractor is to allow for complying with all instructions and regulations of the police Authorities.	
С	ENVIRONMENTAL REGULARATIONS	
	The Contractor shall observe all the requirements of the National Environment Management Authority (NEMA) and especially those conditions given in the Project's Environmental Impact Assessment Report Approved by NEMA. The Contractor shall collaborate with the Environmental Impact Assessment (EIA) expert to ensure that proposed mitigation measures are adhered to during construction phase and where necessary approriate mending up activities undertaken and the same reported back to NEMA as required.	
	In particular the Contractor shall give special emphasis to control dust. The Contractor shall provide all necessary dust screens to prevent dust from the construction works affecting neighbouring property. The dust screens shall be approved by the Project Ma and be acceptable to NEMA officials. The Contractor shall also control dust on site by appropriate watering of the sources of dust.	
	The Contractor shall put emphasis on controlling noise, vibrations and occupational hazards. The provisions of the Occupational Safety and Health Act No. 15 of 2007 must be strictly observed.	
D	CONTRACTORS' SUPERINTENDENCE	
	The Contractor shall constantly keep on the Works a literate English-speaking Agent or Representative, competent and experienced in the kind of work involved, who shall give his whole time to the superintendence of the Works. Such Agent or Representative shall receive on behalf of the Contractor, directions and instructions from the Project Manager and such directions and instructions shall be deemed given to the Contractor in accordance with the conditions of the Contract. The Agent shall not be replaced without the specific approval of the Project Manager.	
	It is to be a specific condition of this Contract that the successful Tenderer shall provide on Site throughout the period of construction until the Date for Practical completion a suitably qualified, experienced and competent person to ensure that the works are carried out to the standard required by the specification and detailed on the Drawings; and shall ensure that upon any termination of employment a suitable replacement is found.	
	Preliminaries Carried to collection KShs.	
		L

		Shs.
	CONTRACTORS' SUPERINTENDENCE -(CONTINUED)	
	Before the Tenderer's offer is accepted the Project Manager may personally interview the Contractor's proposed Representative.	
	A curriculum vitae of past experience and qualifications must be provided for the Project Manager's scrutiny.	
	The Project Manager's decision will be final regarding the suitability of the proposed Representative.	
А	WATER	
	All water shall be fresh, clean and pure, free from earthy, vegetable or organic mater, acid or alkaline substances in solution or suspension	
	The Contractor shall provide at his own risk and cost all water for use in connection with the Works (including the work of Sub-Contractors). The Contractor shall provide at his own expense all temporary distribution pipes, storage tanks, metres, etc., and he shall clear away same upon completion of the Works.	
в	LIGHTING AND POWER	
	The Contractor shall provide at his own risk and cost all artificial lighting and power for use on the Works, including all Sub-Contractors' and Specialists' requirements and including all temporary connections, wiring, fittings, etc., and clearing away on completion. The Contractor shall pay all fees and obtain all permits in connection therewith.	
С	<u>SAFETY</u>	
	The Contractor shall comply at all times with the requirements of the Factory Act (Cap 514), Building Construction Rules, Supplement 18, Legal Notice No.40 dated April, 1984 and ensure that the safety of his workpeople and authorised visitors to the Site is protected at all times. In particular there shall be proper provision of planked footways and guard-rails to scaffolding, etc., protection against falling materials and tools and the Site shall be tidy and clear of dangerous rubbish.	
	The Contractor shall appoint a safety officer as required by the Factory Act and notify the Factory Inspector of his name. the safety Officer shall be on Site at all times and all directions given by the Project Manager to the Safety Officer shall be deemed to be Project Manager's Instructions, and shall be complied with promptly without additional cost to the contract.	
	The Project Manager shall be empowered to suspend work on the Site should he consider these conditions are not being observed, and no claim arising from such suspension will be allowed.	
	Preliminaries Carried to collection KShs.	

		Shs.
А	PROTECTIVE CLOTHING	
	The Contractor shall provide all protective or any other special clothing	
	or equipment for his employees that may be necessary.	
	This shall include, inter-alia, safety helmets, gloves, goggles, earmuffs,	
	gumboots, overalls, etc., according to the type of work. The Contractor shall	
	ensure that safety helmets are worn by all staff at all times.	
	, ,	
В	PROVISIONAL SUMS	
	The term "Provisional Sum" wherever used in these Bills of Quantities shall	
	have the meaning stated in Section A Item A6(i) of the Standard Method of	
	measurements Such sums are net and no addition shall be made to them for profit.	
	Such sums are net and no addition shall be made to them for profit.	
С	ADJUSTMENT OF PROVISIONAL SUMS	
	In the final account all provisional sums shall be deducted and the value of the	
	work properly executed in respect of them upon the Project Manager's order added	
	to the contract sum. Such work shall be valued as described for variations in	
	condition No. 30 of the conditions of contract, but should any articles for the	
	work be executed by a Nominated Sub-Contractor, or any articles for the work be supplied by a Nominated Supplier, the Value of such work or articles shall	
	be treated as a P.C. sum and profit and attendance comparable to that	
	contained in the priced Bills of Quantities for similar items added.	
D	PRIME COST (OR P.C.) SUMS	
	The term "Prime Cost Sum" or "P.C. Sum" wherever used in these Bills of	
	Quantities shall have the meaning stated in Section A item A67(ii) of the Standard Method of Measurements	
	Persons or firms Nominated to execute the work or to provide and fix materials	
	or goods as stated in the Conditions of Contract are	
	described herein as Nominated Sub-Contractors. Persons or firms so	
	nominated to supply goods or materials are described as Nominated suppliers.	
E	ADJUSTMENT OF P.C. SUMS	
	In the final account all P.C. sums shall be deducted and the amount properly expended upon the Project Manager's order in respect of each of them added to the	
	contract sum. The Contractor shall produce to the Project Manager such quotation,	
	invoices or bills properly receipted as may be necessary to show the actual	
	details of the sums paid by the contractor.	
	Items of profit upon P.C. sums shall be adjusted in the final account prorata	
	to the amount paid.	
	Items of Attendance following P.C. Sums shall be adjusted prorata to the	
	physical extent of the work executed (not prorata to the amount paid) and this shall apply though the Contractor's Bills shows a percentage in the rate column	
	in respect of them.	
	Should the Contractor be permitted to tender and his tender be accepted	
	for any work which a P.C. sum is included in these Bills of Quantities, profit	
	and attendance will be allowed at the same rate as it would if the work were	
	executed by a Nominated Sub-Contractor.	
	Preliminaries Carried to collection. KShs.	

MATERIALS AND WORKMANSHIP

A GENERALLY

All materials shall be new unless otherwise directed or permitted by the Project Manager and in all cases where the quality of goods or materials is not described or otherwise specified, is to be the best quality obtainable in the ordinary meaning of the word "best" and not merely a trade signification of that word.

All materials and workmanship shall, unless otherwise specified or described, conform to the appropriate British Standard Institution specification current at the date of tender.

The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also order materials to be obtained from local sources as early as necessary to ensure that such materials are on Site when required for use in the Works.

The Contractor shall be responsible for and shall replace or make good at his own expense any materials lost or damaged.

The Works throughout shall be executed by skilled workmen well versed in their respective trades.

B REJECTED WORKMANSHIP OR MATERIALS

Any workmanship or materials not complying with the specific requirements or approved samples or which have been damaged, contaminated or have deteriorated, must immediately be removed from the Site and replaced at the Contractor's expense, as required.

C PROPRIETARY MATERIALS

Where proprietary materials are specified herein-after the contractor may propose the use of materials of other manufacture but equal quality for approval by the Project Manager.

All materials and goods, where specified to be obtained from a particular manufacturer or supplier are to be used or fixed strictly in accordance with their instructions.

D SAMPLES

The Contractor shall furnish at the earliest possible opportunity before work commences and at his own cost, any samples of materials or workmanship that may be called for by the Project Manager for his approval or rejection, and any further samples in case of rejection until such samples are approved by the Project Manager and such samples, when approved, shall be the minimum standard for the work to which they apply.

Carried to collection

P/8

Shs.

Shs.

A CONCRETE TESTS

Concrete test cubes, will not be required under these works; any concrete works Must be done in the presence of the Project Manager or his/her representative

B OTHER MATERIAL TESTS

The Contractor shall allow for providing samples of all other materials such as reinforcement bars, building sand, cement, building stone, concrete blocks, hardcore, etc, that may be requested by the Project Manager or Engineer for testing. He shall allow for the delivery of the same to the testing Laboratory(ies)), pay the testing fees and any other costs that may be required and arrange for test certificates to be sent directly to the Project Manager or Engineer by the testing Laboratory. Under no circumstances will the Contractor be paid for such tests if he does not allow for that here

Preliminaries	Carried to collection	KShs.	

Shs. **TEMPORARY WORKS** А **OFFICE AND SHEDS** The Contractor shall erect and maintain temporary office accommodation for his own use, and ample temporary watertight sheds for the proper storage and protection of materials and for the use of artisans and remove when ordered. Floors of sheds shall be at least 150mm above ground level. В **SANITATION** The Contractor shall provide the necessary latrines for his staff and workmen to the requirements and satisfaction of the Health Authorities and maintain the same in a thoroughly clean and sanitary condition and pay all conservancy fees during the period of the Works and remove when no longer required.

		Shs.
А	PLANT, TOOLS AND SCAFFOLDING	
	The Contractor shall provide all necessary hoists, tackle, plant, vehicles, tools and appliances of every description for the due and satisfactory completion of the Works and shall remove same on completion.	
	The Contractor shall provide, erect and maintain all temporary scaffolding, sufficiently strong and efficient for the due performance of the Works, including Sub-Contract works, provide special scaffolding as and when required during the Works and remove on completion and make good.	
	Such scaffolding shall be constructed of tubular steel or timber of sufficient scantlings and be provided with planked footways and guard-rails to approval.	
	All such plant, tools and scaffolding shall comply with all regulations whether general or local, in force throughout the period of the contract and shall be altered or adapted during the Contract as may be necessary to comply with any amendments in or additions to such regulations.	
	Scaffolding is not measured hereinafter, and the Contractor must allow here or in his rates for the above.	
в	EXISTING AND ADJACENT PROPERTY	
	The Contractor must take all steps necessary to safeguard existing and adjacent property, make good at his own expense any damage to persons or property caused thereon, and hold the Employer indemnified against any such claim arising.	
	The Contractor will be held fully responsible for the safety of the existing and adjacent buildings and for any damage caused in consequence of these Works. He must reinstate all damage at his own expense and indemnify the Employer against any loss.	
	The Contractor must take such steps and exercise such care and diligence as to minimise nuisance from dust, noise or any other cause to the occupiers of the existing and adjacent property.	
С	LABOUR CAMPS	
	No labour, with the exception of watchmen may be housed on the site and the Contractor shall allow for all transport and other charges in moving labour to and from site at such hours and by such routes as are permitted by the Authorities. The Contractor shall provide, erect and maintain satisfactory housing for the watchmen and shall remove same on completion of the works.	
	Preliminaries Carried to collection KShs.	

		Shs.
А	HOARDING	
	The Contractor shall enclose the Site with a hoarding 2.40 metres high, with openings and gates as required, constructed of substantial timbers to approval and covered with new Galvanised iron corrugated sheeting painted to approval.	
в	WATCHING AND LIGHTING	
	The Contractor shall provide at his own risk and cost all watching and lighting as necessary to safeguard the Works, plant and materials against damage and theft.	
С	TEMPORARY ROADS	
	The Contractor shall provide where directed all temporary access roads, tracks and paths necessary for the execution of the Works, including making good when no longer in use.	
D	SIGNBOARD	
	The Signboard and lettering on same for the display of the General and Sub-Contractor's names shall be of an approved size with the Employer's name painted thereon. The Project Manager's name shall be printed in letters not exceeding 100mm in height all to the Project Manager's design. No other signboard or advertising will be permitted.	
	NOMINATED SUB-CONTRACTORS AND SUPPLIERS	
Е	NOMINATED SUB-CONTRACTORS	
	The Contractor shall be responsible for Nominated Sub-Contractors in every respect and in particular it shall be the Contractor's responsibility to ensure that each Sub-Contractor commences and completes the work in such manner and is ready on the Site with his materials, labour and special plant at such times so as to conform with the progress Schedule, as specified previously, and so ensure satisfactory progress.	
	The Contractor shall also accept liability for and bear the cost of General Attendance on Nominated Sub-Contractors which shall be deemed to include for:	
	Preliminaries Carried to collection KShs.	

		Shs.
	NOMINATED SUB-CONTRACTORS - CONTINUED	
	Allowing the use of standing scaffolding, maintenance and alteration of all scaffolding, retention of all scaffolding until such time as all relevant Sub- Contractors' works are complete and removal of all scaffolding on completion. Providing space for office accommodation, and for storage of plant and materials; allowing use of sanitary accommodation; the supply of all necessary water, and lighting; and clearing away all rubbish.	
	The items for "General Attendance" given herein-after following P.C. Sums in respect of Sub-Contractors' work shall be deemed to include all the above.	
	The Contractor shall also accept liability for and bear the cost of Special Attendance on Nominated Sub-Contractors which shall include for one or more of the following:	
	Unloading, storing, hoisting, placing in position, providing power, provision of special scaffolding.	
	The items of "Special Attendance" given herein-after following P.C. Sums shall include any one or more of the above items as set out in the particular reference.	
	Cutting away for and making good after the work of Sub-Contractors as may be required will be measured and valued separately by the Surveyor.	
А	NOMINATED SUPPLIERS	
	The cost of "Fix only" materials to be obtained from Nominated Suppliers which are covered by prime Cost or Provisional Sums shall include for taking delivery where directed, checking with invoices or indents, reporting and claiming damages for shortages and damaged goods, defraying demurrage signing for as having been received in good order, transporting, unloading, storing, covering and protecting until the time of fixing, unpacking, replacing anything lost or damaged, sorting, assembling, hoisting to required levels and fixing as described.	
	Before placing any orders with Nominated Sub-Contractors or Nominated Suppliers the Contractors must ascertain that the terms and conditions of the quotations and the dates of delivery of materials or execution of works comply with the terms of Contract and the Progress Schedule.	
в	PRIME COST RATES	
	Where description of items include a P.C. rate per unit this rate is to cover the nett supply of the unit only. The Contractor's price must include for the cost of the unit at the rate stated, plus waste, taking delivery, storage, fixing in position, profit and overheads.	
	The actual nett cost per unit will be adjusted within the Final Account against the P.C. rate stated.	
	Preliminaries Carried to collection KShs.	

		Shs.
^	PROTECTION	
A	PROTECTION	
	The Contractor shall cover up and protect from damage, including damage from inclement weather, all finished work and unfixed materials, including that of Sub-Contractors, etc., to the satisfaction of the Project Manager until the completion of the Contract, and carefully preserve all trees or bushes on or near the Site.	
В	CLEANING	
	The Contractor shall, upon completing of the Works, at his own expense, remove and clear away all surplus excavated materials, plant, rubbish and unused materials and shall leave the whole of the Site and Works in a clean and tidy state to the satisfaction of the Project Manager, including clearing away and making good all traces of temporary access roads, offices, sheds camps, etc. Particular care shall be taken to leave clean all floors and windows and to remove all rubbish and dirt as it accumulates. The Contractor is to find his own dump and shall pay all charges in connection therewith.	
С	TRAINING LEVY	
	The Contractor's attention is drawn to legal Notice No. 237 of October, 1971, which requires payment by the Contractor of Training Levy on all Contracts of more that 50,000/- in value and his Tender must include for all costs arising therefrom.	
D	STANDARD LEVY (STANDARDS ACT- CAP 496)	
	The Contractor's attention is drawn to legal Notice No. 267 of 2 nd June,1990 which requires payment by the Contractor of the Standards Levy at a rate of 0.2% of the contract sum less allocation for prime cost sums and provisional sums, subject to a ceiling of KShs. 200,000.00 per annum. The Contractor must therefore include for all costs (if any) arising or resulting therefrom.	
E	VALUE ADDED TAX	
	The Contractor's attention is drawn to the Finance Act 1993 and subsequent ammendments thereof which requires payment by the Contractor of Value Added Tax (VAT) on construction services rendered.	
	Preliminaries Carried to collection KShs.	

COLLECTION

From	page	No.	P/1
"	"	"	P/2
"	"	"	P/3
"	"	"	P/4
"	"	"	P/5
"	"	"	P/6
"	"	II	P/7
"	"	II	P/8
"	"	"	P/9
"	"	"	P/10
"	"	"	P/11
"	"	"	P/12
"	"	"	P/13
"	"	"	P/14

TO GRAND SUMMARY AT END OF BILLS

PRELIMINARIES

KSHS.

Preliminaries

OFFICE BLOCK

BUILDER'S WORKS

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>OFFICE BLOCK</u>				
	<u>ELEMENT NO. 1</u>				
	SUBSTRUCTURES (ALL PROVISIONAL)				
А	<u>Site clearance</u> Clear site of medium size aggregates, small bushes and grub roots of small trees and cart away	712	sm		
	Excavation Over-site excavations: 100-200mm Depth, load and deposit as instructed by the project manager				
В	Reducing levels; 200 mm	712	sm		
С	Excavate for strip footing trenches n.e. 1.5 m deep	160	cm		
D	Ditto; column bases ditto	152	cm		
E	Extra-over all excavation for excavating rock irrespective of class.	62	cm		
F	Level bottom of foundations to receive blinding	102	sm		
G	Return, fill-in and rum selected imported materials around foundations	237	cm		
Н	Remove and cart away surplus excavated materials.	75	cm		
Ι	<u>Diposal of water</u> Keeping all excavations free from all water including spring or running water		Item		
J	<u>Planking and strutting</u> Uphold the sides of all excavations		Item		
К	<u>Filling</u> Hardcore filling in making up levels, hand packed, 300mm thick in layers of 150mm maximum thickness	121	cm		
L	50mm (average) thick quarry dust blinding to surfaces of hardcore	402	sm		
	Carried to Collection	1	I	I	

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>Antitermite treatment</u> Premise 200 SC' or other equal and approved anti-termite insecticide treatment with ten years guarantee, applied strictly in accordance with manufacturer's instructions, to tops of fill and foundation walls	402	sm		
	Concrete				
	Plain concrete (1:3:6) in : -				
В	50mm Blinding to foundations	124	sm		
	Insitu concrete; reinforced; class 20 / (20mm); 1:2:4; vibrated				
С	Strip footing	21	cm		
D	Column bases	3	cm		
Е	Vertical columns	1	cm		
F	150mm thick bed	402	sm		
	Reinforcement				
	Bars; high yield steel; cold worked to B.S. 4461 and hot rolled to B.S. 4449 including bends, hooks, tying wire and distance blocks				
G	In assorted reinforcement of diameters 8,10 & 12)	2781	kg		
	<u>Fabric; B.S. 4483</u>				
Н	Reference A142 mesh 200 x 200 mm , weight 2.22 kgs per square meter (measured net - no allowance made for laps(inclunding bends, tying wire and distance blocks	402	sm		
	Walling				
Ι	200 mm thick natural stone foundation walling bedded in c/s mortar	220	sm		
	Sawn formwork to insitu concrete as described:-				
J	To sides; vertical or battering of foundations, ground beams or the like	60	sm		
	Carried to Collection	1	<u>l</u>	1	

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
А	Column bases	29	sm		
В	Vertical columns	15	sm		
С	Edges of ground floor slab; 75 to 150mm wide	106	lm		
D	Damp proofing Polythene sheet; 1000 gauge, 200mm welted laps (no allowance made to laps), horizontal; 1 no. layer laid on compacted quarry dust blinding	402	sm		
	200mm wide; B.S. 743 Type A bitumen hessian base 150 mm laps (no allowance made for laps); horizontal, 1 no. layer, bedded in cement sand (1:3) mortar	284	lm		
	Insitu Finishings				
F	14mm thick 2 No. coatwork cement sand (1:3) render; wood floated to concrete or blockwork base to walls;	48	sm		
	Painting and Decorations				
	Prepare and apply three coats bituminous paint to:				
G	Wood floated rendered plinths over 300mm girth	48	sm		
	Precast concrete				
Н	600x600x50mm thick precast concrete slabs laid on compacted murram bed; to fall	132	sm		
	Carried to Collection				
	COLLECTION				
	From page BW/2				
	From page BW/3				
	From page above				
	TOTAL FOR SUBSTRUCTURES CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	ELEMENT NO. 2				
	RC SUPERSTRUCTURE				
	Insitu concrete; reinforced; class 20 / (20mm); vibrated:				
А	Beams	15	cm		
В	Vertical columns	2	cm		
	Reinforcement				
	Bars; high yield steel; cold worked to B.S. 4461 and hot rolled to B.S. 4449 including bends, hooks, tying wire and distance blocks				
С	In assorted reinforcement of diameters (8,10 & 12)	1798	kg		
	Sawn formwork to insitu concrete as described:-				
D	To sides and soffits of ring beam	167	sm		
Е	To side of columns; circular	30	sm		
	TOTAL FOR RC SUPERSTRUCTURE CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	ELEMENT NO. 3				
	WALLING				
	Precast concrete grade 20(12mm aggregate) including				
	formwork, finishing fair on all exposed surfaces and				
	hoisting and placing in position, bedding, jointing and				
	pointing in cement and sand (1:3) mortar				
Α	100 x 200 mm Lintel reinforced with and including two				
	12mm diameter mild steel rods hooked at ends (in 2 No.)	9	lm		
В	WINDOW CILL; 250 x 50 mm extreme height; once				
	weathered; once throated; reinforced as necessary for				
	handling; surface fair finish 275 mm girth; bedding,				
	jointing and pointing in cement sand (1:3) mortar	35	lm		
	NATURAL STONE WALLING				
С	200 mm thick approved local; chisel dressed both sides;				
Ũ	bedding, jointing and pointing in cement sand (1:3)				
	mortar; External	230	sm		
D	Ditto; reinforced with hoop iron at every course; ditto;				
	Internal	138	sm		
E	Ditto; but precast concrete vent block walling; reinforced				
	with and including hoop iron in alternate course with and				
	including mosquito gauze	15	sm		
Б	Extra over 200mm thick external walling for pointing in				
F	10mm thick recessed horizontal and flush vertical pointing in				
	in cement and sand (1:3) mortar; one coat of bituminous				
	paint.	223	sm		
	1				
G	150mm thick glass blocks laid in glass adhesives including				
	all necessary accessories; all to approval	18	sm		
	TOTAL EOD WALLING CADDIED TO SUNANAADY				
	TOTAL FOR WALLING CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	ELEMENT NO. 4				
	ROOFING CONSTRUCTION, COVERING AND RAIN				
	WATER DISPOSAL (Provisional)				
	Roof covering.				
	Galvanized steel IT5 box profile sheets; 26 gauge;				
	prepainted				
А	Roof covering; 150mm laps on one end and one and a half				
	corrugation side lap; and nailing to $75x50 \text{ mm}$ celcured				
	sawn cypress purlins (m/s) on timber trusses (m/s) at 1200mm c/c all laid to fall at 22.5 ⁰	588	sm		
		500	5111		
	Accessories, fixing as necessary to roof sheets				
В	150mm dia. Half round ridge sheet	61	lm		
C	Ditto, his short	10	1		
C	Ditto; hip sheet	10	lm		
D	600mm wide; valley sheet	25	lm		
	CARPENTRY				
	The following in sawn celcured cypress timber trusses,				
	bolted connections, to detail; hoisting approx. 3.5m above				
	ground				
Е	150 x 50mm rafters	392	lm		
F	150 x 50mm ceiling joist	336	lm		
1		550			
G	100 x 50mm struts and ties	382	lm		
Н	100 x 50mm king post	36	lm		
Ι	The following in sawn celcured cypress non framed timber 150 x 50mm wall plate rag-bolted at 1200mm centres with				
1	12mm diameter bolts (m/s)	125	lm		
т	200 x 50mm ridge board	<u> </u> 21	1		
J	200 x 50mm ridge board	61	lm		
Κ	150 x 50mm common rafters	392	lm		
L	Ditto; hip & valley rafters	35	lm		
М	75 x 50mm purlins	640	lm		
	Carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	The following in wrot cypress				
А	200 x 25mm thick facsia & barge boards	72	lm		
В	Approved t&g timber boarding; secret fixed to and including 50 x 50mm celcured wrot cypress bearers or brandering at 600mm centres	43	sm		
	Labour and material (Provisional)				
	12mm diameter rag bolt, 200mm long complete with and including head, nut and two washers; cast into and including mortice in stone or concrete and run with cement and sand (1:3) mortar	104	No		
D	Drill 50mm thick timber to receive 12mm dia. Bolt (m/s)	104	No.		
	RAINWATER DISPOSAL				
	24g Galvanised mild steel sheeting; all welds ground smooth				
Е	100 x 75mm box gutter including soldered joints in the running length fixed to fascia board with and including brackets at approved centers	42	LM		
F	Extra; for blocked ends with 75mm dia.outlet 100mm long	6	No		
G	Extra; for 75mm dia.outlet 100mm long	4	No		
Н	75mm dia. rainwater downpipe fixed with and including mild steel straps at 900mm centres, plugged and screwed to wall	33	LM		
Ι	Extra; swanneck bend with 1135mm projection	10	No		
J	Extra; horse shoe bend	10	No		
	Carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS	
	Painting and Decorations					
	<u>On Woodwork</u>					
	<u>Prepare and apply one zinc plumbate primer and three coats</u> of 'CROWN SOLO' or other equal and approved super gloss oil paint to:-					
А	Fascias and barge boards; 200 to 300mm girth; external	72	LM			
	<u>On Metal work</u>					
В	General surfaces; over 300mm girth external	12	SM			
С	Small pipes; external	33	LM			
	Total carried to collection					
	COLLECTION					
	From page BW/7					
	From page BW/8					
	From page Above					
	TOTAL FOR ROOFING CONSTRUCTION, COVERING AND RAIN WATER DISPOSALCARRIED TO	1				
	AND KAIN WATER DISPOSALCARRIED TO					

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	ELEMENT NO. 5				
	DOORS				
	DOORS Metal Doors				
	Supply, assemble and fix the following heavy gauge mild steel				
	panel doors, primed before fixing complete with heavy duty steel				
	hinges, handles, locking devices and other necessary fittings fixed to opening including fixing framing to concrete or masonry,				
	making good disturbed surfaces, all to architects detail drawing.	1			
А	Door size 2800 x 2400mm high in two equal opennable leaves				
		1	No.		
В	Door size 900 x 2400mm high	2	No.		
С	Supply, assemble and fix mild steel grill door size 1200 x				
	2400mm high comprising of 30 x 30 x 2mm thick SHS framing,				
	and infill members: all to detail	1	No.		
			110.		
	Wrot hardwood framed frames and framings				
D	200 x 38 mm; 4 No. labours; plugged door frame	65	lm		
Е	100 x 38mm architraves with 4 No. labours	65	lm		
Ľ	100 x Somm architraves with 4 No. labours	05	1111		
F	38 x 38mm quadrants with 3 No. labours	65	lm		
	1				
	50mm thick mahogany pannelled, single-leave, single				
	swing comprising 150 x 50mm top rail, 150 x 50mm stiles,				
	150 x 50mm middle rails, 200 x 50mm bottom rail infilled				
	with 50mm thick solid moulded timber panels in 5 No. per				
	leave with moulded beading around panels; edges bevelled and grooved into frames; all framed, clamped and grooved				
	together.				
	<u></u>				
G	Double door; overall size 1200 x2400 mm high	1	No.		
	45mm Thick semi-solid core flush doors to B.S 459: part 2				
	veneered both sides with internal Quality mahogany veneer	-			
	and lipped on all edges in approved hardwood including				
	glazed fanlight				
Н	Door size 900 x 2100 mm high	6	No.		
Ι	Door size 800 x 2050 mm high	4	No.		
	Carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	Iron mongery				
	Supply and fix the following to UNION catalogue or other equal and approved				
	To softwood, hardwood or the like fixing with screws				
Α	Five lever mortice lock complete with set lever brass handle furniture	1	No.		
В	Two lever ditto	10	No.		
С	100mm steel butt hinges	36	prs		
D	Door closer as union ref 8850 or other equal and approved	1	No.		
	Door iron mongery cont'd				
	To concrete or blockwork; fixing with bolts; plugging				
Е	Rubber door stop complete with 38 mm rawl bolt	15	No.		
	Painting and Decorations				
	<u>On wood</u>				
	Aluminium primer or other equal and approved wood primer before fixing: -				
F	Backs of frame, board, etc over 100mm but not exceeding 200mm girth	130	lm		
	Prepare and apply high quality clear varnish to				
G	General surfaces of timber doors over 300mm girth;	58	sm		
Н	Frames; over 100mm but not exceeding 200mm girth;	130	lm		
Ι	Frames not exceeding 100mm girth; internal	65	lm		
	Carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>COLLECTION</u>				
	From page BW / 10				
	From above				
	TOTAL FOR DOODS CARDIED TO SUNAMARY	1	1	L	
	TOTAL FOR DOORS CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	ELEMENT NO. 6				
	WINDOWS				
	Bull-nosed burnt clay, finishing fair on all exposed surfaces				
	and hoisting and placing in position, bedding, jointing and				
	pointing in pigmented cement and sand (1:3) mortar				
А	150 x 25mm thick clay window sill	35	lm		
В	6mm thick ceramic tiles finish to internal surfaces of window sills; 150mm girth	3	lm		
	Wrot Cypress				
С	150 x 25 mm thick window boards including bull-nosed edges and 25 x 25 mm bearer; plugged, counter sinking and flush pelleting.	35	lm		
	Pelmet box				
D	Comprising 150 x 25mm wide fascia, 2 No. 150 x 25mm ends 100mm long; 100 x 25mm blockboard top; and 50 x 25mm wrot cypress bearer; plugged	35	lm		
	Curtain Tracks;				
Ε	"Silent Gliss" Stardand I-section light duty brass single curtain track screwed to soffits of timber pelmet top (m/s) with brass plated screws, one bracket runner per 75mm of rail, two end stops per length and complete accessories to	35	lm		
	<u>METAL WORK</u> <u>PURPOSE - MADE UNITS</u>				
	Supply, assemble and fix the following purpose-made mild steel casement windows; standard metal section from approved manufacturer complete with frames, transomes, mullions and with and including permanent ventilators comprising "T" bar, gauze and 16 gauge sheet metal hood 50mm high x 50mm projection to full width of window, coupling mullions, approved ironmongery and one coat manufacturer's primer; all welding ground to smooth finish.				
	Steel; for glazing with putty, lugs to two jambs, cutting and pinning to concrete or blockwork, fixing to head and sill with screws; plugging				
	Carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	Metal work cont'd				
А	Ditto size 1200 x 1800 mm high with openable lights to detail	17	No		
В	Ditto size 750 x 800 mm high ditto	4	No		
6	<u>Grills</u> <u>High tensile steel burglar proof bars at 300mm cross</u> centres horizontal and vertical; ends lugged in masonry;				
С	25x25mm square tubes welded and ground smooth to approval.	40	sm		
D	<u>Glazing</u> 4mm Thick clear sheet glass panes over 0.1 but not exceeding 0.5 square meters; fixing with putty	40	sm		
	Painting and Decorations				
	On Metal work Prepare and apply three coats oil paint full gloss to Crown Solo or other equal and approved to: -				
Е	General window surfaces; over 300mm girth	40	sm		
F	Surfaces of metal over 300mm girth (burglar proofing	40	sm		
G	<u>On wood</u> <u>Aluminium primer or other equal and approved wood</u> <u>primer before fixing: -</u> Backs of frame, board, etc over 200mm but not exceeding 300mm girth	35	lm		
	Prepare and apply three coats polyurethane clear varnish on woodwork internally				
Н	Frames; 200 to 300mm girth	35	lm		
	Carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>COLLECTION</u>				
	From page BW / 13				
	From page BW / 14				
	TOTAL FOR WINDOWS CARRIED TO SUMMARY	•			
<u> </u>					

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	ELEMENT NO. 7				
	FINISHES				
	Wall finishes				
	<u>Insitu finishes</u>				
	Render; 15mm thick, 1 No. coatwork of cement and sand (1:3); wood floated to concrete or blockwork base generally to: -				
А	Beams and walls; external	148	sm		
	Plaster; 18mm thick, 2 No. coatwork, 15mm first coat of cement sand (1:3); 3mm second coat of cement and lime putty (1:9); steel trowelled to concrete or blockwork base generally to: -				
В	Walls, beams; internal	714	sm		
	Tile, Slab or Block Finishings				
	Approved ceramic tiles to B.S. 1281; local; white glazed wall tiles to regular or approved other pattern; bedding and jointing in cement sand (1:4) mortar, grouting with white cement				
С	330x 250 x 6mm thick; butt joints straight both ways; to cement sand base (m/s) to walls internal	72	sm		
D	Plastic edging (Provisional)	46	lm		
	Beds or Backings				
Е	Render; cement and sand (1:3) 12mm thick one coat backings; wood floated to receive ceramic tiles (m/s) to concrete or blockwork base; to walls internal	72	sm		
	Painting and decorations				
	Prepare and apply one undercoat and three coats of first quality silk vinyl paint to: -				
F	Plastered surfaces	862	sm		
	Carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>Floor finishes</u>				
	Terrazo with approved coloured aggegates.				
А	40mm thick terrazo floor finish coloured and polished to approval with plastic dividing strips (m/s) forming an approved pattern with and including screed backing.	29	sm		
В	100mm wide skirting; rounded junction with wall finish, coved junction with floor finish.	8	lm		
С	PROVISIONAL: 25 x 3mm plastic dividing strips cut to lengths and set vertically to screed to form margins	32	lm		
	<u>Tile Finishings</u>				
	Approved granito tiles; non slip floor tiles to regular or other approved pattern; bedding and jointing in cement sand (1:4) mortar; grouting with matching cement				
D	600 x 300 x 10mm thick; butt joints both ways; to cement sand base (m/s); to floors level; internal	373	sm		
Е	100 mm thick skirting; straight junction with wall and floor finish.	229	lm		
F	Backings 28mm thick one coat backings; wood floated to receive ceramic tiles (m/s) to concrete or blockwork base; to floors level; internal	373	sm		
	Carried to Collection	<u> </u>			

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>Ceiling finishes</u>				
	Cornice				
A	Moulded cornice; or any other equal and approved cornice	251	lm		
		231			
	<u>Ceiling finishes cont'd</u>				
	Approved sawn softwood; second grade; pressure				
	impregnated.				
В	50 x 50mm brandering	742	lm		
C	50 - 50 mm ditter rivered	710	1		
C	50 x 50mm ditto; plugged	710	lm		
	Softboard; chipboard				
D	12mm thick V-jointed chipboard ceillings secretly nailed to				
	brandering; all to approval	373	sm		
	<u>T&G timber boarding</u>				
-		•			
E	T&G timber boarding to brandering to approval	29	sm		
	Painting and decorations				
	Prepare and apply one undercoat and three coats of first				
	quality plastic emulsion paint to: -				
F	Softboard ceilling surfaces	373	sm		
-		575	5111		
	Knot, prime, prepare and apply two coats of polyurethene clear varnish to "Crown Solo" or equal and approved				
	cical variation crown Solo of equal and approved				
G	T&G surfaces	72	sm		
	Carried to Collection				
	COLLECTION				
	From page BW / 16				
	From page BW / 17				
	From page Above				
	r rom page Audite				
	TOTAL FOR FINISHES CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	ELEMENT NO: 8 FIXTURES AND FITTINGS				
	KITCHEN				
	PLINTH				
А	1:3:6 mass concrete concrete as described in 100mm thick high plinth in kitchen	3	SM		
В	VRC class(20/20)mix 1:2:4 as described in 100mm thick kitchen worktops	3	SM		
С	32mm cement sand (1:4) screed trowelled hard and smooth and finished with cement grout as described in surface finish to surface of plinth	3	SM		
	Granite work tops				
	10mm thick Polished granite slab ground smooth fixed to;				
D	Worktops	3	SM		
Е	Extraover for forming sinks / basin hole	1	NO		
	Medium Density Fibre boards				
	The following in 25mm thick MDF boards, veneered on one side with Mahogany veneer and hardwood lipped on all edges as described				
F	Averaging 1100 mm high x 550mm deep low level kitchen cabinets complete with all necessary framing, ironmongery, doors, and the like	4	LM		
G	Ditto; high level ditto	4	LM		
	TOTAL FIXTURES AND FITTING CARRIED TO SUN	MMAF	RY		

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	SOFT LANDSCAPING				
А	Site Clearance and Excavations Clear the site of all unwanted wastes including existing unwanted plant materials and boulders and excavate oversite commencing from ground level, average 200 mm deep top soil to remove all turf, weeds and any deleterious materials; including carting away all arising wastes, raking and fine levelling of the ground.	300	SM		
В	Application of Manure Supply approved red soil and farm yard manure, mix thoroughly (ratio 4:1) and spread the mixture over all areas to be landscaped; Average depth =150mm.	25	СМ		
С	Allow for application of DPN fertiliser	25	KG		
	INSTALLATION OF GRASS (GRASSING): Supply, plant, water, weed and tend well undermentioned grass species till full establishment (6months). Grass should also be rolled with a light weight roller to even out 'bumpy' areas. This should be carried out one to two weeks after installation				
D	i) Pennisetum clandestinum (Kikuyu grass) sprigs planted at 100 X 100mm.	300	SM		
	INSTALLATION OF GROUNDCOVERS: <u>Pits excavation for Groundcovers</u>				
Е	Excavate circular pits, average 300mm diameter, commencing at existing ground level but not exceeding 0.5 metres depth average 350mm deep.	12	СМ		
	Planting of Groundcovers (Approx.) Supply, plant, weed, water and tend well under-mentioned Assorted species of groundcovers till full establishment;				
	Small Groundcovering Plants				
F	Kalanchoe thrysiflora	50	NO		
G	Sedum ribrotinctum	10	NO		
Н	Euphorbia milli	60	NO		
	Total carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	Planting of Groundcovers (cont'd)				
	Supply, plant, weed, water and tend well under-mentioned				
	Assorted species of groundcovers till full establishment;				
	Small Cusumdasussing Disute				
	Small Groundcovering Plants				
А	Opuntia cactus (Desert cactus)	10	NO		
В	STONE PLANTS (Sedum spp)	5	NO		
	Supply, plant, weed, water and tend well under-mentioned Assorted species of groundcovers till full establishment;				
	Large Groundcovering Plants				
С	Bougainvellia rosenka	150	NO		
D	Pennisetum setaceum (White pennisetum)	10	NO		
Е	Aloe spp	20	NO		
	INSTALLATION OF TREES/LARGE SHRUBS:				
	Pits excavation -				
F	Excavate pits,1000x1000mm, commencing at existing ground level but not exceeding 1.5 metres depth aver. 1000mm deep .	17	СМ		
	Planting of Trees/Large Shrubs				
	Supply, plant ,weed ,water and tend well undermentioned trees/large shrubs till full establishment and support the same with strong bamboo stakes, adequate in thickness for each tree (generally between 30mm and 50mm diameter));			
G	Phoenix robelinii	20	NO		
Н	Thevetia thevetioides	50	NO		
Ι	Callistemon viminalis	50	NO		
J	Arobaini tree spp	50	NO		
	Total carried to Collection				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	OTHER REQUIREMENTS :				
	River washed stone/rocks for Rock Garden				
А	Supply of river washed stones/rocks of varied sizes (between 0.5 to 1.0 Metres) and arrange them to form a rock garden as directed on site by the pm	15	СМ		
	Suppy of Sand for top-dressing lawns				
В	Supply of clean sand for top-dressing of lawns.	7	СМ		
	Top-dressing of lawns				
С	Apply a top-dressing of clean sand to all grassed or lawn areas (depth of 12.5mm) and rake over all lawns to fill any uneven patches. Top-dressing is to be carried out 2 to 3 weeks after installation or after lawns have fully established.	143	SM		
	Total carried to Collection				
	COLLECTION:				
	Brought forward from page BW/20				
	Brought forward from page BW/21				
	Brought forward from above				
	TOTAL FOR LANDSCAPING CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>SUMMARY</u>				
ELEM	ENT NO. TITLE		PAG	E NO.	K.SHS.
1	SUBSTRUCTURE (ALL PROVISIONAL)		BV	N / 4	
2	RC SUPERSTRUCTURE		BV	N / 5	
3	WALLING		BV	W / 6	
4	ROOF CONSTRUCTION		BV	W / 9	
5	DOORS		BW	//12	
6	WINDOWS		BW	/ / 15	
7	FINISHES		BW	//18	
8	FIXTURES AND FITTINGS		BW	/ / 19	
9	LANDSCAPING		BW	//22	
	TOTAL FOR OFFICE BLOCK CARRIED TO GRA	AND S	UMMA	ARY	

PRIME COST SUMS

PRIME COSTS SUMS

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	Allow for the following PRIME COST SUMS for works to be executed by a nominated sub-contractor or as may be directed by the project manager				
	Electrical Installation				
А	Kenya Shillings THREE HUNDRED FIFTY THOUSAND (KShs. 350,000.00) only		ITEM		
	Allow for profits		%		
	Allow for Attendance		ITEM		
В	Plumbing & Internal Drainage & Fire fighting installations Kenya Shillings FOUR HUNDRED THOUSAND (KShs. 400,000.00) only		ITEM		
	Allow for profits		%		
	Allow for Attendance		ITEM		
С	Air conditioning & Mechanical Ventilation Kenya Shillings FOUR HUNDRED FIFTY THOUSAND (KShs.450,000.00) only		ITEM		
	Allow for profits		%		
	Allow for Attendance		ITEM		
	Total P.C sums carried to Grand Summary				

GRAND SUMMARY

PROPOSED CONSTRUCTION OF AN OFFICE BLOCK AT LODWAR GENERATION STATION - TURKANA COUNTY

GRAND SUMMARY

	r	-				
BILL	DESCRIPTION	Page No.		OR'S OFFICIAL USE		
NO.			USE			
			K.SHS.	CTS.	K.SHS.	CTS.
1	Preliminaries	P/15				
2	BUILDER'S WORKS	BW / 23				
3	P.C. & Provisional Sums	PC / 2				
	SUB-TOTAL 1					
	Add: VAT 16%					
	GRAND TOTAL CARRIED TO FORM OF TENDER (KSh)	K.SHS.				
<u>Amoι</u>	<u>ınt in words:</u> Kenya Shillings					
	Contractors Name, Address					
	Contractors Stamp, Sign & Date					
	Witness Name, Address & Date					