

PROPOSED CURTAIN, SHEERS AND PELMETS FOR EXECUTIVE FLOOR 7TH FLOOR - STIMA PLAZA.						
Item	Description	Qty	Unit	Rate	Amount	
					Ksh	Cts
1	<b><u>Demolition</u></b>					
A	Carefully remove existing curtains and sheers and handover to the client.	ITEM	ITEM			
B	Carefully remove existing pelmet boxes complete with their fabric and set aside for re-use.	ITEM	ITEM			
C	Carefully remove existing wall to wall carpet complete with timber skirting and cart away the debris.	450	SM			
D	Supply and fix 1,200mm long 'Silent glass/sliding curtain track complete with gears to all windows.	50	SM			
2	<b><u>Supply and fix heavy duty curtains and sheers of overall depth 2,700mm with 150% gathers complete with linings and tape as per provided sample with all necessary accessories all to client's approval.</u></b>					
	<b>PHASE 2</b>					
E	Executive Meeting room					
	i) (3,950 x 1,780mm)	2	SM			
	ii) (1,000 x 1,450mm)	2	SM			
F	Company Secretary Office					
	i) (3,920 x 1,630mm)	6	SM			
G	Customer Relations					
	i) (3,011 x 1,630mm)	2	SM			
H	Kitchen/Drivers					
	i) (800 x 1,630mm)	2	SM			
	ii) ( 1,000 x 1,430mm)	4	SM			
J	Executive Library					
	i) (3,920 x 1,780mm)	2	SM			
	ii) ( 1,000 x 1,600mm)	2	SM			
K	Project Mwangaza					
	i) (1,880 x 1,790mm)	2	SM			
L	Former Don's Office					
	i) (3,910 x 1,780mm)	4	SM			
M	Energy Purchase					
	i) (1,880 x 1,790mm)	2	SM			
N	Tenders Office					
	i) (1,880 x 1,790mm)	2	SM			
P	Main Reception sizes:					
	i)(4,200 x 2,700mm)	4	NO.			
Q	Waiting Room					
	i)(2,360 x 2,700mm)	4	NO.			
R	Supply and fix tiled carpet as provided sample or equal and approved complete with underfelt and all necessary fixing accessories.	450	S.M			
S	Allow for new skirting boards to match existing.	400	L.M			
	<b>TOTAL CARRIED FORWARD</b>					

Copy of Copy of 7TH FLR DECO AND REPAIRS (2) (2)

Item	Description	Qty	Unit	Rate	Amount	
					Ksh	Cts
	<b>Mezzanine Floor to 6th Floor repairs</b>					
A	Remove existing tile carpets along the corridors and cart away the debris.	1,000	S.M			
B	Remove existing damaged 600 x 600 x 8mm thick polished granito floor tiles with skirting and cart away the debris.	100	S.M			
C	Remove existing wall papers and cart away the debris	900	S.M			
D	Removing existing armstrong ceiling panels and cart away	450	S.M			
	<b>New Works - Supply and fix the following to required and approved standards.</b>					
E	600 x 600 x 8mm thick approved polished granito floor tiles to match existing in an approved pattern, bedded in cement slurry and grouting to joints in matching colours.	100	S.M			
F	100mm high by 8mm thick polished granito floor skirting piece to skirting in matching colours.	10	LM			
G	1,200mm wide by 8mm thick first quality carpet ( as per sample) secured with aluminium strips or any other approved method	1,000	S.M			
H	Supply and fix new armstrong ceiling panels.	450	S.M			
J	Allow for respraying aluminium branding allowing for extra aluminium materials for branding.	450	S.M			
K	Prepare and apply three coats first quality silk vinyl paint to: Plastered wall	1,000	SM			
L	Prepare and apply three coats first quality vanish matt paint to:- Doors	150	SM			
M	Wall cabinets	100	SM			
N	Allow for a reception counter with one shelf in Company's Secretary office overall size 5,000 x 900 x 1,200mm with 2 no. half doors with all necessary fitting accessories in mahogany finish 25mm thick boards all to clients approval.	2	NO			
P	Allow a P.C Sum of Ksh.200,000 (Two hundred thousands Shillings only) for services repair, to be expended by clients approval.	200,000	SUM	200,000		
Q	Add for Profit		%			
R	Allow a P.C Sum of Ksh.200,000 (Two hundred thousands Shillings only) for suspended gypsum ceiling with light fittings at the reception, to be expended by clients approval.	200,000	SUM	200,000		
S	Add for Profit		%			
	<b>TOTAL CARRIED FORWARD</b>					
	<b>Carried forward from page 1</b>					
	<b>Carried forward from page above</b>					
	<b>Add 16% VAT</b>					
	<b>TOTAL CARRIED TO FORM OF TENDER</b>					

Amount in words.....

Name of Contractor .....

Contractor's Address .....

Contractor's Representative's Signature .....

Date .....

Witness .....

Address .....

Signature .....

Date .....

