



Kenya Power

*Central Office – P.O. Box 30099, Nairobi, Kenya
Telephone – 254-020-3201000
Fax No. 254-02-310336
Stima Plaza, Kolobot Road
Nairobi, Kenya*

M/s.

6th March, 2017

Dear Sir/Madam

ADDENDUM II FOR TENDER NO. KP1/9AA-2/OT/60-SC/16-17 FOR CONSTRUCTION OF CABLE REWINDING MACHINE SHEDS IN EMBU, RUIRU, NAKURU, ELDORET, KAKAMEGA AND KISUMU

1. RELATIONSHIP WITH THE PRINCIPAL TENDER DOCUMENT

Save where expressly amended by the terms of this Addendum, the Principal Tender Document shall continue to be in full force and effect.

The provisions of this Addendum shall be deemed to have been incorporated in and shall be read as part of the Principal Tender Document.

1. SECTION IX – BILL OF QUANTITIES

Additional bill of quantities for lot 1 and lot 2 has been attached as appendix 1.

The tender closing date has changed from 7th March, 2017 to close on **14th March, 2017** at 10.00am.

All other terms and conditions of the tender remains the same.

Yours faithfully,

For: KENYA POWER & LIGHTING COMPANY LIMITED.

JOYCE OCHIENG

For: GENERAL MANAGER, SUPPLY CHAIN

**ADDENDUM FOR LOT NO. 1
EMBU, NAKURU RUIRU SHEDS**

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	Add the following to Embu, Nakuru, Ruiru Sheds				
	<u>ELEMENT NO. 8</u>				
	<u>SUBSTRUCTURES (ALL PROVISIONAL)</u>				
	<u>Excavation</u>				
	<u>Over-site excavations: 100-200mm Depth, load and cart away.</u>				
A	Reducing levels; 300 mm	102	SM		
	<u>Concrete</u>				
	<u>Concrete: reinforced: class 20 / (20mm); vibrated</u>				
B	200mm thick bed	103	SM		
	<u>FINISHES</u>				
	<u>Wall finishes</u>				
	<u>External wall finishes</u>				
	<u>Plaster: 12mm thick 2 No. coatwork, 9mm first coat of cement sand (1:6); 3mm second coat of cement and lime putty (1:10); steel trowelled to concrete or blockwork base generally to: -</u>				
C	Walls	65	SM		
	<u>Internal wall finishes</u>				
	<u>Plaster: 12mm thick 2 No. coatwork, 9mm first coat of cement sand (1:6); 3mm second coat of cement and lime putty (1:10); steel trowelled to concrete or blockwork base generally to: -</u>				
D	Walls, internal	68	SM		
	<u>Painting and decorations</u>				
	<u>Prepare and apply three coats of silk vinyl paint to the following surfaces</u>				
E	Plastered surfaces; internal	68	SM		
F	Extra over horizontal and vertical pointing in 10mm thick rod in cement and sand (1:3) mortar; one coat of bituminous paint.	65	SM		
TOTAL FOR GUARD HOUSES CARRIED TO GRAND SUMMARY					

THE KENYA POWER & LIGHTING COMPANY, LTD.
Human Resource & Administration Division
BQ APPROVED BY:
SIGNATURE: <i>[Signature]</i>
NAME: <i>Silvanus Wanjau</i>
STAFF No: <i>14788</i>
DESIGNATION: <i>Asst. Eng.</i>
DATE: <i>9/5/2017</i>

LOT NO. 1					
EMBU, NAKURU & RUIRU SHEDS					
GRAND SUMMARY					
BILL NO.	DESCRIPTION	Page No	CONTRACTOR'S USE		OFFICIAL USE
			K.SHS.	CTS.	K.SHS.
1	PRELIMINARIES	P / 15			
2	CABLE REWINDING MACHINE SHED	PW / 8			
	ADD 16% VAT)				
	TOTAL TENDER FIGURE				

Amount in words:

THE KENYA POWER & LIGHTING COMPANY, LTD.
Human Resource & Administration Division
BQ APPROVED BY:
SIGNATURE:..... <i>[Signature]</i>
NAME:..... <i>Stamen WSK</i>
STAFF No:..... <i>14788</i>
DESIGNATION:..... <i>Asst. Secy</i>
DATE:..... <i>2/3/2017</i>

ADDENDUM FOR
LOT NO. 2
ELDORET, KISUMU KAKAMEGA SHEDS

ITEM	DESCRIPTION	QTY	UNIT	RATE	K.SHS
	<u>Add the following to Eldoret, kisumu & kakamega Sheds</u>				
	<u>ELEMENT NO. 8</u>				
	<u>SUBSTRUCTURES (ALL PROVISIONAL)</u>				
	<u>Excavation</u>				
	<u>Over-site excavations: 100-200mm Depth. load and cart away</u>				
A	Reducing levels; 300 mm	102	SM		
	<u>Concrete</u>				
	<u>Concrete: reinforced: class 20 / (20mm): vibrated</u>				
B	200mm thick bed	103	SM		
	<u>FINISHES</u>				
	<u>Wall finishes</u>				
	<u>External wall finishes</u>				
	<u>Plaster: 12mm thick 2 No. coatwork, 9mm first coat of cement sand (1:6): 3mm second coat of cement and lime putty (1:10): steel trowelled to concrete or blockwork base generally to: -</u>				
C	Walls	65	SM		
	<u>Internal wall finishes</u>				
	<u>Plaster; 12mm thick 2 No. coatwork, 9mm first coat of cement sand (1:6): 3mm second coat of cement and lime putty (1:10): steel trowelled to concrete or blockwork base generally to: -</u>				
D	Walls, internal	68	SM		
	<u>Painting and decorations</u>				
	<u>Prepare and apply three coats of silk vinyl paint to the following surfaces</u>				
E	Plastered surfaces; internal	68	SM		
F	Extra over horizontal and vertical pointing in 10mm thick rod in cement and sand (1:3) mortar; one coat of bituminous paint.	65	SM		
TOTAL FOR GUARD HOUSES CARRIED TO GRAND SUMMARY					

THE KENYA POWER & LIGHTING COMPANY. LTD.
Human Resource & Administration Division
BQ APPROVED BY:
SIGNATURE: <i>[Signature]</i>
NAME: <i>Stonny KJR</i>
STAFF No: <i>14788</i>
DESIGNATION: <i>Ag. SPA</i>
DATE: <i>6/3/2017</i>

LOT NO. 2

ELDORET, KISUMU & KAKAMEGA SHEDS

GRAND SUMMARY

BILL NO.	DESCRIPTION	Page No	CONTRACTOR'S USE		OFFICIAL USE
			K.SHS.	CTS.	K.SHS.
1	PRELIMINARIES	P / 15			
2	CABLE REWINDING MACHINE	PW / 8			
	ADD 16% VAT)				
	TOTAL TENDER FIGURE				

Amount in words:

THE KENYA POWER & LIGHTING COMPANY. LTD.
Human Resource & Administration Division
BQ APPROVED BY:
SIGNATURE:..... <i>[Signature]</i>
NAME:..... <i>Salomon Waga</i>
STAFF No:..... <i>14788</i>
DESIGNATION:..... <i>Asst. Mgr.</i>
DATE:..... <i>6/3/17</i>