

**PROPOSED ELECTRICITY HOUSE NAIROBI WINDOWS & DOORS REPLACEMENT**

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Kshs.)
<b>PRELIMINARY</b>					
A	Allow for Nairobi county permit and any other legal requirement ie NEMA for execution of such work	ITEM	ITEM		
B	Ditto but 0.5% NCA fee/charges	SUM	SUM		
C	Allow for all Preliminaries including Scaffolding above 3M and Hoarding where necessary	ITEM	ITEM		
<b>WINDOWS</b>					
D	Carefully remove all the existing windows and handover to client for safe custody	NO	1,454		
<p><b><u>The following in Heavy duty/ gage Natural anodised Aluminium sliding window frames with ironmongery, stationed mosquito mesh vent on top, 6mm reflective glass fitted on the framework and firmly secured with approved rubber gasket.</u></b></p>					
E	<b>1500x1330mm</b> window two top sliding and bottom fixed panels.	NO	14		
F	Ditto but <b>1730x1500mm</b> window	NO	46		
G	Ditto but <b>1500x1200mm</b> window	NO	1,336		
H	<b>1400x900mm</b> window two top hang projecting bottom fixed panels.	NO	36		
J	Ditto <b>600x1400mm</b> one hang projecting panel.	NO	22		
<b>DOORS</b>					
K	Carefully remove frame & doors and handover to client for safe custody	NO	20		
<p><b><u>The following in Heavy duty Natural anodized aluminium doors frames 6mm reflective glass fitted on the framework and firmly secured with approved rubber gasket.</u></b></p>					
L	<b>1800x2500mm</b> high double leaf swing door top panel fixed as per sample	NO	20		
<b>Extra over swing doors for:</b>					
M	3 lever cylinder mortise lock	NO	20		
N	Concealed floor door closer	NO	20		
P	Ditto concealed overhead door closer	NO	20		
Q	Cranked Pull/Push Handle stainless steel, brass polished Finish, 25.4mm (1") Diameter CTC:274.6mm, L: 300mm, Finger Clearance: 45mm, Projection: 70mm, Offset: 100mm	NO	20		
<b>Total carried to collection page</b>					

ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT (Kshs.)
<b>FIRE EXIT DOORS</b>					
A	Carefully remove existing frame & door and handover to client for safe custody	NO	28		
B	Fubracate Supply and fix emergency exit doors complete, with push bar and all acesories. As per sample in electricity 4th floor price to include Auto Magnetic closer	NO	28		
<b>TILLING</b>					
C	Allow for removing and re-fixing all equipments, hand dryer, soap dispensers, notice boards, watches, picture frames as directed by client	ITEM	ITEM		
D	Prepare the wall surface, supply and fix <b>250 x330 x10mm</b> ceramic wall tile, prior to client aproval	SM	1,310		
E	Ditto but to walls of lift lobby and staircase	SM	894		
F	Carefully remove, cart away, prepare and fix affected staire case tiles to match the existing	SM	100		
G	Allow for Making good all surfaces affected during both demolishing and install by plastering ,painting with existing colours & varnish	ITEM	ITEM		
H	Allow a Contingency sum of Kshs. 250,000.00 (Two hundred and fifty thousands) to be expended with client's approval.	SUM	SUM		
<b>Total carried to collection page</b>					

**COLLECTION AREA**

	DESCRIPTION	AMOUNT (Kshs.)
	N/B	
	The bidder must visit the site and ensure his site visit form is stamped before submitting the teder documents	
i	Total Brought forawrd from page 1	
ii	Total Brought forawrd from page 2	
iii	<b>SUM TOTAL</b>	
iv	<b>Add 16% VAT</b>	
v	<b>GRAND TOTAL</b>	

Tender Sum in Words.....

Contract Period..... Weeks.....

Signature.....Official Rubber Stamp.....