

STIMA PLAZA AND STIMA MALL PARTITION WORKS

Item	Description	Qty	Unit	Rate	Amount	
					Ksh	Cts
	ALL PROVISIONAL Demolition Works					
	<i>Demolish existing natural aluminium and double tempered glass partitions complete with all its necessary accessories and set aside for re-use.</i>					
A	General Manager - Business Strategy office	12	SM			
B	Meeting rooms 6th and 3rd floor phase I	30	SM			
C	Mezzanine floor Emergency Office and switchboard	102	SM			
D	Ditto frosted doors ditto	6	NO.			
E	Remove existing top class on all meeting rooms and cart away	30	SM			
	<i>Demolish existing natural aluminium and with strand straw boards partitions complete with all its necessary accessories and handover to the client.</i>					
F	Banking Hall - Stima Plaza	130	SM			
G	Mohagany doors complete with frames and locks	5	NO.			
	NEW WORKS					
	<i>Re-use natural aluminium and double tempered glass partitions complete with all its necessary accessories and allow for extra materials</i>					
H	General Manager - Business Strategy office	12	SM			
J	Meeting rooms 6th and 3rd floor phase I	40	SM			
K	Premier Banking	33	SM			
L	IT & T server room	65	SM			
M	Allow for extra materials	20	SM			
N	Supply and fix double glazed 6mm th. clear toughened glass including all aluminium glazing beads and all necessary anti-vibration leather gaskets to be sound proof all to clients approval	30	SM			
P	Allow for filling the void at the edge with the window with approved timber board and finished good.	8	SM			
Q	Re-use frosted doors and allow for 1 No. three lever approved dead lock with stainless steel facing and 2 No. 600 x 40mm diameter stainless steel handles	6	NO			
R	Allow for adjusting existing frameless doors complete with matching locks with three keys and 10mm aluminium stopper biddings.	22	NO.			
	TOTAL CARRIED TO COLLECTION					



Item	Description	Qty	Unit	Rate	Amount	
					Ksh	Cts
	<u>Supply and fix</u>					
	100mm Thick partition comprising 100 x 50 x 2mm thick natural aluminium framings, vertical ones at approximately 1,200mm centres complete with top and bottom frames; with fixed double glazed 6mm th. clear toughened glass full height glass panel with middle manual blinds including aluminium glazing beads and all necessary anti-vibration leather gaskets, overall height 2,800mm as per existing sample offices.					
A	Stima loan meeting and consultant rooms	65	SM			
	<u>Frameless glass doors</u>					
B	Frameless door in one leaf comprising 10mm thick tampered and frosted glass, 1 No. action floor springs, 1 No. three lever approved dead lock with stainless steel facing and 2 No. 600 x 40mm diameter stainless steel handles, overall size, 900 x 2,100mm high.	2	NO.			
	100mm Thick partition comprising 100 x 50 x 2mm thick natural aluminium framings, vertical ones at approximately 1,200mm centres and three horizontal ones; top panel of 300mm height with openable louvers of 5mm th. toughened clear glass top panel, middle panel filled in with 1400mm panels filled in 5mm thick tinted toughened glass including aluminium glazing beads and bottom panel filled in with 20mm thick double layers of non-scratch veneered MDF upto 1,000mm high from the floor, including aluminium glazing beads and all necessary anti-vibration leather gaskets, overall height 2,700mm.					
C	Banking hall	105	SM			
D	Forensic Audit Lab	19	SM			
E	Mezzanine floor	90	SM			
F	Supply and fix door stopper including screwing to the floor	30	NO.			
G	Allow for push bar fire escape door complete with all necessary accessories	1	NO			
	<u>Aluminium doors</u>					
H	45mm th. aluminium door overall size 900 x 2,100mm complete with 6mm thick frosted toughened glass pane size 900 x 2,100mm to match partition complete with iron mongery, door closer (briton) and cylinder lock as Union (Eng) all to client's satisfaction.	3	NO.			
J	Allow for adjusting existing frameless doors complete with matching locks with three keys and 10mm aluminium stopper biddings.	22	NO.			
	<u>6 and 4 way workstation partitions as per existing samples</u>					
K	6 way workstation aluminium frame screens with 3 no. four way posts overall height 1,200mm and 9 no. fabric panels covering being pinboard overall size 1,500 x 1,200mm complete with all necessary accessories.	50	NO.			
L	4 way ditto 2 no. fourway posts overall height 1,200mm and 6 no. fabric panels covering being pinboard overall size 1,500 x 1,200mm complete with all necessary accessories.	40	NO.			
M	Allow to supply four way posts 30 x 30mm overall height 1,200mm	30	NO.			
N	Ditto 60 x 60mm ditto	30	NO.			
	TOTAL CARRIED TO COLLECTION					

Handwritten signature and date:
10/4/15

Item	Description	Qty	Unit	Rate	Amount	
					Ksh	Cts
Forensic Audit Lab						
A	Supply and fix antistatic tiled carpets size 600 x 600 x 8mm th. Secured to polished granite tiles with approved adhesive to clients satisfaction.	17	SM			
B	Working counter overall size 5,000 x 600mm wide x 1100mm high comprising 100mm thick plinth in 1:3:6 concrete finished in screed (1:4) on 25mm thick blockboard; granite tops fixed on 50 x 50mm wrot cypress bearers place at 600mm centres; 20 mm thick x 600mm wide polished granite writing top with fascia and nosed edges fixed.	1	NO			
C	Low level cabinet comprising 25mm thick blockboard back and divisions at approximately 1000mm, 25mm thick wrought hardwood top for polishing, 25mm thick wrought cypress sliding front panels, 50 x 50mm wrought cypress top, bottom front and rear vertical framings at approximately 500mm centres, top and bottom sliding track gear including 100mm thick mass concrete(1:3:6) finished smooth in cement sand (1:3) screed, overall size 500mm wide x 850mm high	2	LM			
D	Allow for making good all disturbed areas	1	ITEM			
TOTAL CARRIED TO COLLECTION						
SUMMARY PAGE						
TOTAL CARRIED TO COLLECTION FROM PAGE 1						
TOTAL CARRIED TO COLLECTION FROM PAGE 2						
TOTAL CARRIED TO COLLECTION FROM PAGE ABOVE						
Add 16% VAT						
TOTAL CARRIED TO FORM OF TENDER						
Amount in words..... Name of Contractor Contractor's Address Contractor's Representative's Signature Date Witness Address Signature Date						

Handwritten signature and date
10/6/15