THE KENYA POWER & LIGHTING COMPANY PLC
CENTRAL OFFICE, STIMA PLAZA,
KOLOBOT ROAD, PARKLANDS,
P.O. BOX 30099-00100,
NAIROBI,
KENYA.

TENDER NO. KP1/9A.2/OT/009/NM/26-27

TENDER FOR REHABILITATION OF TRANSMISSION LINES - DESIGN, SUPPLY AND CONSTRUCTION

NOVEMBER 2026

VOLUME II

WORKS DESCRIPTION, SCOPE

TECHNICAL REQUIREMENTS, SPECIFICATIONS AND

SCHEDULE OF RATES

FOR

JUJA – NAIVASHA, ESCARPMENT COLLAPSED TOWER AND LESSOS –

LANET 132kV, L. NAKURU SUBMERGED TOWERS PROJECT

TABLE OF CONTENTS

SUMMARY OF SCOPE OF WORK 4

OTHER SERVICES 6

- CONTRACTORS' OFFICE AND NECESSARY FACILITIES 6
- COMMUNICATION AND TRANSPORTATION FACILITIES FOR EMPLOYER 6
- TRAINING FOR EMPLOYER 6
- SUPPLY OF MANDATORY SPARE PARTS 6

SITE CONDITIONS 7

- CLIMATIC CONDITIONS 7

QUALITY ASSURANCE 8

- GENERAL 8
- QUALITY ASSURANCE PROGRAMME 8
- QUALITY PLAN 9
- RELATED STANDARDS 9
- QUALITY CONTROL 10
- NON-CONFORMING PRODUCTS 10
- MONITORING OF QUALITY ASSURANCE AGREEMENTS 10
- SUPPLIERS AND SUB-CONTRACTORS 11
- METHOD STATEMENTS 11

DESIGN REQUIREMENTS 12

- PHILOSOPHY OF DESIGN 12
- UNITS OF MEASUREMENT 12
- DOCUMENT SUBMISSION 12
- DESIGN CALCULATIONS 12
- DRAWINGS 13
- SAG TEMPLATES 15
- SAMPLES AND MODELS 15
- PHOTOGRAPHS 15

TRANSPORT, ACCESS AND SERVITUDE 16

- WAYLEAVES 16
- ACCESS TO SITE, NOTICE OF ENTRY 16
- ACCESS ROADS 17
- CROSSING OF OBSTACLES 17
- DAMAGE 20

SURVEY, PROFILE AND GEOTECHNICAL INVESTIGATIONS 22

- ROUTE SELECTION 22
- CONTRACTOR DETAILED SURVEY 22
- GEOTECHNICAL INVESTIGATION 25

CONDUCTORS AND FITTINGS 27

- POWER CONDUCTOR 27
- TABLE 2: TECHNICAL DETAILS OF POWER CONDUCTORS (LYNX AND CASABLANCA) 29
- CONDUCTOR SAG DESIGN 30
- DRUMS 30
- JOINTS AND REPAIR SLEEVES 30
- ACCESSORIES FOR POWER CONDUCTORS AND EARTH WIRE 31
- CORONA AND RADIO INTERFERENCE 32

OPTICAL FIBER GROUND WIRE 33

TECHNICAL DESCRIPTION 33
OPTICAL FIBERS 36
OPGW FITTINGS 36
OPTICAL JOINT BOXES 36
FIXING CLAMPS 37
MATERIALS 37
PROTECTIVE TREATMENT 37
INSTALLATION 38
TERMINAL EQUIPMENT 38
QUALITY CONTROL 39
LINE INSULATION 41
INSULATORS DESIGN 41
FITTINGS 41
POLLUTION 42
ZINC COLLARS 42
INSULATOR PROTECTIVE DEVICE 42
MATERIALS 43
TESTS 43
TOWERS 45
TYPE OF TOWER 45
TOWER DESIGN GENERAL ARRANGEMENT 45
TOWER ACCESSORIES 49
MATERIALS 51
WORKMANSHIP 52
FOUNDATIONS 53
GENERAL 53
CONCRETE BLOCK FOUNDATION 53
SPECIAL FOUNDATIONS 54
FOUNDATION WORKS 56
ERECTION OF TOWERS 60
GROUNDING OF TOWERS 61
ERECTION OF CONDUCTOR AND OVERHEAD EARTHWIRE 61
TESTS AT SITE 64
METHOD OF MEASUREMENT & PAYMENT 67
PRICE SCHEDULES 67
SURVEY 69
ROUTE CLEARANCE & ACCESS 69
FOUNDATIONS 69
SUPPORTS (STEEL TOWERS) 71
INSULATOR SETS AND ASSOCIATED FITTINGS 71
CONDUCTORS AND FITTINGS 72
MISCELLANEOUS 72
SITE VISIT 72
SCHEDULES 73
PREAMBLE 73
13.1 SCHEDULE A: LOCATION ORIENTATION 74
13.2 SCHEDULE B - PLACES OF MANUFACTURE 82

SECTION 1

SUMMARY OF SCOPE OF WORK

The project scope is categorized as follows;

Overall Extent of Contract;

This Contract is aimed at reconstructing section of line affected by rising waters of L. Nakuru by rerouting the submerged section to higher dry land within the park and reconstruction of collapsed tower No. 1052 at escarpment area.

The Scope of the Contract includes the design, manufacture, supply, quality assurance, testing, galvanizing, painting (where specified), insurance, packing for transport, shipment, delivery to the site, unloading, soil investigation, clearing for and provision of access roads where necessary, complete erection, setting to work and defect liability for a period of 12 calendar months of the specified sections of the transmission lines.

The works shall further include, but not limited to, factory testing, testing on site and setting to work as set out in the general conditions of the contract and prices stated in the schedules or at such other prices or rates as may from time to time be agreed, together with the provision of such spares as directed and training of the Employer's personnel (if specified) to all works associated with the transmission line in accordance with the specification, standards, schedules and accompanying drawings and maps for the transmission line defined in Appendix.

The line route shall be as per the jointly established corridor. The final proposal is expected to maintain the alternative wayleave trace agreed by KWS. The Contractor will conduct a resurvey to enable him to prepare the profile drawings. However, it should be noted that confirmation of the survey shall be done by the Employer and KWS. Where there are gaps, the Contractor is to conduct detailed survey through conventional methods at no extra cost.

Check survey, profile survey, plotting of support positions & pegging out shall be carried out by the Contractor. All and any structures and obstacles which the new transmission lines cross shall be identified so that the Contractor shall basically consider the check survey works by traditional methods.

Transmission Line Reconstruction/Rerouting

The particulars of transmission line to be reconstructed/rerouted under the Contract are as follows.

132 kV Transmission Line Section Submerged by Nakuru and section of collapsed Tower at Escarpment

The project scope shall include;

- Reconstruction of section of 132 kV double circuit three phase transmission line of single conductor per phase of ACCC code name "Casablanca" conductor along Lanet - Lessos (UEB) 132kV Transmission Line at Lanet area between towers **747** and **765** in Central Rift Region.

- Reconstruction of collapsed tower 1052 on section of 132 kV double circuit three phase transmission line of single conductor per phase of ACSR code name "Lynx" conductor along Juja- Naivasha (UEB) 132kV Transmission Line at Escarpment area between towers **1051** and **1053** in Central Rift Region. The collapsed section is currently on Emergency Restoration Towers (ERT), recovery of ERTs shall be KPLC scope. Design and construction to adopt double string insulators. Bidders to note that the site location is inside gazzeted forest with Kenya Forest Service (KFS) control and regulations.

Table 1: Scope of works

No	Location	Line Name	Collapsed/Submerged towers section	Proposed no. of lattice towers
1.	Escarpment Maimahiu	Juja - Naivasha 132kV Line	T1051 – T1053	1
2.	Lanet	Lanet - Lessos 132kV Line	T747 - T765	20

Scope, will involve Design, Procurement , construction and commissioning of approximately 9.0 km of double circuit 132kV Transmission line on self-supporting galvanized lattice steel towers with ACSR 175mm^2 (code name "Lynx") and ACCC 273.6mm^2 (code name "Casablanca") conductor and overhead 48 core OPGW shield wires and steel earth wire 7/14 on a high twin peaks to cover both circuits complete with spliced junction boxes.

The scope of work for the transmission line will cover design, factory testing, manufacture, supply, shipping, transport from docks to stores, delivery to site, unloading, check survey and all associated profile plotting, support pegging, provision of access facilities and route clearing, transportation to site, installation of foundations and all associated civil works, erection of supports, installation of insulators, conductors and all associated fittings.

The transmission line shall be constructed completely in accordance with the specifications and associated design and general arrangement/outline drawings.

Tenderers shall submit a program of works in Gantt Chart indicating the planned plant manufacture, delivery and erection program (as appropriate) to complete the works. The Gantt Chart shall indicate the various phases of work for all appropriate items of the project from commencement to final completion e.g. design, survey, approval of drawings, ordering of materials, manufacture, delivery, erection (as appropriate) and commissioning. The

program shall allow for periods of approval by the employer and/or any other regulatory body.

OTHER SERVICES

Contractors' Office and necessary facilities

The Contractor shall provide the following facilities for his own use to accomplish his works.

- Office for his own use with security provision.
- Labour camp for the Contractor's work force
- Storage for temporary storage of the goods and materials until they are transported to the final construction sites.
- First aid facility for medical care
- Other facilities necessary for executing his works

Communication and Transportation Facilities for employer

Communication and transportation facilities for Employer shall be provided as per the Technical Specifications.

Training for Employer

The Contractor shall provide the training as specified in the Technical Specifications.

Supply of mandatory spare parts

The Contractor shall supply the mandatory spare parts as specified in the Technical Specifications. Such mandatory spare parts shall be delivered to the Employer's permanent store as reasonably designated.

SECTION 2

SITE CONDITIONS

Site specific conditions and data shall be bidder confirmed at the time of biding.

CLIMATIC CONDITIONS

The following climatic information is given for tender purposes only:

Minimum ambient temperature	:	-1^0C
Maximum ambient temperature	:	40^0C
Average ambient temperature	:	24 - 28^0C
Relative humidity- maximum	:	90 - 100%
Average Annual Rainfall	:	1500-2500 mm
Maximum Wind velocity	:	180km/hr (50 m/s)
Isokeraunic level	:	180 thunderstorm days
Seismicity Coefficient	:	0.16
Altitude or Terrain	:	1500-2500m a.s.l.

SOILS

Ground condition is fairly homogenous along the transmission line route, being mainly residual soil comprising silty clay, loam soil, as well as disintegrated to hard rock that should be encountered at different depths. Ground water level is high due to proximity to the Lake for Lanet - Lessos section.

The Contractor will be expected to carry out extensive soil investigations during the detailed design stage.

SECTION 3

QUALITY ASSURANCE

GENERAL

The quality assurance arrangements shall conform to the appropriate sections of ISO 9001:2015.

The Contractors/suppliers Quality Programme for the Works shall define the system and procedures adopted to ensure compliance with the contract requirements. These systems shall include the following.

Hold point - "A stage in the material procurement or fabrication/workmanship process beyond which work shall not exceed without the documented approval of the employer or their appointed representatives.

Notification point - "A stage in the material procurement or fabrication/workmanship process for which advance notice of the activity is required to permit attendance.

The Contractors/suppliers are required to give the employer or their appointed representatives the requisite period of notice of any notification point for which attendance is required. If the employer or their appointed representatives do not respond/attend after receiving the documented notification the work may proceed.

QUALITY ASSURANCE PROGRAMME

The quality assurance programme shall give a description system for the works and shall include the following details: -

a. The structure of the Contractors/Sub-Contractor/ Suppliers/Manufacturer organization.
b. The duties and responsibilities of staff assigned to ensure quality of the work.
c. The system for purchasing, taking delivery and verification of materials.
d. The system for ensuring quality of workmanship.
e. The system for control documentation.
f. The system for retention of records.
g. The arrangement for the Contractors/suppliers auditing.
h. A list of the administrative and work procedures required to achieve and verify the Contractor's quality requirements. These procedures shall be made readily available to the employer for inspection on request.

The Quality assurance programme for the works shall be submitted to the employer for approval within the requisite period prior to the commencement of the works. This will be a hold Point.

QUALITY PLAN

A specific Quality plan for each section of the work shall be produced by the Contractor and/or supplier. Each quality plan shall set out the activities in a logical sequence and shall take into account the following:

a) An outline of the proposed work and programme sequence
b) The structure of the contractor's and/or supplier's organization for the project
c) The duties and responsibilities of staff assigned to ensure quality of the work for the project
d) Hold and Notification points
e) Submission of Engineering Documents required by this specification
f) The inspection of materials and components on receipt
g) Reference to the Contractor's and/or supplier's quality assurance procedures appropriate to each activity
h) Inspection during fabrication/construction
i) Final inspection and tests.

The Contractor's and/or suppliers Quality plan shall be submitted to the employer for approval, within the requisite period prior to the commencement of the works. This will be a hold point.

RELATED STANDARDS

The specified BS, KS, ISO, IEC standards or other relevant internationally recognized standards approved by KPLC shall be applied in this project.

It is the Contractor's responsibility to ensure that they are in possession of the latest edition of the specified IEC standards and other relevant standards specified, including all amendments current on the defined date prior to the tender closing date.

Materials or equipment conforming to alternative international or national standards will be considered by the employer, provided that these standards ensure an equivalent or higher quality.

The Contractor/supplier shall bring to the attention of the employer any inconsistencies between the requirements of these standards and this specification.

The Contractor/supplier shall supply the requisite number of copies of the applicable reference standards specified in each appropriate section within the requisite period after the signing of the contract

Where equivalent standards are offered as an alternative, the Contractor/supplier shall, when requested by the employer, provide the requisite number of English language translation copies of the standards at no extra cost to the project.

QUALITY CONTROL

Inspection and Testing

The prime responsibility for inspection and testing shall rest with the Contractor/supplier. The inspection and acceptance of drawings, materials and workmanship, or the waiver of inspection by the employer, shall not relieve the Contractor/supplier of any obligations or responsibilities to carry out the work in accordance with specification and good engineering requirements. The inspection and testing shall be documented such that it is possible to verify that it was undertaken. Records of inspection shall include as a minimum the project identity, the name of the inspector/tester, date of inspection/ test, operation/inspection, technique used, acceptance standard and acceptability.

Type, Sample and Routine Tests

Type, sample and routine tests shall be undertaken on all components supplied and/or installed under this project, in accordance with the requirements of this specification.

The Employer may waive the requirements for type tests on submission by the Contractor/supplier of the requisite number of test certificates, either certified by an independent quality assurance organisation, or undertaken by an internationally acknowledged independent testing organisation, showing that the component had successfully passed the type tests specified in this specification.

Certificate of Conformity

Prior to the issue of the Release Certificate or agreement to shipping the Contractor/supplier shall submit to the employer the requisite copies of the completed certificates of conformity **(see Appendix 1.A.7).** The certificate shall be supported by copies of the appropriate material test certificate inspection records, type and sample test reports as detailed in the relevant section of this specification.

NON-CONFORMING PRODUCTS

The employer shall be responsible for reviewing the non–conforming products in accordance with ISO 9001:2015.

MONITORING OF QUALITY ASSURANCE AGREEMENTS

Monitoring of the Quality Assurance arrangements may be undertaken by the employer during the course of the project. This will take the form of surveillance of the activities at work locations and/or by formal audits of the Contractors/supplier system and procedures which constitutes their quality assurance arrangements. Corrective actions shall be agreed and implemented in respect of any deficiencies.

The Contractor/supplier shall provide all facilities including access (including their suppliers or sub-contractors) which may be required by the employer for monitoring activities.

SUPPLIERS AND SUB-CONTRACTORS

The Contractor shall ensure that any supplier or sub-contractor appointed by them under the project shall conform to the requirements of this specification. Prior to the appointments of any supplier/sub-contractor the Contractor shall ensure that their quality assurance arrangements comply with the requirements of ISO 9001:2015 and this specification.

The Contractor's auditing of their suppliers/sub-contractors quality assurance arrangements shall be documented to demonstrate to the employer their extent and effectiveness.

METHOD STATEMENTS

Prior to commencing any section of the work, the Contractor shall submit method statement in accordance with the requirement of the relevant section of this specification. Submission of these method statements shall be treated as Hold Points.

When requested by the Employer or their appointed representative, the Contractor shall provide additional method statements related to specific item of work.

SECTION 4

DESIGN REQUIREMENTS

PHILOSOPHY OF DESIGN

The philosophy of design contained within this specification is based upon deterministic principles whereby the applied loading multiplied by the appropriate safety factor must be less than the ultimate strength of the component.

In tendering the Contractor will be deemed to have concurred as a practical manufacturer with the design and layout of the works as being sufficient to ensure reliability and safety in operation freedom from undue stresses and satisfactorily performance in all other essentials as a working plant.

The transmission lines shall be designed with high reliability and low cost of maintenance as the primary consideration in accordance with the relevant sections of the specification.

The design shall incorporate all reasonable precautions and provisions for the safety of those concerned in the erection and subsequent maintenance of the contract works.

UNITS OF MEASUREMENT

In all correspondence, technical schedules design calculations and drawings the metric (SI) units of measurement shall be used. Angular measurements shall be degrees with 90^0 comprising a right angle.

DOCUMENT SUBMISSION

The Contractor shall submit to the Employer all design calculation, drawings, method statements, test programmes and test records of the relevant section of the specification or as otherwise agreed by the Employer.

DESIGN CALCULATIONS

All sets of calculation shall be complete, bound titled and given a unique drawing number. The binding shall be such as to allow the easy introduction of subsequent pages if necessary.

Bound into each set shall be fully detailed index. Following this shall be a design information sheets which incorporates the following details: -

a) The design concept shall be summarized
b) Full details of manual design papers or other aids referred to in the text shall be given with photocopies of relevant sheets if appropriate.
c) Full loadings shall be reiterated with their deviations if appropriate.
d) Design stresses shall be reiterated.

e) Code or standard references should be quoted and equation written out in full for initial calculation.

Should the Contractor be required to re-submit amended calculations or additional sheets the following annotation shall be adopted: -

f) Amended sheets should retain the same sheet number but have a lower-case revision letter suffix i.e. sheet 14 when amended becomes 14a then 14b.

g) Additional sheets that needed to be inserted shall be given the sheet number they are added to plus an upper-case letter prefix i.e. additional sheets to page 60 become A60, B60 and if subsequently amended A60a etc.

Where a computer program is used for design calculations a full explanation in the English language shall be provided to assist the Employers approval of the calculations for each and every program used. Details must include name of program author source, comprehensive description of theoretical basis including all references to relevant documentation, checks undertaken on program and list of projects on which the program has been used.

DRAWINGS

General Requirements

Drawings shall be to scale fully detailed and all dimensions shall be in Metric Units. General arrangements drawings submitted shall be to scale of not less than1 to 50 and all detail drawings not less than 1 to 20. Profile drawings shall normally be drawn to a vertical scale of 1 to 200 and a horizontal scale of 1 to 2,000.

Drawings sheets shall conform in size to BS 3429, mainly A0, A1, A2, A3, and A4. A3 drawings shall be used as much as possible for construction drawings. The sheet size is to be stated on the drawing within or adjacent to the title block.

Drawings shall conform to BS 308 or equivalent. The scale used shall be stated on the drawing as a ratio together with linear scale at a convenient position along the margin of the original drawing sheet.

The physical draughting requirement in respect of line density, strength, contrast, spacing and character legibility shall be met to ensure drawings are suitable for microfilming in accordance with BS 5536 and the specification for micro-copying of drawings to BS 4210.

All drawings shall bear in English, serial number of the project, drawing number, which shall be unique to this project and scale. The system of numbering and layout of the title block will be to the approval of the Employer. The title block shall include the name and address of the Employer. The revision notes shall detail the nature of each revision. The revision shall be enclosed in a cloud with the revision letter indicated.

Computer Generated Drawings

The submissions generated drawings sent by electronic transmission or any other electronic form shall be subject to agreement by the Employer.

Contract Drawings List

At defined interval the Contractor shall submit the requisite number of copies of the contract drawing list.

The list shall contain the following information:

a. Drawing number,
b. Drawing title
c. Revision status
d. Approval status

All changes since the previous issue shall be clearly indicated and when agreed only the front (index) revised sheets need to be submitted.

Contract Record Drawings

The Contractor shall submit to the Employer:

a) A final issue of the contract drawing list indicating which of the drawings design calculations, methods statements etc. that they propose to issue as final contract drawings. These drawings shall be updated to incorporate all modifications made during erection and commissioning.

b) Requisite number of prints (minimum of four) of each schedule, including where appropriate the supply and installation material manual.

c) Requisite number of drawings (minimum of four) including design calculations schedules including the supply and installation material manual in data stick format in either WPG or DXF format.

d) Requisite number of polyester/transparency film copy of each drawing, including design calculations, profile and route maps.

The distribution of the contract record drawings will be advised by the Employer.

Route maps

During the progress of the work the Contractor shall record on profiles, supply and install material manuals (SIMMs) and on a set Survey Maps of approved scale such particulars as will allow an accurate reference to be made afterwards in case of any faults or projected modifications to the line.

The map and/or profile sheet shall show the exact position of every support with approved reference marks. The maps shall be supplemented or profiles marked by sketches where

necessary to delineate boundary position of support which cannot be clearly indicated on the maps.

The date included on the maps profile sketches and SIMMS shall be submitted to the employer to whom facilities shall be given for examining such records during the progress of the work.

SAG TEMPLATES

The Contractor shall supply the specified sets (minimum of two) of templates in strong stable colourless plastic or similar material not less than 3mm thick. Engraving shall be on the back face of the templates. The templates shall be for the specified equivalent spans.

Each template shall be accurately shaped to provide the sag curve; the same curve shall be engraved on the template at a distance below representing the minimum allowable vertical clearance to normal ground. A further sag curve in still air at minimum temperature shall also be shown. Each template shall be clearly endorsed with the sagging basis, conductor particulars equivalent span and unless otherwise specified to a scale of 1:200 vertical and 1:2000 horizontal.

Templates shall be supplied to the Employer before the submission of the profiles. Failure to do so may result in delay which will be responsibility of the Contractor.

SAMPLES AND MODELS

If the nature of the works makes it desirable the Contractor/ supplier may be asked to submit or prepare for the Employer such samples, patterns and models as the Employer may reasonably require for the purpose of design approval at the expense of the Contractor/supplier.

PHOTOGRAPHS

The Contractor shall make all arrangements to provide progress photographs of all tests and such sections of the work in progress as directed by the Employer. Each photograph shall be of size 25cm x 20cm suitably entitled, in digital format. The photographs shall be the property of the Employer and no copies of the photographs shall be released without the authority of the Employer.

The Contractor will normally be required to provide every month at his own cost the specified number of sets of un-mounted progress photographs suitably inscribed of potions of the work in progress throughout the period of construction. Any variation to these quantities will only be with the permission of the Employer.

SECTION 5

TRANSPORT, ACCESS AND SERVITUDE

WAYLEAVES

General

Wayleaves and access facilities, subject to the requirement of landowners and occupiers, will be provided by the Employer to enable the Contractor to carry out the erection of the contract works. Such facilities will not necessarily include facilities for storing materials nor necessarily include access for wheeled vehicles.

The Contractor shall satisfy themselves that the necessary rights of entry and access have been obtained before.

The contractor shall indicate to the employer such pipes or other obstructions telephone telegraph and power lines which infringe the clearance specified or otherwise fail to satisfy the requirement of the specification.

The necessary agreement for the removal of obstruction such as trees and for the permanent removal or guarding of pipes telegraph telephone and power lines, will be obtained by the Employer.

Wayleaves Schedule

Before the Contractor commences work on any property he shall obtain the wayleaves schedule from the Employer, including details of any special requirement of the occupiers concerned. This is a Hold Point.

ACCESS TO SITE, NOTICE OF ENTRY

Access Routes – General

The Employer may indicate to the Contractor the general route for access to each or any position as agreed by the Employer, otherwise the Contractor shall make all necessary arrangements (other than questions of way leaves) with the occupier.

Subject to the provisions of the preceding paragraph before commencing work, the Contractor shall at his own expenses do what is necessary to make the access suitable for his use and shall take all reasonable precautions to avoid damage, including if required erection of temporary fences or gates where permanent fences, hedges or gates have been removed. The Contractor shall not be entitled to any additional payment in the event of a particular access being difficult.

The Contractor shall be responsible for maintaining agreed access routes in a usable condition without undue widening for the duration of the contract. The occupier shall not be

put to any inconvenience in gaining access to his land or buildings. No unauthorized access routes shall be taken by the Contractor.

Commencement of work

Before beginning on any property, the Contractor shall be responsible for obtaining confirmation from the Employer that wayleaves are in order and any agreed accesses have not been altered and for giving not less than 48 hours' notice to the occupier that work is to begin. Work shall proceed on any land within the requisite period of such notice being given to the occupier.

Suspension of work

Where work is to be suspended without the expectation of it being resumed within the specified period, the Contractor must notify the occupier of such intention and shall similarly give the occupier prior notification of the resumption of work. The purpose of this Clause is to assist in maintaining good relations between the occupier, the Contractor and the Employer and to keep the occupier informed of what is going to happen on or across his land.

Compliance with occupier's requirements

At all times during the execution of the works, the Contractor shall ensure compliance with all such reasonable requirements of the occupier as are brought to the Contractor's notice by the Employer. The Contractor shall not be entitled to any additional payment in respect of his compliance with the reasonable requirements of the occupier.

Notice to Authorities

Before the Contractor carries out the stringing of conductors along or across power or telecommunication circuits, public roads, bridge, railway etc., he shall give the requisite notice to the appropriate Authorities of the time and date when he proposes to perform the work and shall send a duplicate copy of each notice to the Employer.

Route Clearance

For details of the clearance requirements for survey, access routes, line route, support locations and conductor stringing, contractor to submit for consideration.

ACCESS ROADS

For details of the access road requirements, contractor to submit for consideration.

CROSSING OF OBSTACLES

General

The Contractor shall, at his own expense, make any necessary arrangements and take the necessary precautions where the route crosses buildings, telecommunication, power or pipe lines, orchards, gardens, railways, antiquities or other obstructions or ground over or across which erection cannot be carried out in the normal manner or has to be avoided. These arrangements must be submitted to the Employer. This is a Hold Point

Where a support is set across a fence, hedge, bank or wall, the Contractor shall remove and reinstate the fence, hedge, bank or wall at his own expense and he shall be responsible at his own expense for making good to the satisfaction of the Employer, owners and tenants concerned, all land, property, roads, drains, fences, walls hedges, gates and the like which he has damaged or disturbed during the execution of the contrast works and shall remove all surplus material after erection. The Contractor shall take proper precautions to prevent the straying of and damage to livestock until after the backfilling of excavations and permanent reinstatement of fences, walls, hedges, gates and the like are completed.

Public Utilities

The Contractor shall ensure that the erection of the contract works does not cause damage to or interference with existing telecommunication, power or pipe lines.

Where appropriate Authorities affected deem it necessary for the protection of their employees, property, or the public, or for the assistance of traffic, to provide flagmen and watchmen, the cost of such provision shall be borne by the Contractor. Where required by the appropriate Authorities work shall be carried on outside normal hours and at the Contractor's own expense.

The Contractor shall also be liable to make good at least to the original condition or compensate the owners, operators and users or any public undertaking in respect of any damage however caused to their property, lands or roads arising out of or in consequence of the execution of the works.

Scaffolding

The Contractor shall provide all necessary scaffolding and the like for the crossing of telecommunications or power lines, roads, railways building or other obstacles. The Contractor shall advise the Employer in each instance of the scaffolding he proposes to use. Drawings of the proposed scaffolding shall be submitted to the Employer, and the appropriate regulatory authorities. This is Hold Point

Live Line Scaffolds

The scaffolding which is used to cross specified low, medium and high voltage power lines shall be of such dimensions and allow such clearances that the power lines being crossed may remain in commission during construction of the new transmission line. It may only be possible to have shut-downs on the lines to be crossed for sufficient periods of time to top out and net the scaffolds. Such restrictions in building and use of the scaffolds will not be grounds for claiming additional costs. Design and construction of the live scaffold shall not be inferior to the minimum standards outline in the following clause.

Live Line Scaffold-Construction

The scaffold shall be designed to withstand the maximum design wind speed, except that a reduced return period will be accepted. Consideration shall also be given due to impact loading, due to dropping of the upper phase conductor.

The scaffold shall, unless otherwise approved by the Employer, consist of 3m wide 300mm squire mesh nylon nets attached to steel wire ropes running perpendicular to the lower line route, carried by metal scaffolding at 3m intervals. The nets shall be attached to the catenary wires by means that do not require the presence of any persons on the net or the catenary wires whilst the lower line is alive. An additional movable 3m by 50 mm mesh walk net laid over the 300 mesh nets may be used whilst the lower line is dead.

Normally, steel or aluminium tubular scaffolding to BS 1139 and BS 6323 should be used. The use of pre-formed units or frames shall be subject to the Employer's approval.

The mechanical construction shall be in accordance with BS 5950. Reference shall also be made where appropriate to BS 5973.

The design of the scaffold shall have due regard to the requirements of safety with particular respect to accidental contact with live conductors during construction, use and removal.

The scaffold, including foundations, shall be designed and constructed to ensure stability during the process of erection and removal, and also at times when work has caused for any reason including adverse weather conditions. The foundations shall be suitable for the ground concerned.

The base width of any tubular steel supporting structure shall not be less than 25 percent of its height. Lighter materials (e.g. Aluminium) shall be used with caution. Adequate diagonal bracing shall be provided.

The scaffold shall extend at least 5m either side of the outermost conductors of the upper line. A maximum of 2m of this distance may be provided by means of catchers.

Catchers shall be provided at each end of each scaffold support. The catcher may be vertical or inclined to a maximum angle of 45^0 from the vertical. They shall be capable of withstanding the specified impact loads without excessive distortion that would permit a falling conductor to approach or touch a live-line.

The upper parts of the scaffold shall be provided with soft wood rubbing boards or otherwise protected in an approved manner to prevent damage to the conductors resting on or being drawn over the guard. Soft wood poles may be used for this purpose. The height of these boards shall be sufficient to prevent the conductor damaging the nylon net. To avoid damaging the conductors no object other than non-metallic lashing or the catchers shall protrude above the rubbing boards.

Sufficient endless or double ended lead lines for hauling over pilot wires shall be placed over the scaffold prior to re-energization of the lower line.

The side supports shall have working platforms to facilitate the required running of conductors and prior wires. Working platforms shall be provided with hand rails, toe boards and notices warning of the danger of live conductors. The heights of hand rails shall be 1m and the toe boards 230 mm. Each working platform shall have a notice plate indicating the "Safe Climbing Height".

The scaffold shall be fitted with danger plates at intervals of not more than 6m along the anti-climbing device with at least one plate on each face of the structure.

The scaffold shall be constructed to prevent unauthorized access or climbing by the use of barbed wire anti-climbing devices, fences or other means approved by the Employer. The scaffolding shall be lit with red warning lamps from ½ hour before sunset to ½ hour after sunrise if erected within 2m from a highway or footpath without an intervening fence. The scaffold the Contractor shall provide or arrange for the supply and maintenance of these lamps (e.g. with the line Contractor).

If the scaffolding is constructed adjacent to a roadway, a guard constructed from steel drums filled with soil or a soil bund shall be provided and suitably lit.

Where possible the resistance to earth of the scaffold shall be less than 10 ohms. Special consideration by the Employer and the lower line operator shall be given in cases where this is not attainable with a reasonable number of driven earth rods.

Bonding the scaffold to the earthing systems of either the live-line, or the line under construction is not normally acceptance. In the former case a nearby line fault could cause the scaffold to become live. In the latter case a fault between the live-line and the scaffold could cause components of the line under construction to become alive, particularly as its earthing system may not be complete.

The earth rods should normally be driven into the ground around the outside and approximately 1 m from the scaffold structure. The rods should be securely connected electrically and mechanically to the scaffold structure by flexible copper or aluminium leads with minimum across-sectional areas of 64 mm^2 or 100 mm^2 respectively.

Drawings of the scaffold complete with details of the clearance plates and earthing arrangement, together with supporting calculations shall be submitted to the Employer and appropriate regulatory authorities. This is a Hold Point.

DAMAGE

General

The Contractor shall take all reasonable precautions to avoid damage to land, property, roads, crops, field drains, fences, walls, hedges, gates, trees and the like and shall ensure that the work is adequately supervised so that any damage is reduced to the minimum. Save as

otherwise provided, the Contractor will be liable for all damage arising by or in consequence of the works except unavoidable damage to crops and shall pay compensation or make good at the option of the Employer.

Contractor's Responsibility

The Contractor's liability for loss or damage shall extend to any such loss or damage resulting from the employment of a Subcontractor. This does not relieve the Contractor of his liability for all actions of his Subcontractor.

Wildlife/Livestock

Adequate provision shall be made by the Contractor to prevent the straying of or injury to livestock/wildlife during the execution of the work and until the permanent reinstatement of fences, wall, hedges, gates and the like is completed.

The Contractors shall be liable for any injury to or loss of livestock due to failure to comply with the above requirements.

SECTION 6

SURVEY, PROFILE AND GEOTECHNICAL INVESTIGATIONS

ROUTE SELECTION

The Employer will indicate to the Contractor either on maps or during visits to the sites the proposed route of the transmission line, with approximate positions of the angle and terminal support and the position of such intermediate supports as it may have been desirable to determine during preliminary wayleaves negotiations. The Contractor shall give the Employer the requisite period of notice prior to commencing the survey. This is Hold Point.

CONTRACTOR DETAILED SURVEY

Access for Survey

The Contractor's surveyors shall in all cases announce himself to the occupier/landowner immediately before entering any private property for the purpose of survey.

Accuracy

Profiles shall be produced as a result of a precision ground or aerial survey, the accuracy of which shall be such that the vertical tolerance between levels forming the profile and actual ground level shall not exceed 300 mm, and the measured to an accuracy of not less than 0.2 percent. All levels shall be related to the specified national datum.

Profile Drawings – Size & Scales

Computer plotted profiles on plain plastics drawings sheets will be accepted by the Employer.

The profile shall either be drawn on a mixture of a melinex type material or as otherwise approved with printed grid lines of increasing thickness in 1, 5, 10 and 50 mm squares and shall be drawn on the reverse side of the melinex to the grid lines.

However, the format of the profile shall not differ from the details specified in the following clauses.

Unless specified to the contrary the scale of the profile shall be:

- 1:2000 horizontally and
- 1:200 vertically

The profile shall be plotted with the direction of the line route left to right on profile sheet. In general, individual profile sheet shall commence and finish at tension supports but where this is not practicable and continuation sheets are found to be necessary the ground line is to be drawn so that there is an overlap of at least 300 mm between adjacent sheets. The chainage of each section between tensions structures shall start at zero be on 50mm printed grid line and not less than 150mm from the left-hand margin. Each section shall normally be started on a new sheet. The date of survey of each section shall be added.

If more than one section is drawn on one sheet a gap shall be left in the ground line of not less than 150mm.

Profile Drawings – Details

The following details and information are to be included on the profile drawings:

a. At each angle position "tie– in" sketch shall be provided on the profile sheet. This sketch shall show clearly the location of the support using as reference where possible points which can be located on the ground and on the 1:5,000 or closest available scale of survey map. The direction of the line and angle of deviation are to be shown stating also whether the deviation is left or right. Where reliable maps of reasonable scale and accuracy are not available for locating and plotting support positions survey methods acceptable to the Employer shall be employed to establish grid co-ordinates supports and ground features shall be related to these.

b. Where ground slope across the line route exceeds 1 in 25 the level of ground left and right of the centre line shall be recorded at specified horizontal offset distances where the side slope is uniform. Where the slope breaks upwards beyond this distance levels will be recoded up to a specified horizontal offset distance. The offset levels shall indicate on the profile as broken and/or chain lines and the distance off-line started.

c. The profile shall show all changes of level of 300 mm or more along the route centre line and along the off-set lines. All features such as hedges, fences, graves, ditches, roads, railways, rivers, buildings, canals, telephone and railway lines and all power lines shall be shown. Route numbers or name of roads shall be stated or, if unclassified the destination. Railways are to be given the destination, number of tracks, whether or not electrified and the level at the top of rail stated.

d. The chainage is to be shown at each 300 m and at every geographic feature or obstruction. Chainage shall also be given to all pegs.

e. The specified Datum shall be the basis for all levels and the levels above the specified Datum shall be shown at 10 m vertical interval at the beginning and end of each profile sheet. Levels shall be shown at each peg on line and at every obstruction or geographical feature.

f. The visual nature of the ground shall be noted whether cultivated, woodland, etc., with special reference to marsh soft ground or rock and other relevant information such as soil instability.

g. All buildings or high obstruction within 30 m of the centre line shall be shown dotted at their measured height with the distance left or right of line indicated.

h. Where the ground contour rises to a point which would be less than 100 mm from the top of the profile sheet, the ground line shall be terminated and continued on a new sheet with an overlap of 300 m of line route.

i. The following detail shall be shown for crossing of power lines: -

- Voltage and type of construction
- Ground levels at point of crossing and support structures;
- Height of top conductor and earth wire at point of crossing and at point of support;
- Distance from crossing point to support structures along route of line to be crossed;
- Angle of crossing;
- Temperature at time levels were taken (state date and time);
- Support structures members.

j. Along the bottom of the profile sheet a route map shall be drawn, to the same scale as the horizontal scale of the profile, showing all relevant details, within a distance of 30m each side of the route centre line. All items covered by sub-paragraphs (a) and (i) above as appropriate shall be included

k. On tower spot locations, local profile for each tower shall be provided. Stub length and foundation depth design shall refer local profiles as much as possible.

Support Location on Profiles

The Contractor shall submit to the Employer the requisite copies of the profile drawings upon which shall be indicated the proposed location and type of each support, spans, section lengths, (i.e. distances between tension supports), equivalent spans, wind and weight span, phase conductor swing angles, difference in level between adjacent phase conductor attachment points and the sag templates used. This is a Hold Point.

In addition, the relevant position of the bottom or lowest phase conductor at the specified maximum conductor temperature, together with another line parallel to the phase conductor at the minimum statutory ground clearance, shall be shown on the profile.

Check Survey

The Contractor shall carry out a check survey. Proposed surveyed route for which wayleaves have been obtained will be made available to the Contractor, who will be required to check the profile survey and survey and design final route for approval.

The Contractor is required to check thereon the proposed support positions and submit the profile to the Employer. Profile details and support locations shall be in accordance with the preceding clauses. Check survey shall include Contractor notes on final route selected and shall be approved by Employer; approved centre shall be the transmission line approved design centre. Design and construction set out will be based on this without changes, and any deviation shall be reported immediately to the Employer with the proposal for restoring design centre.

GEOTECHNICAL INVESTIGATION

General

Geotechnical investigations shall be undertaken in accordance with the technical requirements detailed in the following clauses and British standard code of site investigations BS 5930. Tests shall be to BS 1377 British standard for civil engineering soils properties.

Where required by the Employer, the Contractor or his appointed geotechnical consultant shall undertake the specified slope stability analysis and design.
The Contractor shall give the Employer the requisite period of notice prior to commencing the geotechnical investigation. This is a Hold Point.

Level 1

Level 1 geotechnical investigations shall be based on a visual-tactile examination of disturbed soil samples for the determination of both soil classification and strength.

Level 2

Level 2 geotechnical investigations shall be based on in-situ testing for the determination of the soil strength and visual tactile examination of disturbed samples for the determination of soil classification

Level 3

Level 3 geotechnical investigations shall be based on in-situ testing (as level 2) for the determination of the soil strength and the recovery of disturbed soil samples for the subsequent laboratory testing.

Laboratory soil classification tests for non-cohesive soils shall be particle size distribution, moisture content and relative density, whilst those for cohesive soils shall be moisture content and Atterberg limits.

Level 4

Level 4 geotechnical investigations shall be based on a combination of in-situ testing (as level 2) and the recovery of disturbed/undisturbed soil samples for the subsequent laboratory testing.

Soil and Ground Water Samples

Where specified, soil and ground water samples shall be obtained for determination of the chemical content i.e. organic matter, sulphate, pH and chloride content.

Geotechnical Investigation Criteria

Geotechnical investigation shall be undertaken to the following criteria:

a) Geotechnical investigation shall be undertaken as near as possible to the tower site. For test foundations the investigation shall be undertaken as near as possible

to the test site, and shall take account of the theoretical failure surface of the foundation.;

b) Time lapses between the investigation and foundation installation shall take into account any noticeable effect on the geotechnical properties due to rainfall or seasonal variations in the groundwater level;

c) Depth of investigation shall be:

i. For trial pits 2m; or
ii. the foundation depth plus 1.5 times the maximum base width dimension for concrete pad and chimney or steel grillage foundations; or

iii. 3m or 5 times shaft diameters (whichever is greater) below the foundation depth for drilled shaft, piled foundations; or
iv. at least2m into rock or hard dense stratum (N_{SPT}> 50) if this occurs before the recommended depth; or
v. For uplift or lateral foundation tests not less than 1m below the base of the test foundation.

d) SPTs (standard penetration tests) should be undertaken at the top of each stratum and then at 1m intervals in soil or weak rock;

e) PMTs (Pressure meter tests) should be undertaken in each stratum or as required;

f) CPTs (Cone Penetration Tests) should be taken continuously over depth of investigation

g) VSTs (Vane Shear Tests) should be undertaken at top of each stratum and then at 1m intervals;

h) Soil/rock description should be based on disturbed samples taken in each stratum and thereafter at 1m intervals.

i) Highest ground water level and variation in water level

j) Electrical resistivity of the soil shall be verified on every tower site in accordance with British standard code CP 1013-1965,

SECTION 7

CONDUCTORS AND FITTINGS

POWER CONDUCTOR

The power conductor shall be Aluminium Conductor Steel Reinforced (ACSR) for escarpment and Aluminium Conductor Composite Core (ACCC) for Lake Nakuru.

Aluminium Conductor Steel Reinforced (ACSR) shall comply with IEC 60889. The outermost layer of the conductors shall be right-handed lay (z-lay). The Aluminium shall be of the highest purity commercially obtainable and shall not be less than 99.5%. The Contractor shall submit certificates of analysis giving the percentage and nature of impurities in the metal from which the wires were made. There shall be no joints in the individual wire of the outer layers of aluminium wires. All steel core wires unless specified to the contrary shall be hot-dipped galvanized to comply with the requirements of IEC 60888.

Unless specified to the contrary all conductors shall be uniformly covered with neutral grease as per IEC 61089. The minimum fill factor of grease shall not be less than 70 percent. Each layer of wire except the outer layer shall have, both lengthwise and peripherally, an even and continuous coating of grease. Wax thickened greases shall be applied at a temperature above the dropping point and shall be substantially free from contaminants.

The grease shall protect the conductors from corrosion in service, not corrode the steel or aluminium, be compatible with any wire drawing lubricant that might be applied on the conductor, not flow nor exude from the conductor during storage, transport, erection or service at temperatures of up to 100 degrees C. In addition, the grease should have adequate resistance to oxidation and conform to relevant current health and safety requirements.

ACCC (Aluminium Conductor Composite Core) is a high-temperature, low-sag (HTLS) overhead conductor. It has a lightweight core of carbon fibre and glass fibre in an epoxy matrix. The carbon fibre center gives high tensile strength, and the outer glass fibre layer keeps the carbon away from the aluminium so that galvanic corrosion cannot occur. The core is wrapped in trapezoidal (TW) strands of fully annealed 1350-O aluminium. The strands pack tightly, so the conductor carries about 25–30% more aluminium. The core expands very little with heat, so the conductor can run continuously at up to about 180 °C with much less sag. It does need the manufacturer's own compression fittings and careful handling during stringing to avoid damaging the core.

The ACCC conductor shall comply with ASTM B857 or EN 50540 for conductor construction, stranding and lay ratios. The composite core shall comply with ASTM B987/B987M and shall be tested in accordance with IEC TS 62818-1. The aluminium strands shall be trapezoidal (TW) wires of fully annealed 1350-O aluminium complying with ASTM B609, with a minimum conductivity of 63% IACS. The aluminium shall be of the highest purity commercially obtainable and shall not be less than 99.5%. The Contractor shall submit

certificates of analysis giving the percentage and nature of impurities in the metal from which the wires were made. The outermost layer of the conductor shall be right-handed lay (Z-lay). There shall be no joints in the individual wires of the outer layer of aluminium wires.

The composite core shall be a single solid rod consisting of a carbon fibre center within an outer layer of glass fibre, bonded in a high-temperature epoxy resin matrix. The glass fibre layer shall be of sufficient thickness to fully isolate the carbon fibre from the aluminium strands and prevent galvanic corrosion. The core shall be supplied in continuous lengths with no joints or splices in any manufactured length of conductor. The core and aluminium strands shall be suitable for continuous operation at a conductor temperature of not less than 180 °C without loss of mechanical strength, permanent elongation or degradation of the resin matrix. The Contractor shall submit the core manufacturer's certificates showing compliance with ASTM B987/B987M for tensile strength, glass transition temperature, and flexural and torsional properties. The Contractor shall also submit evidence that the conductor manufacturer is licensed by the core supplier.

Unless specified to the contrary, the conductor shall be supplied ungreased. Electrical joint compound shall be applied to the aluminium strands within all compression dead-ends, joints and repair sleeves in accordance with the conductor manufacturer's installation instructions.

Table 2: Conductor types, specifications and associated standards.

NO	Line	Conductor Type	Conductor size
1.	132KV Juja - Naivasha Line, Escarpment	ACSR 175mm^2"Lynx"[1]	175 sq mm
2.	132KV Lanet - Lessos Line, L. Nakuru, National Park	ACCC 273.6mm^2 "Casablanca"[2]	273.6 sq mm
3.	❖ KP1/13D/4/1/TSP/06/022-3 - ALUMINIUM CONDUCTORS STEEL REINFORCED (ACSR) Part 3: 175 mm2 (BARE) - **SPECIFICATION Dated 2025-06-30** ❖ KPI/13D/4/1/TSP/06/019- ALUMINIUM CONDUCTOR COMPOSITE CORE (ACCC) - **SPECIFICATION Dated 2024-01-09**		

Table 2: Technical details of Power Conductors (Lynx and Casablanca)

NO	TECHNICAL DATA	LYNX (ACSR)	CASABLANCA (ACCC)
1	Nominal section	175mm^2	273.6mm2
2	Conductor strand	30/7 (2.59mm)	20/1(Composite core diameter-7.11mm)
3	Tolerance of diameter:		
	Aluminium	± 1.0%	± 1.0%
	Steel	± 2.0%	N/A
	Carbon Core	N/A	± 1.0%
4	Calculated section		
	Aluminium	158.1mm^2	273.6 mm2
	Steel	36.88mm^2	N/A
	Carbon Core	N/A	39.7 mm2
	Total	194.9mm^2	313.3 mm2
5	Outside diameter	18.13mm	20.5mm
6	Unit weight of conductor	842kg/km	832.2 kg/km
7	Rated Strength	69.2kN	101.1kN
8	DC resistance at 20 deg. C	0.183 Ohm/km	0.1024 Ohm/km
9	Approximate current carrying capacity	406A	1174A @180^0
10.	Specification and GTP document	Annexed	Annexed

Conductor Sag Design

Sags shall be computed under the following conditions:

Most severe design conditions -	Max. wind pressure under min temperature
Max. wind pressure on conductor	385 N/m^2
Max air temperature	36^0 C
Min. air temperature	10^0 C.
Min. conductor temperature	0^0 C
Max. Conductor temperature (continuous loading)	75^0 C
Max. Conductor temperature (fault conditions)	200^0 C
Average conductor temperature	35^0 C
Factor of safety	
- Max. Working tension to UTS	more than 2.5
- Everyday stress to UTS	more than 5.0
Young's modulus of aluminium	6,300kg/mm^2
Young's modulus of steel	21,000kg/mm^2
Linear expansion coefficient	17.8/^{0}C x 10^{-6}

DRUMS

The conductors shall be supplied on impregnated drums of approved materials constructed so as to enable the conductors and earth wire to run smoothly and those as spare materials shall be supplied on steel drums of approved materials for storage for long duration. Length of conductors on one drum shall not be less than 2,000m. Actual conductor lengths shall depend on stacking chart stringing sections and drum schedule so prepared shall be submitted for approval.

JOINTS AND REPAIR SLEEVES

Tension joints of the conductors shall be of compression type and shall be free from slipping off, causing damage to or failure of the complete conductors, earth wire or any parts thereof at loads less than 95 per cent of the ultimate breaking strength of the conductors and earth wire.

Electrical conductivity and current carrying capacity of the tension joints for the power conductors shall not be less than those of equivalent length of the conductors.
The cut ends of steel wires and steel component inside the joint shall be protected from the weather in an effective and permanent manner.

Aluminium sleeves shall have plugholes for injecting compound.

All tension joints shall be supplied with aluminium fool proof gauges or anti-displacement pins for correct positioning, adequate quantity of filling compound in injectors and aluminium collars for gap filling.

Full details of the joints including an illustration of practices for filling the air gap between sleeves, method of correct positioning of steel sleeves, gauges for ascertaining the compressed size, etc. shall be submitted with the tender.

Repair sleeves for the power conductors shall be of the compression type and the conditions stated above for the tension joints shall apply to the repair sleeves where applicable.

Accessories for Power Conductors and Earth wire

In order to prevent fatigue of power conductors and earth wires due to repeated vibrations caused by breeze, the following countermeasures shall be applied.

a) Trunnion type suspension clamps
b) Vibration dampers
c) Armor rods.

Trunnion type suspension clamps

Suspension clamps shall be of trunnion type, made of aluminium alloy and as light as possible. They shall be designed to avoid any possibility of deforming the stranded conductors and earth wires and of separating the individual strands and shall be free to pivot in the vertical plane containing the conductors and earth wires.

Suspension clamps except jumper suspension sets shall have a suitable dimension for clamping the conductor with preformed armor rods; and shall not permit the complete conductor with armor rods to split at load less than 2,250kg for ACSR. Particular attention shall be paid to the elimination of corona emission from all parts of the suspension clamp.

Vibration Dampers

Vibration dampers shall be of Stockbridge type for both conductors and earth wire. The dampers shall be applied in all conductors and earthwires in every span except slack spans into the substations. The dampers shall be designed to be attached to the conductors and earthwire in a manner, which will prevent damage thereto and free drop of the weight in service. Clamping bolts shall be provided with domed self-locking nuts designed to prevent corrosion to the thread.

The nominal weight of damper shall be 5.3 pounds (2.4kg) for the conductors and 4 pounds (1.81kg) for the earthwire. The numbers of the dampers to be installed per span shall be:

a) 2 pieces per conductor or earthwire for spans up to 600 m and,
b) 4pieces for the spans longer than 600 m.

First and second dampers will be positioned at 1.1m and 2.2m for power conductors and 0.6m and 1.2 m for earthwires respectively from the centre of suspension clamps or from the mouth of tension clamps.

Armour Rods

Preformed armour rods shall be applied to all suspension points of the power conductors except jumper suspension points.

Suspension clamps for those conductors protected by armour rods shall be suitable for the enlarged conductors.

CORONA AND RADIO INTERFERENCE

The design of all line conductor fittings, vibration dampers, etc., shall avoid sharp corners or projections which would produce high electrical stress in normal working. The design of adjacent metal parts and matching surfaces should be such as to maintain good electrical contact under service conditions. Particular care shall be taken during manufacture of conductors and fittings and during subsequent handling to ensure smooth surfaces free from abrasion.

SECTION 8

OPTICAL FIBER GROUND WIRE

TECHNICAL DESCRIPTION

The Transmission line earth wire integrating optical fiber shall be of design and construction to ensure long service with high economy and low maintenance costs. It shall be suitable in every respect for continuous operation at nominal parameters as well as in transient operating conditions under the climatic conditions peculiar to the site.

The OPGW shall incorporate at least 48 optical fibers. The fiber optic earth wire shall comprise an optical sub-unit containing optical fibers over which shall be laid aluminium, aluminium alloy or aluminium coated steel strands. The clad steel wire incorporated in fiber optic earth wire shall comply with the requirements of IEC 61232. Shaped aluminium or aluminium alloy wire sections shall conform to the requirements of the appropriate IEC standard. Other OPGW types are acceptable if the required performance characteristics are met.

All materials used shall be of the best quality and workmanship, and shall be of the highest class throughout with the designs and dimensions of all parts such that the stresses to which the OPGW are subjected to shall not render them liable to distortion or damage under the most severe conditions encountered during installation as well as in service.

Special attention shall be paid to the OPGW stranding process to ensure the necessary tightness between different layers in order to avoid slippage or relative movement of strands or cage formation during stringing.

Stranding tolerances as well as inspection and testing shall be as per IEC 61089 as far as applicable, and to the respective manufacturing standards.

The OPGW manufacturer shall have ISO 9001 quality assurance system certified and shall prove a minimum experience in successful supply of similar OPGW in the last 5 years.

The OPGW installation shall include all cable fittings (tension and suspension spirals, vibration dampers, earth connection etc.), joint boxes, termination boxes, fiber connectors and other accessories required for a complete working fiber link. The earth wire fittings and optical joint boxes shall be type approved.

The optical sub-unit shall withstand the temperature rise associated with the specified lightning fault current flowing in the earthwire without damage. The fiber optic earthwire (OPGW) shall be manufactured in continuous lengths of appropriate lengths to keep joints to a minimum.

The overall system design of the fiber optic system shall meet the following minimum requirements:

a) Single failure or degradation in any optical fiber not more than one year averaged over five years;

b) Failures or degradations affecting more than one optical fiber, not more than one in ten years;

c) Increase in optical system transmission attenuation due to accumulated ageing and other effects at the end of five years, not more than 0.05 dB/km.

Optical fiber parameter and performance

The OPGW, access cables and underground cables shall have at least 48 (forty-eight) single mode optical fibers with following characteristics:

- Transmission wavelength: 1310 nm and 1550 nm
- Mode field diameter: 9.0 to 11.5 micrometers (μm), including tolerances
- Optical cladding diameter: 125 μm ± 2.0%
- Cable Attenuation: not greater than 0.40 dB/km for every fiber in every drum at optical wavelength of 1310 nm; and not greater than 0.25 dB/km for every fiber in every drum at optical wavelength of 1550 nm
- Joint attenuation: not greater than 0.1 dB at optical wavelength of 1310 nm and not greater than 0.2 dB at 1550 nm for every fiber, measured on the fully installed joint
- Total dispersion: not greater than 3.5 ps/km.nm at optical wavelength of 1310 nm and not greater than 19.0 ps/km.nm at optical wavelength of 1550 nm
- Core numerical aperture: less than 0.23
- Life span: greater than 30 years

The Contractor is required to supply a graph of attenuation versus wavelength over the range of 1200 nm to 1600 nm

No joints shall be allowed in any fiber in any drum length.

Discontinuities will be acceptable if:

- Less than 0.10 dB in magnitude measured at 1310 nm, and
- OTDR traces from both ends of the cable at 1310 and 1550 nm wavelength show a difference of less than 0.05 dB/km for every fiber in every drum.
- Power Meter & Light source. The test shall be used to verify that the measured loss is in average equal or less than the calculated link budget.

The Contractor shall state the refractive index of the optical fibers at 1310 nm and 1550 nm.

Table 3: OPGW Mechanical Properties

MECHANICAL PROPERTIES		
NO	**PARAMETERS**	**SPECIFICATION**
1	Number of Cores	48
2	Cable diameter	< 10.5 mm
3	Cable weight	< 360 kg/m
4	Rated Tensile strength RTS	≥ 60kN
5	Working tensile (40% RTS of item 3)	≥ 24kN
6	Every day working tension	20% RTS
7	Elasticity coefficient	14276 kgf/mm²
8	DC resistance	≤ 1.0 Ohms/km
9	Short circuit current capacity	≥ 4.8kA
10	Thermal expansion Coefficient	0.000014 1/K
11	Initial temperature value of short circuit	40°C
12	Failure time value	1s
13	Matching conductor wire type	Aluminum Clad Steel
14	Conductor cross section	≥ 55mm^2 (metallic cross section)
15	Mode Field Diameter	1310nm and 1550nm
16	Optical cladding diameter	125 µm ± 2.4%
17	Cable Attenuation	≤ 0.38 dB/km for every fibre in every drum at optical wavelength of 1310nm; and not greater than 0.22 dB/km for every fibre in every drum at optical wavelength of 1550
18	Joint attenuation	Not greater than 0.1dB at optical wavelength of 1310 and not greater than 0.2 dB at 1550 nm for every fibre, measured on the fully installed joint
19	Total dispersion	Not greater than 3.5ps/km.nm at optical wavelength of 1310nm and not greater than 19.0ps/km.nm at optical wavelength of 1550nm
20	Core numerical aperture	Less than 0.23
21	Life span	Greater than 30 years
22	Acceptance Tests	As per IEC 60794 – 4 – 10
23	Marking details	

OPTICAL FIBERS

Optical fibers shall be single mode fiber and shall conform to IEC 793-2-BI.

The fiber coating material shall be mechanically strippable. The optical fibers shall be capable of being jointed by fusion technique.

There shall be no measurable long term or short-term optical attenuation change due to the temperature rise associated with a fault current flowing in an earth wire, or a lightning strike on the earth wire.

OPGW FITTINGS

The fiber optic earth wire shall be with approved conductor fittings. The application of these fittings shall not damage the earth wire or fibers, either mechanically or optically.

At each support, a bypass device shall be provided to guide the cable around the earth wire fittings associated with the support.

OPTICAL JOINT BOXES

Optical joint boxes shall be provided to protect the splice joint of optical fibers, either when individual lengths of the fiber optic OPGW, are jointed or between the fiber optic earth wire and the underground fiber optic cable.

The joint boxes shall consist of external steel or die cast aluminium housing providing protection to IEC 529 IP 44 and an internal die cast aluminium or high impact plastic ABS box to IEC 529 IP54

The external housing shall be designed so that the rainwater is directed away from the door and there shall be no water ingress when the door is opened.

The joint boxes shall be supplied complete with all fittings to secure and seal the cable in the gland plates or blank the unused spigots. The cable cleats to secure the fiber optic OPGW or underground cable shall be fitted inside the box. The cleats shall not have a detrimental effect on the performance of the optical fibers when tightened to the recommended torque.

The top and bottom of the joint box shall be vented and the vents provided with the vermin shields.

The box shall be supplied complete with internal splice cassettes to accommodate the required number of splices. The glands shall be fitted to accommodate either the fiber optic OPGW or underground fiber optic cable.

FIXING CLAMPS

A bolted clamping system shall be used to attach the OPGW to the inside of the support, without drilling or modifications to the support steel work.

The attachment clamps shall be capable of being attached and detached from the support, without affecting the OPGW.

MATERIALS

Fiber optic earth wire materials
External aluminium, aluminium alloy or aluminium coated steel strands.

Optical Joint boxes
Optical joint boxes shall be made from either a suitable grade of aluminium alloy complying with the requirements of BS 1490 and / or BS EN 1676 or steel complying with requirements of BS 3100

Fixing Clamps
Fixing clamps shall be made from a suitable grade of aluminium alloy complying with the requirements of BS 1490 and / or BS EN 1676. Bolts shall be made from mild steel grade S275JR to BS EN 10 025. Bolts and nuts shall be ISO Metric Black Hexagon to BS 4190 and shall unless otherwise specified be threaded ISO Metric Coarse Pitch to BS 3643: Part 2, Tolerance Class 7h/8g.

PROTECTIVE TREATMENT

Fiber optic earth wire
Where two layers of wire strands are provided over the optical sub-unit, the external surface of the optical sub-unit and the inner strand layer shall be greased, using approved conductor grease.

Ingress of Moisture
The cable shall be capped before shipment to prevent the ingress of water.

Optical Joint boxes
Optical joint boxes (steel exterior) shall be hot dipped galvanized after manufacture to meet the requirements of BS 729/ISO1460.

INSTALLATION

General

The supplier of the OPGW shall be responsible for the supervision of installation by the Contractor; to ensure that system reliability requirements are met.

Workmanship

The Contractor shall ensure that the fiber optic cable are not strained or damaged either mechanically or optically during stringing and/ or jointing.

Fiber optic joints

Optical fiber joints in the OPGW, or between the OPGW and the non-metallic underground fiber optic cable, shall be housed in optical joint boxes. The joint boxes shall be located immediately above the anti-climbing device for convenient access by technical personnel. All joint boxes shall be earthed to the support steel work using approved multi-wire / multi-strand flexible aluminium earth bond.

TERMINAL EQUIPMENT

The All fibers of the OPGW shall be terminated at an Optical joint box provided on the terminal tower by the contractor. Lead in cable shall be provided at the substations by the employer, to connect the OPGW to the terminal equipment.

Scope of Work

The Contractor shall include detailed system design, manufacture, supply, installation, testing, commissioning, remedying of defects, maintaining the works during the defects liability period and any incidental work necessary for the proper completion of the work in accordance with this contract.

The existing lines already has an optical fiber earth wire. The Contractor shall open this connection, and complete the OPGW link

Detailed requirements are as follows:-

- System design – The system design and preparation of Contractor's drawings for approval of the Engineer
- Supply and installation of fiber optic cable including mounting hardware and splicing
- Factory testing of the OPGW prior to delivery.
- Testing and commissioning of the systems up to the terminal joint box at adjacent substation

QUALITY CONTROL

FATs shall be carried out for the OPGW. During the attendance, the Contractor shall give the Employer's persons a brief explanation on design, manufacture, operation and maintenance of the materials and equipment.

Types of Tests

Type, sample and routine tests shall be undertaken on the OPGW, their associated fittings, non-metallic underground fiber optic cable and optical fibers in accordance with the requirements of specification, CCITT G652, IEC 793 and IEC 794 as appropriate.

OPGW Tests

a) **Fatigue**

The Contractor shall submit documentary evidence to show the fatigue life of the OPGW including that of the optical sub-unit compared to that of a conventional conductor of similar characteristics e.g. diameter, mass, stranding etc.

b) Stress-Strain

A sample of OPGW not less that 10m length, complete with the proposed end fittings shall be subject to a stress-strain test. The test shall be undertaken in accordance with IEC 1089 Annex B and the measuring techniques in accordance with IEC 794-1-E1.

c) Tensile performance

The test shall be undertaken in accordance with the load conditions specified in IEC 1089 Annex B and the measuring techniques in accordance with IEC 794-1-E1.

d) Crush and Impact

The test shall be undertaken in accordance with the recommendations of IEC 7941-1-E3 and IEC –794-1-E4.

The crush test shall be undertaken by applying a 10kN load for 1 minute to the OPGW via two 50mm x 50 mm flat plates.

The impact test shall be undertaken by dropping a 4 kg weight from a height of 150 mm onto the end of a 20mm diameter steel mandrel placed on the OPGW. These should be done 20 times.

e) Temperature cycling

The optical performance under temperature cycling shall be tested in accordance with IEC 794-1-F1 with specified temperature ranges for a duration of 4 hours. The test should be undertaken twice.

f) Water Ingress

The optical sub-unit shall be tested for water ingress in accordance with IEC 794-1-F5

g) Fault Current

A sample of OPGW not less than 2 metres in length shall be subjected to a fault current pulse. The test shall be performed twice with an interval of 30 minutes between tests. After the second impulse the OPGW shall be dismantled and the optical cable examined throughout its length for any signs of deterioration.

h) Lightning Strike

Tests shall be carried out to verify the effectiveness of the OPGW to withstand the effects of a lightning strike. The test shall consider both an initial stroke and a follow through. The test shall be carried out on a sample of OPGW not less than 2 metres long. The acceptable criteria shall be that earthwire' calculated residual strength is not less than 90 percent of the original stated ultimate strength.

Optical Fibers

Optical fibers shall be tested in accordance with the requirements of IEC 793.

Optical joint Boxes

Optical joint boxes shall be visually inspected to ensure they meet the specified requirements.

Non- metallic underground Fiber Optic cable

Non-metallic underground fiber optic cable and the optical fibers shall be tested in accordance with the requirements of IEC 793 and IEC 794 as appropriate.

Fiber Optic cable

All fiber optic cables shall be tested prior to dispatch using an OTDR on each fiber and other tests detailed in this document.

Test Certificates

Test records, covering type and sample tests shall be provided.

SECTION 9

LINE INSULATION

The transmission line for the project is aligned on an elevation level of 2000m above sea level. The area has high humidity levels, tropical sunshine and prone to medium to heavy pollution by agricultural and industrial activities.

Silicon-rubber long-rod type Composite Insulators of the approved type shall be used to support the power conductors of the Transmission line. All insulator units will be composed of top and bottom arcing rings to equalize the voltage distribution over the insulator. The top shed of the insulators shall also have a larger diameter to prevent waste from birds and animals tracking down along the insulator.

INSULATORS DESIGN

The insulator units shall be designed to withstand the design service voltages including lightning, switching and power frequency, the mechanical loads relevant to the installation-service-maintenance conditions, the service temperature and environmental effects. Internal stresses due to expansion and contraction of any part of the insulator unit shall not lead to deterioration.

The insulators should withstand wind pressures of up to a maximum of 385N/ m^2.

The design of insulator units shall be with end over mould or such as to avoid local corona formation and no significant radio interferences shall be exhibited. The long rod Insulator units shall comply with the requirements of **IEC 61109.**

FITTINGS

All fittings to make each composite insulator set complete for beneficiary use shall be supplied and included in the rate for each insulator unit. Such bolts, nuts, washers, cotter pins and retaining pins with necessary spares as may be necessary for the use for erection shall be deemed to be included in the appropriate items.

Ball and socket couplings shall be in accordance with the requirements of IEC 60120/16. Sockets shall have “R” type security clips in accordance with the requirements of IEC 60372.

Clevis tongue couplings shall be in accordance with the requirements of IEC 60471.

All ferrous fittings shall be made of steel, ductile iron or malleable iron hot dip galvanized, and shall have sufficient strength for abrasion and weariness produced by repeated vibration. Cotter pins shall be made of non-ferrous metal or stainless steel and designed as the self-locking type.

The arcing ring shall be provided for the top and bottom of each insulator string and shall be of such design and shape that it reduces the voltage across the part of the insulator adjacent to the conductor for each insulator string, to a value which prevents visual corona formation on the metal caps and pins of the insulators and shall minimize the Radio / Video interference voltage from complete insulator and hardware assemblies when operated at the voltage up to 420 KV.

The arcing rings shall be of such design that when added to suspension and tension assemblies, the resulting flash-over values of the complete insulator string shall not be reduced below the percentage indicated hereunder, of corresponding flash over values with the rings omitted.

The percentages are:
a) Wet 50 Hz: 100%
b) 1.2 / 50 Impulse: 96%

The rings shall be of hot dip galvanized steel or Aluminium tube having outside diameter as required for corona control and minimum thickness of 2.5mm. Both inner and outer surfaces shall be galvanized to the required specifications (BS 729/ISO 1460). The details of the rings, brackets and methods of mounting shall be of such design that the rings may be readily replaced under 'hotline' maintenance.

The horizontal distance between corona rings at suspension rings at suspension insulator strings shall be kept as small as practicable to accomplish the required reduction in Radio/ Video Interference (RVI).

All the accessories and the fitting offered against this specification shall be subjected to corona test. The corona shall not take place and shall extinguish at the voltages specified i.e. when a voltage of the specified value applied (Phase to Neutral i.e. RMS) the corona shall appear and shall disappear again at the specified value of voltage.

Pollution

The design of insulator units should take into account the principles contained in the IEC 60815 for heavy pollution environment. For this project the minimum creepage value of 31 mm/kV shall be applied (Creepage distance of 4495 mm).

Zinc Collars

The insulator unit cap and pin shall be fitted with zinc-collared pins to prevent cracking due to pin corrosion caused by the effects of pollution and high humidity in the project area.

Insulator Protective Device

The design of insulator fittings including corona shields shall comply with the following requirements:

a) Shall effectively protect the insulator unit and fittings from damage caused by power arcs.
b) Shall effectively improve the voltage distribution along the insulator unit;
c) Shall effectively improve the corona performance of the insulator unit.
d) Shall be designed in such a way as not to subject to breakage fatigue due to wind induced vibration;
e) Shall withstand the specified mechanical load
f) Shall be suitable for live line maintenance

Materials

The silicon rubber composite insulator shall comply with requirements of **IEC 61109.** The tension bearing material shall be E-CR Fiber Glass and the housing and sheds made of HTV silicone rubber.

Insulator caps and pin bases of malleable cast iron shall be manufactured from a suitable grade of MCI complying with the requirement of BS EN 1563 for spheroidal graphite or BS EN 1562 for white heart and peralitic.

Insulator end fitting of forged or cast aluminium alloy shall be manufactured from a suitable grade of aluminium alloy complying with the requirements of BS 1472 or BS 1490 and/or BS EN 1676 respectively.

Security '**R**" clips shall be of phosphor-bronze composition in accordance with the requirements of BS 2870 and supplied in the half-hard condition with a minimum harness of 155 VPN

Zinc collars shall have a total impurity not greater than 0.05 percent and shall comply with the requirement of BS EN 1179.

All insulator caps, bases and pins shall either be inherently resistant to atmospheric corrosion or a suitably protected against corrosion, such as may occur in transit, storage and in service. All ferrous parts which will be exposed to the atmosphere in service, except those made in the appropriate grade of stainless steel, shall be protected by hot-dipped galvanizing to comply with the requirements of BS 729/ISO1460.

TESTS

Type, sample and routine tests shall be undertaken on the insulator units in accordance with the IEC 61109.

MINIMUM CLEARANCES

Minimum Clearance of Live Parts to Towers for 132Kv shall be As Appendix 1.A.6

SECTION 10

TOWERS

TYPE OF TOWER

Towers shall be self-supporting and broad base galvanized steel lattice type with body and hillside extensions. The hillside extensions shall be applied for tower legs on the slope so that legs are suited to the original slope of tower site and also that excessive land cutting around foundations and land collapse is prevented.

The following tower types shall be designed for the project in order to meet various tower positions and loadings economically.

a) Type-S: Use at positions of line suspension or slight angle up to 2 degrees of horizontal angle deviation with suspension insulator sets.

b) Type-H: Use at positions of line termination or heavy angle up to 60 degrees of horizontal angle deviation with tension insulator sets.

c) Type-T: Use at positions of line termination or 90 degrees of horizontal angle deviation with tension type insulator sets.

TOWER DESIGN GENERAL ARRANGEMENT

Design of the towers shall be done by the contractor. They shall be designed to resist the specified ultimate system loading. Clearances between live parts and supporting steelwork and between the phase conductors and ground or other obstacles shall be as specified.

All tower designs shall be such as to facilitate inspection, painting, maintenance, repairs and operation with the continuity of supply being the prime consideration.

The design shall be such that the number of different parts shall be as few as possible to facilitate transport, erection and inspection. The maximum weight of the heaviest single member should be limited to that within the normal lifting capability of the proposed erection equipment.

Main leg members of lattice steel towers shall be formed of the maximum single lengths, appropriate to the body or leg extensions and shall not without the Employer’s approval incorporate additional spliced sections.

For lattice steel towers a fully triangulated system of bracings shall preferably be adopted. If full triangulation is not adopted, the overall stability and secondary bending stresses must be considered in the design.

Where fabrication processes employed adversely affect the material properties, or introduce zones of high stress concentration the overall design of the structures shall take such factors into account.

Cross-arms shall be so arranged that they can be disconnected in the plane of the longitudinal face of the support without disturbing any members forming part of the support body.

The cross-arms should be designed to take and be compatible with the Live Line maintenance tools and equipment.

Appropriate bird guard protective devises shall be installed to keep away birds from roosting directly over the insulator units.

Height of Towers

Height of towers shall be determined in the under-mentioned way:

$H = G_c + S_g + L_i + H_c + H_g$

Where;

- H = Total height of tower.
- G_c = Necessary ground clearance of power conductors above ground or other objectives.
- S_g = Maximum conductor sag
- L_i = Length of a suspension insulator set, but nil for a tension type towers.
- H_c = Vertical spacing of upper conductor cross -arm spacing
- H_g = Vertical spacing between upper conductor cross-arm and overhead earthwire.

Towers shall be provided with body extensions in a 3 m step to a standard height for maintaining necessary conductor ground clearance mentioned in **APPENDIX 1.A.2** on various ground profiles. In addition to the body extensions, each leg will have hillside extensions in a 1 m step to suit for the original ground slope and ensure that cutting ground to level setting will not be used. Standard tower structures are shown in **APPENDIX 1.A.1** as well as insulation clearance diagram of conductors.

Design Span (adopt existing spans in this tender)

The design of all towers shall provide for the following basic, wind and weight spans:

Type of Tower	H	T
Basic span (m)	350	350
Wind span (m)	350	350
Weight span (m)	1,200	1,200

Uplift Weight (m) -300 -300

The term basic span means the horizontal distance between centres of adjacent supports on the level ground which the height of standard towers is derived with the specified conductor clearances to ground in still air at maximum temperature.

The term wind span means half the sum of adjacent horizontal span lengths supported on any one tower.

The term uplift weight means the weights of conductors and overhead earthwire supported upwards at any one tower for reinforcing strength of cross arms.

Design Loads

Structural loading shall refer, ASCE Manual and Report on Engineering Practice No. 74 - 1991 "Guidelines for electrical transmission line structural loading".

The following loads shall be applied in the design of towers:

a) Wind Loads
b) Maximum working Tensions of Conductor and earth wire
c) Vertical Loads
d) Horizontal Angle Effect

Design Conditions

(a) Assumed Normal Loading Condition:

The assumed maximum simultaneous working loading on towers shall be as follows:

(i) Vertical loads : as above-mentioned.

(ii) Transverse loads : wind loads, horizontal angle deviation effects

(iii) Longitudinal loads : wind loads and erection loads but together with maximum working tensions of power conductors and overhead earthwire for their termination for Type-T tower.

(b) Assumed Broken-Wire Condition:

Under the condition, any one-power conductor or an earthwire is assumed broken at their maximum working tensions in addition to the loads under the normal condition.

(c) Factor of Safety:

The following factors of safety for tower structures shall be applied in the design.

(i) More than 2.5 for the synthetic maximum load under the normal loading condition.

(ii) More than 1.5 for the synthetic maximum load under the broken-wire condition.

Those factors of safety shall be proved under tower loading tests on the proto-type towers in the manufacturer's testing station, and there should be no failure or permanent distortion during the tests when 100% factored loading is sustained for five minutes.

Design of Towers

Latticed or monopole steel structures shall be designed with geometric configurations based on structural strength, electrical, economic, and safety requirements. Member forces caused by the design-factored loads shall be determined by established principles of structural analysis.

Each type of towers shall be designed so that no failure or permanent distortion shall occur when tested with applied force equivalent to 2.5 times the maximum simultaneous working loadings specified in the Clause 10.2.4 [Normal Working Loading] and also equivalent to 1.5 times the maximum simultaneous working loadings resulting from the assumed broken wire condition. Design loads shall consider:

a) Minimum legislated levels
b) Client specifications including factors of safety,
c) Expected climatic conditions,
d) Line security provisions,
e) Design life of not less than 50 years,
f) Construction and maintenance operations.

The ultimate design stress, obtained from the working stress multiplied by the factor of safety of 2.5 under the normal condition and 1.5 under the broken wire condition, in tension members shall not exceed the yield point of materials. The ultimate design stress, obtained from the working stress multiplied by the above mentioned factor of safety, in compression members shall not exceed a figure obtained from an approved formula to be entered in Tender based on the yield point of materials. Alternately, formulas in the American Society of Civil Engineers standard for the design of self-supporting latticed steel transmission structures ASCE 10- 97 and ASCE Manual and Report on Engineering Practice No. 74 guidelines for electrical transmission line structural loading shall refer.

Tower design report shall consist of full structural analysis report showing correctness of dimensional detail calculations, tower profile/layout drawings, shop detail drawings, erection drawings and bills of materials. Shop detail drawings shall be approved by the producing utility Engineer of Record (EOR) regarding compliance with the purchaser's specifications and the strength requirements of the design.

Designed tower full scale prototype proof test to BS EN 60652: 2004 loading tests on overhead line structures shall be conducted and approved before tower materials shop production and delivery to site.

Materials and Fabrication

The towers shall be fabricated with mild and/or high tensile steel of the finest quality or other approved materials, of which mechanical properties shall comply with BS EN 10025 or BS EN 10210 as appropriate or Grade Fe 430/275N/mm^2 and Fe 510 /355N/mm^2 specified in ISO 630-1980, BS 5950-1/2 or equivalent.

No member of the tower shall be less than 12 mm in thickness and 60 mm in width of flange for leg members of towers and main members of the cross-arm, and 6 mm and 50mm for the web and nominal members respectively.

The slenderness ratio shall not exceed 150 for the leg and arm members, 200 for the web members and 250 for the nominal members as compression member and 350 for tension only member.

All the connection shall be made by mild and/or high tensile steel bolts and nuts. No bolt shall be less than 12 mm in diameter and grade 6.8. All bolts and nuts shall be provided with approved spring washers. Antitheft bolts shall be used from ground level to the tower anti-climb level.

Bolt holes shall not be more than 1.5 mm larger in diameter than the corresponding diameter of bolts. Holes shall be drilled for the members not less than 13 mm in thickness. For the members having thickness below 13 mm, holes may be drilled or punched, but the former is preferred.

All the steel members should have clearly identifiable part numbers which enable quick identification of similar parts. The letters ***'KPLC'*** should also be inscribed on each bracing-by punching or any other suitable method, with more than one inscription for parts of length greater than 0.5m.

All burrs shall be removed completely by reaming and smoothing before hot-deep galvanizing.

Tower Accessories

The following accessories shall be provided for every tower.

(i) **Anti-climbing device and climbing steps**: All towers will be provided with the anti-climb device on each leg at the height of 3 m to 5 m above the highest ground level at all tower locations. The device installed on the step-bolted legs shall be provided on all towers. Gates shall be designed to open upwards only and shall be secured with galvanized bolts and nuts. No padlocks are required.

Each tower shall be provided with step-bolts of an approved type on diagonal sides of the tower at a spacing no more than 380mm, starting immediately above the anti-climbing device and continuing to the earth wires.

Holes for removal step-bolts below the anti-climbing guards shall be provided at not more than 380mm centres on the step legs.

(ii) **Danger, Number and Helicopter patrol plates**: Danger plate which shows warning sign for tower climbing of other people than maintenance crew will be provided on all towers.
Number plates which show tower number set serially from the previous tower in ascending/descending sequence.

All plates shall be of anti-corrosive material. If enameled iron plates are used, the whole surface of each plate including the back and edges shall be properly covered and resistant to corrosion. On all plates the colours shall be permanent and free from fading. With enameled plates, washers or fiber or other approved material shall be provided back and front of the securing bolts.

(iii) **Tower Earthing**: No separate earth conductor from top to bottom of towers is required and earthing continuity will therefore depend on surface contact between bolted members.

All structures shall be provided with means for connecting earthing devices at or around nominal ground level, on each leg and for connecting earth wire bonds to each top cross-arm or earth wire peak.

Each leg of towers will have an earthing rod underneath its foundation to act as basic grounding required by good transmission line Engineering. Basic grounding shall be constructed in such a way that isolation from the tower and concrete foundation is possible to allow earthing survey if required during line service life.

Maximum earthing resistance of a tower is targeted on **10 ohms**, and in case of higher resistance than 10 ohms, additional horizontal counterpoise earthing system will be added in the ground longitudinally to the line route with more than 50 cm depth. The rate entered in the schedule of prices shall include for all necessary fittings and shall be adjusted at the variation rate for increased or reduced fittings.

(iv) **Aircraft Warning Devices**: Due to the activity of aircraft in the vicinity of certain parts of the transmission line, it shall be necessary to mount warning spheres on earth wires at some locations. Aircraft warning spheres shall be capable of being clamped securely to overhead earth wire. The sphere itself shall be of plastic or fiberglass construction of at least 0.5m in diameter and coloured orange or yellow as required by local regulations. The Contractor is to enter rates against appropriate item in the schedule of prices for the above and he will be advised early in the contract of actual requirements.

(v) **Bolts:** Where appropriate all metal parts hall be secured with bolts and nuts with single spring washers. When in position the bolts shall project through the corresponding nuts by at least three threads, but such projections shall not exceed 10mm. No screwed threads shall form part of a shearing plane between members.

In order to safeguard the tower members from theft; special anti-theft bolts shall be applied from ground level up to the anticlimb. The bolts shall be approved by the Employer. The bolts are of the type that shears once the full torque has been applied.

The nuts of all bolts attaching phase conductor insulator set, earth wire sets, maintenance brackets/plates shall be locked in an approved manner preferably by locknuts.

The bolts of any one diameter in a tower shall be one grade of steel 8.8. Leg members shall be joined in such a way that electrical continuity is maintained to ground.

(vi) Rectangular and Auxiliary Cross Arm

The type H, and T towers may be provided with rectangular arms where horizontal angle exceeds 45 degree.

The prices of the rectangular arm set shall be included in the prices for the towers.

MATERIALS

All steel shall comply with BS EN 10025 or BS EN 10210 as appropriate, unless otherwise specified and shall be suitable for all the usual fabrication processes, including hot and cold working within the specified ranges.

The quality of finished steel shall be in accordance with BS EN 10163. All steel shall be free from blisters, scale, laminations, segregations and other defects. There shall be no rolling laps at toes of angles or rolled-in mill scale.

Unless specified to the contrary the following grades of steel shall be applicable:

a) Mild steel shall be grade S275JR.

b) High tensile steel shall be grade S355JR for sections less than 20 mm thick and S355JO for sections greater or equal to 20mm thick, except for plates, which shall be greater or equal to 40mm thick.

WORKMANSHIP

All steel lattice members shall be cut to jig and all holes in steelwork shall be drilled or punched to jig using CNC machine. All steel parts shall be carefully cut and holes located so that when the members are in position the holes will be opposite each other before being bolted up. The drilling, cutting, punching and bending of all fabricated steelwork shall be such as to prevent any possibility of irregularity occurring which might introduce difficulty in the erection of structures on site. High tensile steel members shall be bent hot. Care shall be taken not to punch holes too close to the edge of members.

Means shall be provided to enable the Employer to carry out such checking of members, as he may consider necessary. Built-up sections, when finished, shall be true and free from all kinks, twists and open joints and the materials shall not be strained in any way.

In order to check the workmanship, not less than 1 per cent, of the members corresponding to each type of tower or cross-arm shall be selected at random and assembled to form complete latticed supports or cross-arms in the presence of the Employer representative at the manufacturer’s works.

SECTION 11

FOUNDATIONS

General

Concrete pad and chimney type foundations will be applied to the towers, the design of the concrete foundations of the towers shall be performed based on the requirements and assumptions set out below, and the details of the design and drawings for each type of foundations shall be submitted for approval.

Such design of foundations for the towers are subject to modifications to suit the site conditions as indicated in writing by the Engineer during execution of the Contract without any price adjustment of the items of the foundation stubs and foundations.

Concrete Block Foundation

Prior to determination of the type of foundation to be used, the contractor shall carry out geotechnical investigations to BS 5930 and BS 1377 to establish field ground conditions.

The concrete foundations shall be done to meet the following standards:

- BS 8004: Foundations
- BS 8081: Code of practice for ground anchorages
- BS 8100: Towers and masts
- ASCE 10-97: Design of latticed towers
- ASCE 74-1991: Guidelines for electrical transmission line structural loading
- BS 8110: Structural use of concrete
- BS 5328: Methods of specifying concrete

The types of the concrete foundations and natures of earth to be considered shall be as follows: -

- Shallow foundations shall be used for bearing capacity of more than 100kN/m^2
- For bearing capacity less than 100kN/ m^2, special foundations shall apply. Suitable special foundations shall be designed according to technical need and are further classified as:
  --Rock anchor for rocky foundations
  --Raft foundations for swampy areas and
  --Deep foundations, which require use of suitable piles.

All Structural Concrete shall be reinforced with deformed steel bars type 1 to BS 4449 and structural design details to BS 8110 and structural steel detailing to BS 4466.

The angle of frustum of earth shall mean the angle vertical of earth frustum to resist the uplift force and shall be established by geotechnical tests.

The factor of safety shall not be less than 2.5 under the normal working conditions and 1.5 under the broken wire conditions.

The upper surfaces of the foundation pads shall be reinforced and sloped within 45 degrees to the horizontal. The minimum thickness of the edges of base pad shall be not less than 300mm.

The frustum shall be assumed to start from the top edges of the pad. Where frustums overlap each other, allowance shall be made for loss of uplift resistance.

Concrete shall cover any part of the top steelwork by at least 100mm and shall extend above the ground level for the minimum height of 350mm. Additional 500mm minimum chimney extension shall be provided to foots on lower side in sloping areas. The upper surface of chimney shall be sloped to ensure drainage of water.

The cleats shall be attached by bolting at the base of each stub to assist in transfer of leg load to the foundation pad as shown on drawing **APPENDIX 1.A.3**. Minimum portion of stub loads in the design of cleats shall be assumed at 50 per cent.

Special Foundations

Besides the above-mentioned concrete foundations, special foundations such as raft type foundation, rock anchor, piled foundation or others may be required. Final type of foundation to be applied for each tower shall be determined in accordance with results of soil investigation performed by the Contractor during execution of the Contract.

For the purpose of tendering, basic designs shall be submitted with the tender under the following assumptions, and prices for the special foundations shall be quoted based on the design.

[a] Raft type foundation

The foundation shall be designed with the following specifications: ultimate bearing capacity of 10 Ton/m^2, soil weight of 1.4 ton/m^3 and no angle of frustum of soil. Weights of reinforced concrete and soil shall be taken as entirely submerged. Other design conditions specified in this subsection will be applied.

[b] Piled foundation

Piles used for the foundation shall be either precast concrete pile with circular or square cross section or in-situ concrete pile.

[i] Pile data

Pile diameter or dimension

- Circular cross section - Φ300 mm.
- Square cross section - 300 x 300 mm
- Pile depth below ground level - 12 m
- Ratio or ultimate bearing/uplift capacity of pile - 2.5: 1

[ii] Uplift

The mass density of concrete below ground level shall be assumed as 1,600 kg/m^3 to allow for hydrostatic effects and similarly soil as 960 kg/m^3. Additional weight of concrete shall be included as necessary to provide the specified resistance to uplifting under any condition. Where bored or driven piles are proposed having no specially made bulb or enlarged concrete foot to provide positive uplift resistance but relying on skin friction alone, at least 75% of the networking uplift force, and 50% of the net broken wire uplift force shall be provided in dead weight of concrete, whichever is the greater. The cost of such concrete shall be included in the piled foundation rate.

[iii] Compression

Mass density of plain concrete shall be assumed as 2,300 kg/m^3 on their technical acceptability and cast.

Contractors must justify assumptions of equal performance of their piling system with that proposed. No extra payment shall be made for access tracks necessary for heavy piling rigs.

Piles shall be embedded in a reinforced concrete cap of adequate dimensions and the caps tied with nominal reinforced concrete beams of a minimum size of 460 mm deep by 300 mm wide with at least eight 20 mm diameter main reinforcing bars per beam.

Piling shall be carried out using an approved procedure throughout. The actual length and numbers of piles required at any given location shall be approved by the Engineer on the basis of the final agreed design data.

[c] Other Foundations

Where special ground conditions exist which do not allow for any of the above designs in an original or modified fashion, special types of foundations may be employed. They will be paid for on basis of submitted rates schedule for concrete, steel and excavations applying throughout, irrespective of special conditions.

Tower prices shall cover for all costs not covered by special scheduled rates where admissible including the provision of access tracks and standings for piling equipment or building of bund for the Contractor’s convenience in paddy fields or other flooded areas.

FOUNDATION WORKS

Soil Investigation

The Contractor shall make tests of subsoil conditions at every tower site by means of an approved simple hand-operated borer [sampling] and sounding tool, and indicate results on the approved soil test sheets together with ground water levels and proposed foundation type to be applied at the tower position.

The Contractor shall obtain the Engineer's approval for the foundation type in advance of the foundation works at each tower site. Particular note is to be made where any poor ground is encountered likely to require special foundations. The test results shall show firm evidences to prove reasons why the proposed type of foundation is selected from the specified foundation types. The cost of the sub-soil tests is deemed included in the rate for foundation work.

The Engineer may request the Contractor additional sub-soil tests at the bottom of excavated foundation holes, if the Engineer judges its necessity for further confirmation on the proposed foundation types. The sub-soil tests shall be done at the earliest stage of the field works to cater for the urgency of having tower stubs and templates on site and in order that foundation works can proceed with a minimum of delay. BS5930, British soil investigation code will apply as a technical guide for reference.

Excavation and Backfilling

Where angle towers are fitted with unequal length cross arms at each side of the tower, the tower centre shall be offset to ensure that conductors are located as near as possible equidistant either side of the route centerline in adjacent spans.

The Contractor shall ensure that excavations are made to the correct depth and width. If excavations are taken deeper that the designed dimension the excess depth shall be backfilled with concrete at the Contractor's expense. If excavations are made wider than the designed dimension, such modifications to the design as the Engineer may require shall be made at the Contractor's expense.

For uplift foundations, undercutting or other approved method shall be applied as far as possible for allowing upward bearing of the foundation pad against undisturbed soil for a minimum width of 250mm all around. Alternatively, the concrete pad shall be cast to the edge of the excavation for a minimum height of 250 mm in order to gain assistance by adhesion to the original ground. In cases where the concrete block is cast in undercutting, the earth frustum assumed to resist uplift shall be considered to start from the bottom of the vertical edges of the block. Otherwise, the frustum shall be assumed to start from the upper top of the block edges.

The backfill of all types of foundations shall be thoroughly rammed with mechanical rammers, and the ramming shall be carried out at intervals of not greater than 300 mm to ensure thorough consolidation of the backfill as the Engineer requires.

Foundation Concrete faces shall be painted with three coats of an approved bituminous paint to separate backfill from concrete before backfilling.

In no circumstances shall peat, black Cotton soil or equivalent materials be used as backfill for foundations. Where excavations are made in peat ground, backfilling to the foundations shall be made with a suitable soil or hardcore from an approved source at the Contractor's expense. Backfill shall be finished in such a way that the original ground contours are restored as nearly as possible; any subsidence of backfill shall be made good before the issue of the Taking-Over Certificate.

Stub Setting

Stubs for tower foundations shall only be installed with the use of templates or by use of the lower sections of the tower with the suitable temporary bracings to ensure correct spacing. The stub setting templates shall be of approved type with sufficient rigidity to ensure correct setting of the stubs. The method selected shall be such that all four stubs are supported and interconnected by a rigid steel framework. The main members of the templates must be in the position by the template while the concrete is placed. The templates are not to be removed until at 48 hours after the foundations have been completed and backfilled.

The templates shall be manufactured from mild steel angle or channel or a combination of both, of approved and adequate cross-section, and shall be equipped with central alignment notches or holes, corner braces, riser-braces, and stub angle bolting legs to permit the accurate setting of stubs in respect of the following requirements:

a) Longitudinal centerline
b) Tower lateral centerline
c) Stub elevations [with reference to datum]
d) Stub leveling
e) Inclinations of stubs
f) Stub hip bevels
g) Spacing between stubs

No concrete shall be started before the stubs are confirmed to be in the design positions.

Concrete Works

[a] Concrete for concrete foundation and pile shall have the minimum required breaking strengths as specified in the technical schedules. BS 5328 will refer when specifying concrete and BS 8110 in reference to structural use of concrete.

[b] Cement used shall be Portland with minimum strength of 42.5 N/mm^2 or other approved composition obtained from an approved maker. Portland cement shall conform in all respects to BS-12.

[c] Aggregates shall be clean and free from dust, earthy or organic matter or salt. Coarse aggregate shall be approved grading to be retained on a mesh not less than 5mm square, and of a maximum size to pass a mesh not more than 30 mm square. Where specially approved in writing by the Engineer, coarse aggregate of uniform size which will pass a 25mm mesh may be used throughout. Fine aggregate shall be river sand and shall be coarse, sharp, clean and fee from dust, salt, clay, vegetable matter or other impurity and shall be screened through a mesh not more than 5mm in the clear. It shall be well graded mixture of coarse and fine grains from 5mm gauge downwards. Aggregates shall conform in all ways to BS812 and KS 95:2003.

[d] Water shall be clean and free from all earth, vegetable or organic matter, salt, soil, oil, acid and alkaline substances either in solution or in suspensions. Quality shall be confirmed by lab test to BS 3148.

[e] At least four weeks before commencing any concreting work, the Contractor shall make trial mixes using proposed samples of cement and fine and coarse aggregates.

The test specimens for the trial mixes shall be of cube type. Preliminary test specimens shall be taken from the proposed mixes as follows:

For each proposed mix a set of 6 specimens shall be made from each of 3 consecutive batches. Three from each set of six shall be tested at an age of seven [7] days and three [3] at an age of 28 days. The test shall be carried out in an approved laboratory.

Upon approval of trial mixes neither the mix proportions nor the source of supply of materials shall be altered without the prior approval of the Engineer except that the Contactor shall adjust the proportions of the mix as required, to take account of permitted variations in the materials, such approval shall be subject to the execution, to the Engineer's satisfaction, of trial mix procedures set out herein.

[f] Where directed by the Engineer concrete cubes are to be taken and tested to verify the concrete strength during site concreting works. The Contractor shall provide the cube moulds at site for the purpose accordingly. The test specimens shall be 150 mm cubed and the mould shall be of metal with inner faces accurately machined in order that opposite sides of the specimen are plane and parallel. Each mould shall be provided with the metal base having a smooth machined surface. The interior surfaces of the mould and base should be lightly oiled before concrete is placed in the mould.

[g] The cost of concrete testing shall be deemed to be included in the Contractor's general schedule rates or in the Contract Price. Testing Lab shall be approved.

[h] Requirements for testing concrete samples during construction are set out in BS 8110.

[i] The concrete shall thoroughly be wetted before backfilling commences. When shutters are to be struck, backfilling of excavation is not to take place immediately, and the concrete shall be kept continuously moist to avoid rapid drying.

[j] In the event that the Contractor proposes to use ready mixed concrete for foundation work, approval must first be obtained from the Engineer, who will inspect the batching plant and cement, sand and gravel used for concrete. No ready mixed concrete shall be used in foundation work if it has been mixed in the lorry during its journey for more than 45 minutes. At the discretion of the Engineer, ready mixed concrete may be used in foundations in excess of 45 minutes journey, if the cement is added to the drum at site and is thoroughly mixed prior to placing, or alternatively if the ready mixing lorry carried its own drum during the lorry's journey and not mixed for more than 45 minutes prior to placing. The Engineer's decision to reject any of the above methods of supplying ready mixed concrete shall be final.

[k] Throughout the line route, the Contractor shall at regular intervals and at the time of survey, obtain samples of subsoil and ground water, which he shall have analyzed to ascertain if any agents be present which may have an adverse effect on concrete made with normal Portland cement. The analyses shall be forwarded to the Engineer without delay together with any recommendations for the use of special cement. The Engineer's decision as to the type of cement to be used will be final. The cost of obtaining soil and ground water samples is deemed to be included in the Contract Price. The cost of any special cement used will be paid at an appropriate rate to be agreed with the Engineer.

[l] Concrete shall be placed immediately after mechanical mixing. All concrete shall be thoroughly compacted by mechanical vibration during the operation of placing, and shall be free from honeycombing and other defects. The upper surface of the concrete for all types of foundations shall be finished smooth and sloped in an approved manner to prevent accumulation of water. A concrete addictive of a type approved by the Engineer may be used.

Piling and Other Special Works

Pilling will be carried out using an approved procedure throughout. The actual length and numbers of piles required at any location will be approved by the Engineer on the basis of the final agreed design data and payment made for departures from the assumed tender design quantities on the basis of the difference of quantities times the Schedule variation rates. Piles shall be tested in accordance with Clause 11.8. Tender Prices shall include for all necessary casings, pumping, and depreciation of piling machines, materials, transportation, testing and others.

Where special ground conditions exist which do not allow for any of the designs in an original or modified form, special types of foundations may be employed which will be paid for on the basis of schedule rates submitted. To this extent the submitted schedule of rates for concrete, steel and excavations shall apply throughout irrespective of special conditions.

ERECTION OF TOWERS

Where tower members arrive on site with slight distortions due to handling in transit, they shall be straightened by the Contractor using approved means and offered to the Engineer for inspection and acceptance or rejection before erection commences.

In general, towers shall be assembled and erected with bolts finger tight only. Final tightening of bolts shall only take place when all members are in place. As far as practical, bolts shall be inserted with the nuts facing outwards or downwards.

Whenever wire slings or ropes are liable to abrade tower members, the members shall be suitably protected by heavy Hessian bags or strips, or by some other approved means.

The Contractor shall make use of temporary struts on panels prior to lifting, if in the opinion of the Engineer, there is likelihood of damage occurring to that panel during lifting. Where derricks are used for lifting panel, they shall be securely guyed and shall be supported only at approved locations on the legs.

All towers shall be vertical under the stress set up by the completed overhead line to the satisfaction of the Engineer. The maximum acceptable deviation from vertical shall normally be 1^0.

Proper precautions shall be taken to ensure that no parts of the towers or supports are unduly stressed or damaged in any way during erection. Drifting shall not be allowed.

Suitable ladders shall be used whenever necessary during erection, but such ladders and removal step bolts shall be removed when erection work is in progress.

Before assembly of members, joints shall be free of all earth, or any other substances which might prevent the correct alignment of members. After erection, all materials shall be cleaned of all foreign matter or surplus paint.

Spanners used during erection shall be well shaped and fit closely on the nut to avoid damaging nuts and bolt heads. Approved equipment shall be used for tightening the shear bolts which will be used from ground level up to the lower cross-arm level.

Damage to the galvanized surfaces of bolts, tower steelwork or smashed bolts shall be repaired using zinc rich paint or similar and the cost of such repair is deemed to be included in the appropriate rates.

The Contractor must ensure that tower erection, steel handling and operation of equipment shall be such as to ensure the maximum safety of all personnel associated with the project as well as the public.

Lower parts of towers erected in the submerged area during wet seasons shall be protected from corrosion with an approved bitumastic paint as instructed by the Engineer. The cost for the paint shall be quoted in the Price Schedule.

GROUNDING OF TOWERS

Before placing foundation concrete, basic grounding earthing rods specified in Clause 11.8 shall be installed to each of the foundation cleats. Installation shall ensure that earthing can be isolated from the tower and concrete foundation to allow earthing survey. Measurement of footing resistances of all towers shall be carried out with an approved instrument before stringing of an overhead earth wire. A target value of the resistance is less than **10 ohms**. The Contractor shall report the measured value in an approved form to the Engineer. The Engineer will instruct necessitate of installation of counterpoises to the Contractor who shall then provide the counterpoises as specified in the Clause 11.8 to the instructed towers and measure the resistances for reporting the Engineer. In case the resistance is still high, the Engineer may order the Contractor to install additional counterpoises at no additional cost. Final confirmation of ground resistance shall be carried out before stringing of the overhead ground wire.

ERECTION OF CONDUCTOR AND OVERHEAD EARTHWIRE

a) The fullest possible use shall be made of the maximum conductor lengths in order to reduce the number of joints to the minimum. The number and location of conductor and overhead earthwire tension joints shall be approved. The proposed conductor lengths shall be designed specifically for the final stringing length and appropriate drum schedule submitted for approval before production. Tension joints shall not be less than 15m from the nearest clamp.

b) Unless the Engineer agrees to the contrary, midspan joints shall not be used-

    (i) at locations which would allow less than 3 clear spans between mid-span joints on a given conductor and wire
    (ii) in spans crossing power lines, telecommunications lines, public roads or buildings, and
    (iii) In single, span sections.

c) Conductor repair sleeves shall not be used without the permission of the Engineer, which will be granted only in exceptional circumstances.

d) Conductor and earthwire stringing shall be carried out entirely by tension stringing methods and the Contractor shall submit for approval full details of the precise method of tension stringing and of the stringing equipment which he intends to use. Conductors shall be kept off the ground at all times when the conductor is in motion. The method of tension stringing required to install all conductors and earthwire shall be continuously controlled.

e) The conductor and earthwire tension during stringing operation shall be kept as low as possible, consistent with keeping the conductor and earthwire clear of the ground whilst in motion. At no time will the tensions be allowed to exceed 75% of the final tension.

f) All stringing equipment shall be properly anchored and shall be positioned in such a way that structures, insulators and fittings will not be overloaded.

g) Conductor and earthwire drums shall be securely anchored during the stringing operation and drum jacks shall be of the self braking type to prevent conductor over run.

h) Conductor and earthwire pulling shall be such as will ensure a continuously steady pull. Every precaution is to be taken to prevent damage to the conductor and earthwire. Clamps and other devices used for handling conductor and earthwire during erection shall allow no slippage or relative movement of strands or layers and shall not pinch or deform the conductor and earthwire. Grooves in sheaves and tensioners shall be lined with neoprene or rubber. Sheaves shall have an electrical conducting path between their suspension points and the conductor supported within them and shall run with minimum friction.

i) Conductor and earthwire shall be effectively earthed in an approved manner during running out and at all places where men are working on them.

j) At least one month before stringing commences, the Contractor shall give due to consideration to all the factors involved and submit to the Engineer for approval a fully detailed stringing schedule stating locations of conductor and earthwire drums, winch operation for stringing and the proposed positions of mid-span joints, together with temporary staying wires of towers and all other relevant information.

k) Conductor and earthwire drums shall be closely examined before conductor pulling commences and all nails and other things which could damage the conductors and earthwires shall be removed. During stringing, the conductor and earthwire drums are to be supervised at all times and the conductor and earthwire shall be inspected for defects while it is being pulled off the drums. Any damage caused to conductors or earthwires shall be reported to the Engineer whose decision to replace or repair will be final.

l) Conductors and earthwires shall be carefully regulated to the correct pre-stress and initial tensions by a measurement of sags. Ambient temperature shall be measured by a thermometer suspended on the tower at the sag measurement position. Making for and application of anchor clamps shall follow regulation to initial tension without delay. Immediately after regulation and clamping has been completed in a section, the sag of conductors and earthwire shall not depart from the correct value by more that $^{+}/_{-}$1.5%. Suspension insulator sets shall be installed so that clamps are within 20mm of their correct position on the conductor.

m) The insulators strings shall be cleaned and inspected before assembly. Any defective insulator be shall be removed from site forthwith. Insulators shall have the security clip, cotter pins and other locking devices fully in place and shall be erected in a manner avoiding damage to the sheds, fiber-glass rod or locking devices.

n) Where required by the Engineer, the Contractor shall check prior to the issue of the Taking-Over Certificate that the sags of conductors and earthwire in selected spans are within the specified tolerance, and shall make any adjustment necessary to ensure compliance.

o) Joints, clamps, etc. shall be applied using the approved tools and in such a manner that no bird-caging, over-tensioning of individual wires or layers or other deformation or damage to the conductor and earthwire occurs. Cutting of layers of conductors shall be carried out with tools designed to prevent damage to underlying strands.

p) Compression fittings shall be applied only by linemen approved by the Engineer, using approved methods. The outer surfaces of conductors and earthwires and the interiors of compression sleeves shall be scratched-brushed immediately before assembly.

q) After conductors have been made off and landed, stringing sheaves shall be removed and suspension clamps and vibration dampers shall be fitted with minimum delay. Suspension clamps shall be fitted with due regard to offsets where appropriate, and the conductor and earthwire shall be cleaned before the clamp is assembled.

r) The Contractor shall keep a record of all sagging showing details of the section, the sagging and checking spans, ambient temperature, pre-stress, initial and final sags, the date of sagging and clipping-in offset, etc. This record shall form part of the final records for the line and shall be handed over to the Engineer prior to the issue of taking-Over Certificate. The records shall be available for inspection at any time.

TESTS AT SITE

[1] General

Following investigations and tests shall be carried out by the Contractor, when ordered by the Engineer.

Those investigations and tests as mentioned in the Price schedule will be paid for at the rates entered. Other investigations and tests not scheduled in the Price Schedule shall be deemed to be included in the prices of the relative items of the works.

[2] Ground Prove Tests

Tests by means of an approved type of penetrometer or other approved means shall be carried out during the check survey as provided for in Clause 11.4. Results of these tests shall be submitted to the Engineer on an approved form giving a preliminary indication of the ground bearing properties and water levels, etc. Bore penetration shall be at least 9m below ground level in poor ground.

[3] Laboratory Soil Tests

Where ordered by the Engineer, the Contractor shall obtain soil samples and submit these for tests to an approved laboratory to determine the necessary properties of the soils for the purpose of foundation designs. Such information shall be detailed in an approved manner and conclusions given as to the recommended bearing pressures to be adopted. Tests shall be carried out generally in the manner described in BS-1377.

[4] Ground Bearing Test

Where ordered by the Engineer, the Contractor shall carry out ground bearing tests to determine the ground bearing capacity, by means of loading a 300 mm square plate in an approved manner. Tests shall be carried out generally in the manner described in BS-5930.

[5] Pile Bearing and Uplift Tests

Where ordered by the Engineer, the contract shall carry out pile bearing and uplift tests for all types of pile generally in accordance with the method given in the BS CP-2004. Such tests shall be carried out to determine the ultimate uplift and bearing values.

[6] Foundation Loading Tests

Where ordered by the Engineer, foundation loading tests shall be carried out in full scaled individual footings.

(7) Records of Site Investigation Tests

All records of site investigation tests shall be detailed in an approved manner. Sample log sheets, charts, etc. shall be submitted to the Engineer for approval before any investigation commences. All site investigation data, charts, etc. shall be handed over to the Engineer in

triplicate upon satisfactory conclusion of the tests, and before the issue of Taking-Over Certificate.

Where the Contractor carried out other tests at his own expense, not ordered by the Engineer, and to the contrary, where the Employer had independent tests made along the route of the line, such information shall be made available to the Employer or Contractor as appropriate.

[8] Concrete Tests

The Contractor shall carry out tests on sample of concrete from the foundation works, as required by the Engineer as specified in Clause 11.4. The test specimens shall be stored at the site at a place free from vibration under damp sacks for 24 hours. They shall be then removed from the moulds, marked and stored in water at a temperature between 10^0 C and 21^0 C until the testing date. Specimens which are to be sent to a laboratory for testing shall be packed for transit in a damp sand, or other suitable damp materials, and shall be brought in the laboratory at least 24 hours before test. On arrival at the laboratory, they shall be similarly stored in water until the time of the test.
The results shall be handed in triplicate to the Engineer, as soon as possible after testing, and not later than seven days.

[9] Support Footing Resistance

The resistance to earth of the complete foundation of individual structures shall be measured in an approved manner before the stringing operation of overhead earthwire. The placing of tests electrodes shall normally be along the centre line of the route in such direction as to ensure that the lowest resistance to earth is recorded, and a note shall be made of the direction in the time of the test.

[10] Additional Footing Resistance Test

If in the opinion of the Engineer, it is necessary to reduce the tower footing resistance by means of counterpoises, the Contractor shall make further measurement after the additional counterpoises have been carried out before the stringing operation of the overhead earthwire. Any further measurement shall be carried out as necessary without extra charge.

[11] Measurement of Galvanizing Thickness

The Contractor shall have on site an instrument suitable for accurate checking of galvanizing thickness for the Engineer's use. The gauge shall be available from time of arrival of the first consignment of steel work until the issue of Taking-Over Certificate. The cost of the gauge and other operating expenses shall be deemed to be included in the contract price and the gauge shall remain the property of the Employer.

[12] Testing of Rock Anchors

Where rock anchor foundations are used in hard rock, as provided for by the Engineer's order, the Contractor shall test individual anchors by tensile test loading to failure for

obtaining design data of the foundations. The test shall be considered satisfactory if the steel bar fails by yielding of the bar at or above its ultimate strength.

Anchor for the testing shall be installed away from permanent foundation anchors but in the same rock. The frequency of the test shall depend upon the different types of hard rock encountered and the number of tests performed shall be such as to give confidence in the employment of rock anchor foundations and experience of the type of rock suitable for their use. The frequency of test shall, in the case of dispute, be reasonably determined by the Engineer. Tests shall be carried out generally in the manner described in BS-8081 on ground anchorages. The cost of rock test shall be included in the relevant schedule rates.

[13] Test on Completion

The line shall be energized at full working voltage before handing over, and the arrangement for this and such other test as the Employer/ Engineer shall desire to make on the completed line shall be assisted by the Contractor who shall provide such labour, transport and other assistance as required without extra charge.

SECTION 12

METHOD OF MEASUREMENT & PAYMENT

Price Schedules

General

1. The Price Schedules are divided into separate Schedules as follows:

   AS PER PRICE SCHEDULE

2. The Schedules do not generally give a full description of the plant to be supplied and the services to be performed under each item. Bidders shall be deemed to have read the Employer's Requirements and other sections of the Bidding Document and reviewed the Drawings to ascertain the full scope of the requirements included in each item prior to filling in the rates and prices. The entered rates and prices shall be deemed to cover the full scope as aforesaid, including overheads and profit.

3. If bidders are unclear or uncertain as to the scope of any item, they shall seek clarification in accordance with ITB 7 prior to submitting their bid.

Pricing

4. Prices shall be filled in indelible ink, and any alterations necessary due to errors, etc., shall be initialed by the Bidder.

   As specified in the Bid Data Sheet and Special Conditions of Contract, prices shall be fixed and firm for the duration of the Contract, or prices shall be subject to adjustment in accordance with the corresponding Appendix (Price Adjustment) to the Contract Agreement.

5. Bid prices shall be quoted in the manner indicated and in the currency specified in the Instructions to Bidders in the Bidding Document.

   For each item, bidders shall complete each appropriate column in the respective Schedules, giving the price breakdown as indicated in the Schedules.

   Prices given in the Schedules against each item shall be for the scope covered by that item as detailed in Section 6 (Employer's Requirements) or elsewhere in the Bidding Document.

6. Payments will be made to the Contractor in the currency or currencies indicated under each respective item.

7. When requested by the Employer for the purposes of making payments or partial payments, valuing variations or evaluating claims, or for such other purposes as the

Employer may reasonably require, the Contractor shall provide the Employer with a breakdown of any composite or lump sum items included in the Schedules.

The Contractor when requested shall attend for purpose of measurement, or otherwise accept measurements made by the Employer alone.

Where applicable the Contractor shall indicate on each invoice the identification number of each support to which items in the invoice refer.

Where applicable, unit prices in the Schedule shall be deemed to include for all works on site irrespective of access conditions, including if necessary helicopter transportation, slope of ground, nature of subsoil, presence of water or other obstacles adjacent to or across the line of the route.

All unit prices in Volume II, Schedule 4 shall include all incidental expenses which the Contractor or specialist Subcontractor may incur in the preparation of maintenance of access, in the provision of site services and of all transportation for labour whether skilled or unskilled.

The unit prices in the Schedules shall include all allowances or other supplementary payment to skilled or unskilled labour, customary, authorized or required by regulations in force at the date of the Tender.

All unit prices shall be deemed to include payment to labour, or other expenses incurred for idle time during which work on site is interrupted by liveline, weather conditions or flooding by storm overflow or the like.

While every assistance will be provided to facilitate line construction activities in sequence in accordance with the Contactor's agreed programme of work, there could be occasions when this may not be possible. No claims for additional costs to the Contractor will be accepted solely for such discontinuity of working.

Surplus Material

Surplus material paid for by the Employer shall remain property of the Employer and shall be stored at the project terminal substation. Waste material will not be taken over or paid for by the Employer.

Nominated Subcontractor/Supplier

Where the contract provides for the work to be executed by a Nominated Subcontractor, or goods to be supplied by a Nominated Supplier, the Contactor shall ensure that the Nominated Subcontractor's works are programmed and executed or nominated goods supplied to comply with the requirements of the Contractor's agreed programme. The Contractor shall ensure

that enquiries for Nominated Subcontracts and Supplies are returned to the Employer. The Contractor shall obtain all necessary drawings and accounts, as may be directed by the Employer.

Specialist Subcontractors

Specialist Subcontractors' names shall be submitted to the Employer for approval before they are appointed.

Quantities

The quantities set out in the schedules are, unless otherwise defined, estimated quantities of the works. They are not to be assumed as the actual and correct quantities to be executed by the Contractor in fulfillment of his obligations under the Contract. The Contactor is presumed to have satisfied himself as to the relevance of the estimated quantities in the preparation of his Tender.

Drawings, Reference Standards and Records

The provision of all drawings, design calculations, records and the supply of the relevant reference Standards etc. as stated or specified in the Contract shall be included in the Contract Price.

SURVEY

The cost of full precision or check ground survey undertaken by the Contractor on the Employer's instruction shall be entered in appropriate Schedules in Volume I of the tender document, and distances shall be measured to the nearest meter along the centre-line of the route. The unit price shall include for the establishment or re-establishment of the line route from terminal points and other such fixed points the Employer may define, full ground survey, profiling, support plotting, preparation of Simms document tree marking and tree schedule and pegging of support locations.

ROUTE CLEARANCE & ACCESS

Route clearance undertaken by the Contractor on the Employer's instruction shall be entered in the appropriate schedules in Volume I, and distances covered shall be measured to the nearest metre along the centre line of the route.

FOUNDATIONS

General

The cost of foundations shall be entered in Schedule 4 of Volume II. this shall refer to the supply and installation of foundations in accordance with the Specifications and good engineering.

Where additional work is required over and above that provided for in the Specifications, this will be paid on a measured basis at unit prices submitted.

The unit prices for foundations shall include all necessary geotechnical investigation and geotechnical studies as defined in the Specification, or as required by relevant authorities.

The unit prices for all foundations shall include for site clearing, excavating in any material by any means, manual or mechanical, and for ensuring stability and natural drainage inside the working area, steel formwork, reinforcement, concrete, bitumastic painting for all backfilled depth, compacting and disposal of surplus material, routine testing, site restoration and for all necessary supports to sides of excavations.

Removal of 'man-made' materials such as industrial waste, etc., which the Employer agrees is hazardous and which cannot be removed by normal means and not generated by the contractor shall be paid for at unit prices to be agreed.

The complete cost of foundations for a support shall be entered at the appropriate Schedule 4 unit prices. The unit price shall include for all excavations, conventional pumping (including well-point dewatering), excavation supports, concrete work, formwork, reinforcing, stub steelwork, stub cutting, routine testing, bitumastic painting, backfilling, clearing up and all other work required to complete the foundation in accordance with the Specification.

The unit prices shall also include supply of blinding concrete or the importation of any backfill material necessary due to the excavated material being unsuitable as backfill.

The unit prices for foundations shall include the use of whichever type of cement is to be used and density of concrete necessary to meet the requirements of the specification.

The unit prices for foundations shall include all stub steelwork installation and setting out including the use of templates, setting to any level and any excavation necessary for setting out. The protective treatment to defined concrete faces or support steelwork and provision of site protection barriers shall be included in the rates for the foundations.

The unit prices for foundations shall include the cost for all earthing requirements and labour.

Where site stabilizations outside the defined 'working area' is required, this shall be undertaken at unit prices to be agreed.

The cost of design tests on foundations to prove the foundation design shall be entered in the appropriate section of Schedule 4. The unit prices shall include for the removal of concrete and steel down to 1m below ground level where this deemed necessary by the Employer.

Pile Foundations.

The cost of complete foundations for each support shall be entered at the appropriate Schedule 4 unit prices. The unit prices shall include for mobilization and de-mobilisation of piling rigs, setting out, cleaning, cutting to length, reinforcement and pile cap connection, jointing or piles as necessary, irrespective of number of piles, all excavations (including rock), conventional pumping (including well-point dewatering), exaction supports (including use of bentonite slurries), concrete work for piles, pile cap and tie beams, formwork, reinforcing, stub steelwork, stub cutting, routine testing, backfilling, clearing up and all other work required to complete the foundation in accordance with the Specification.

The unit prices for piled foundations shall be based on:

1. The unit price for a complete tower foundation including pile cap and tie beams.
2. A unit price for piles for the complete tower based on the nominal length defined in Schedule 4.
3. An additional unit price per foundation for the "average" length of pile greater than or less than the defined length below existing ground level. This unit price shall be applied once per complete support foundation irrespective of the number of piles in the foundation and shall be applied per metre length of increased or decreased "average" pile.

Flood Protection Walls

Where the Contractor considers that a gabion wall is necessary to protect a support, the cost shall be entered in the appropriate Schedule 4 unit prices.

SUPPORTS (STEEL TOWERS)

The cost of steel towers, normal extensions shall be entered in Volume I, Schedule 1 unit prices. The unit prices shall include for standard cross-arms, and shall include stub steelwork and setting template.

The unit prices for steel towers shall include for access facilities, anti-climbing devices, attachment plates, ancillary steelwork etc. used as standard on the support. The unit prices shall include for all support mounted notice plates.

The cost of type tests on individual supports to prove the support design shall be entered at the unit prices quoted in the Schedule 4 for successful tests only. All other quality control requirements shall be included within the appropriate unit price.

The cost of tower paint including all necessary preparation, sample and routine tests shall be entered at Schedule 1 unit prices.

INSULATOR SETS AND ASSOCIATED FITTINGS

The cost of all insulator sets shall be entered in Volume II,Schedule 1. The unit prices for insulator sets shall include for all insulator units, links, sag adjusters, turnbuckles, weights,

insulator protective devices (arc horns), tension joints (dead ends) and suspension clamps (inclusive of helical armour rods), used as a standard between the support and the phase conductor.

Unit prices for earthwire tension and suspension sets shall where specified include for all earthwire bonding to the supports including all earthwire bonding clamps in accordance with the Specification.

The cost of all conductor tee-connectors and line termination fittings shall be entered in Schedule1.

CONDUCTORS AND FITTINGS

The cost of phase conductors and earthwires (OPGW), and associated fittings shall be entered in Volume I Schedule 1, and distances shall be measured to the nearest metre after erection, along the centre of the route without allowance for sag, jumpers or scrap.

The unit price shall include for all normal phase and earthwire jumpers including the jumpers from the terminal towers to the substation gantries

The unit prices shall include for conductors, jumpers and associated fittings but excluding insulator sets and earthwire tension sets.

The cost of fiber optic earthwire connections to the joint boxes, fixing clamps, joint boxes and fusion splicing of optical fibers shall be included in the erection and stringing unit price.

MISCELLANEOUS

The cost of tools and spares to be supplied under the contract shall be entered in Volume 1, Schedule 1 (Mandatory Spares) and schedule 6 (Recommended).

SITE VISIT

In practicing due diligence, the contractor is specifically advised to inspect the site & terrain and be well acquainted with the actual working and other prevalent conditions, facilities available, position of material and labor. The bidder is advised to visit and examine the site where the plant is to be installed and its surroundings and obtain for himself on his own responsibility all the information that may be necessary for preparing the bid. The bidders shall ask for necessary clarifications required for clearly understanding the scope & technical /commercial requirements of the tender from KPLC before submitting their offer.

MOBILE PHONES AND ENABLED LAPTOPS

Mobile telephones and enabled laptops are to be provided for use by the Employer's Project Engineer and Employer's Site Supervisors with usage charges relevant to the project paid for by the contractor. The Mobile telephone service provider and the mobile service usage limits are to be agreed on between the service contractor and the employer.

SCHEDULES

PREAMBLE


1. The Technical Schedules and appropriate appendixes shall be filled in and completed by the Bidder, and submitted with the Bid.

2. All documentation necessary to evaluate whether the equipment offered is in accordance with this Specification shall be submitted with the Bid.

3. All data entered in the Schedules of Technical Guarantees are guaranteed values by the Bidder/Authorized manufacturers and cannot be departed from whatsoever.

13.1 SCHEDULE A: LOCATION ORIENTATION


13.1.1 Scope: NAIVASHA – LANET 132kV



*Naivasha- Lanet T*ransmission Line at L.Nakuru **T 747 to T 765**

Station	Easting	Northing
1	173798.516	9965560.32
2	174024.349	9965621.42
3	174117.728	9965732
4	175124.977	9966181.94
5	175644.795	9966628.45
6	175805	9966651
7	175934.774	9966778.094
8	176121.56	9967040.84
9	177808.987	9967885.766
10	179498.517	9967202.359
11	179819.393	9967335.475
12	180155.592	9967473.11
13	174582.586	9965185.141

Appendix 1 A-1



STANDARD HEIGHT

G/A OF 132KV STEEL TOWER
SUSPENSION TOWER

	DATE	SIGN
APPROVED		
CHECKED ENGINEER I/C		
CHECKED HEAD D'MAN		
DRAWN	*13/Sep./06*	*J.M.Kahare*
TRACED		

REF	REVISION	DATE	SIGN


TITLE

GENERAL ARRANGEMENT OF TOWER


APPENDIX 1.A.1

Appendix 1 A-2


CLEARANCE DIAGRAMS




SUSPENSION TOWER



TENSION TOWER



LOWEST PANEL OF TOWER
AND HILL SIDE EXTENSION



LEG AND STEP BOLTS

	DATE	SIGN
APPROVED		
CHECKED ENGINEER I/C		
CHECKED HEAD D'MAN		
DRAWN	*13/Sep./06*	*J.M.Kahare*
TRACED		


REF	REVISION	DATE	SIGN


TITLE


CLEARANCE OF TOWER

APPENDIX 1.A.2


Appendix 1 A-3







ANTI - CLIMBING DEVICE



CLEAT AND GROUNDING ANGLE


	DATE	SIGN
APPROVED		
CHECKED ENGINEER I/C		
CHECKED HEAD D'MAN		
DRAWN	19/Sep./06	J.M.Kahare
TRACED		

REF	REVISION	DATE	SIGN

TITLE **ANTI - CLIMBING DEVICE AND GROUNDING SYSTEM**

APPENDIX 1.A.3

Appendix 1.A.4



Appendix 1.A.5

Electrical & Mechanical specifications for the Composite Insulators

	Specifications	Suspension	Tension
1	Maximum System Voltage (kV)	145	145
2	Pollution Category	Heavy Category -III	Heavy Category -III
3	Dielectric	Silicon rubber	Silicon rubber
4	One-minute power frequency withstand voltage, 50 Hz, wet. (kV)	275	275
5	Lighting impulse withstand voltage, 1,2/50 pos. (kV)	650	650
6	Power arc current	25 kA, 0.5 sec	
7	Minimum creepage distance (mm)	4495	4495
8	Specified mechanical load, tension (kN)	70	100
9	Minimum Arc Gap (mm)	1450	1450
10	Material fittings	Steel h.d.g.	Steel h.d.g
11	Material of rod	E- CR Glass	E- CR Glass
12	Material of housing and sheds	HTV- Silicone	HTV Silicone
13	Socket	IEC 60120/16	IEC 60120/16
14	Ball	IEC 60120/16	IEC 60120/16
15	Arcing Rings material	Steel h.d.g	Steel h.d.g
16	Arcing rings	IEC 61284	IEC 61284
17	Specified mechanical load(KN)	90	120(210)

Appendix 1.A.6

MINIMUM CLEARANCES

Minimum clearance of live parts to towers

The minimum 132kv electrical clearances of live parts to earthed structures for the project shall be as follows (See Figures Appendix 1.A.2):

a) In still air (vertical position) : 1350mm

b) Under 20^0 swing of suspension insulator set or jumper conductors : 1350mm

c) Under 40^0 swing of suspension insulator set or jumper conductors : 1140mm

d) Under 60^0 swing of suspension insulator set or jumper conductors : 830mm

Minimum Ground clearances of conductors

Above general terrain:	7.2m
Above main roads:	9.0m
Above other Power lines:	3.2m
Above Communication/Telephone lines:	3.2m
Above railways:	8.5m

APPENDIX 1. A.7

CERTIFICATE OF CONFORMITY

From: (Contractor Details)

To: Kenya Power and Lighting Company Ltd,
P. O Box 30099 - 00100,
Nairobi,
Kenya.

For the Attention of …….

JUJA/LANET – NAIVASHA/LESSOS 132 kV Transmission Line Rehabilitation Project

We certify that the products detailed below have been inspected, tested and unless noted to the contrary, conform in all respects to the requirements.

QUANTITY DESCRIPTION

ATTACHMENTS

Test reports (details) _____

(Other details as per relevant section)

Dated _____ Signed _____

Status _____

13.2 SCHEDULE B - PLACES OF MANUFACTURE

MANUFACTUERS AND PLACES OF MANUFACTURE, TESTING, INSPECTIONS (MUST FILL THIS INFORMATION)

Item	Details	Manufacturer	Place of Manufacture	Place of Testing & Inspection
1	Design of Towers			
2	Steel Sections			
3	Fabrication			
4	Nuts & Bolts			
5	Galvanizing			
6	Tower Tests			
7	Composite Insulators			
8	Lynx compression joints & clamps			
9	Insulator /fittings			
10	Lynx conductor			
11	Conductor Aluminium strands			
12	Steel core for conductor			
13	Steel earth wire 7/14			
14	ACCC Conductor-Casablanca			
15	Composite core			
16	Armour rods for ACCC			
17	Optical Ground Wire			
18	Vibration dampers			
19	ACCC Jointing Compressors			

Note: The words “or Similar” or “equivalent” etc. will not be accepted

In the event of award of contract, no manufacturers or sub-contractors other than those named above will be accepted by the Employer for the appropriate service or equipment.
Any change in manufacturer not in employers record will necessitate due diligence at the bidder’s cost.

13.3 SCHEDULE C; TECHNICAL PARTICULARS AND GUARANTEES FOR TRANSMISSION LINE

C1 - PHASE CONDUCTORS

Item	Description	Units	Proposed
a	**STRANDED CONDUCTORS**		
	Type of Conductor-	-	
	Code Name- LYNX/Casablanca	-	
	Aluminum wire	Nos./mm	
	Steel wire	Nos./mm	
	Overall diameter	mm	
	Cross-section of Aluminium area	mm^2	
	Cross-section of Steel area/Carbon core	mm^2	
	Weight per km	kg	
	Calculated Breaking load	ken	
	Maximum resistance at 20 deg. C per km	ohm	
	Modulus of Elasticity	kg/ mm^2	
	Conductor lay	-	
	Minimum weight of grease	Kg/km	
	Length of conductor per drum	m	
	Approximate net weight per drum	kg	
	Approximate gross weight per drum	kg	
	Dimension of drum (diameter x thickness)	mm x mm	
b	**INDIVIDUAL WIRES BEFORE STRANDING**		
	Tolerance of diameter of Aluminum wire	%	
	Tolerance of diameter of Steel wire	%	
	Minimum tensile strength of Aluminum wire	kg/ mm^2	
	Minimum tensile strength of Steel wire	kg/ mm^2	
	Conductivity	%	
	Minimum twisting number of steel wire: -100 x diameter (length)	Nos.	
	Galvanizing: - Min. coating weight of Zinc	Grams/m^2	

TECHNICAL PARTICULARS AND GUARANTEES FOR TRANSMISSION LINE

C2 - CONDUCTOR ACCESSORIES

Item	Description		Units	Proposed
2	**CONDUCTOR ACESSORIES**			
	a	**Tension Joint**		
		Type- Compression	-	
		Materials- Aluminum & steel	-	
		Length	mm	
		Ultimate breaking Load	kg	
	b	**Vibration Dampers**		
		Type- Stockbridge	-	
		Weight	kg	
		Galvanizing: - Min. quantity coating	g/ m^2	
		Galvanizing: - Min. number of uniformity 1 minute coating	times	
	c	**Preformed Armored Rod**		
		Number of individual wires	Nos.	
		Diameter of individual wires	mm	
		Length wires	mm	

C3 - CONDUCTOR FITTINGS

Description		Units	Proposed	
FITTINGS			**Suspension**	**Tension**
a	**Clamp for Conductor**			
	Type		Trunnion	Compression
	Material of clamp			
	Length of clamp	mm		
	Ultimate breaking Load	kg		
	Approx. slipping Load	kg		
b	**Clamp for Earth wire**		Trunnion	Bolted or Compression
	Type			
	Material of clamp	mm		
	Length of clamp	kg		
	Ultimate breaking Load	kg		
	Approx. slipping Load	kg		

C4 - INSULATOR UNITS & ACCESSORIES

	Description	Units	Proposed	
			Suspension	Tension
1	Maximum System Voltage	kV		
2	Pollution Category	class		
3	Dielectric			
4	One-minute power frequency withstand voltage, 50 Hz, wet.	kV		
5	Lighting impulse withstand voltage, 1,2/50 pos.	kV		
6	Power arc current	kA, 0.5sec		
7	Minimum creepage distance	mm		
8	Specified mechanical load,	KN		
9	Minimum Arc Gap	mm		
10	Material fittings			
11	Material of rod			
12	Material of housing and sheds			
13	Socket	IEC standard		
14	Ball	IEC Standard		
15	Arcing Rings material			
16	Arcing rings	IEC Standard		

C5 – OPGW

Type: _____

Item	Particulars	Unit	Employer's requirement	Tender value
	OPGW			
1	Number of fibers		≥ 48	
2	Core diameter	µm	8.3 or 9 with a 3% tolerance	
3	Cladding design, either matched or depressed			
4	Clad diameter	µm	125.0 ± 2	
5	Core-clad concentricity		< 2%	
6	Coating diameter	µm	250.0 ± 15	
7	Coating concentricity	≥	0.70	
8	Attenuation: 1310 nm 1550 nm	dB/km	≤ 0.40 ≤ 0.25	
9	Bending attenuation: 1310 nm 1550 nm	dB/km	≤ 0.40 ≤ 0.25	
10	Temperature dependence	dB/km	≤0.05 (-20°C-+85°C)	
11	Cut-off wavelength	Nm	≤ 1250	
12	Chromatic dispersion:			
	Zero dispersion at	Nm	1310 ± 12 1550 ± 15	
	Zero dispersion slope (max.)	ps/nm^2 (km)	0.092 0.085	
	Zero dispersion slope (max.)	ps/nm^2 (km)	0.092 0.085	
13	Mode field diameter:			
	1300 nm	mm	9.30 ± 0.50	
	1550 nm	mm	10.50 ± 1.00	
14	IL-proof test level	g/m2	35 x 106	
15	Splice attenuation	dB/ splice	0.02	
16	Connector loss	dB/ connector	< 0.5	

	ODF			
Item	**Particulars**	**Unit**	**Employer's requirement**	**Tender value**
	Manufacturer	-		
	Type	-		
	Number of fiber interconnections	-	96	
	Connector loss	dB/connector	< 0.5	
	Screw on type connectors	-	yes	
	designed for 19” cubicles	-	yes	
		-	-	

C6. TOWERS & FOUNDATIONS

Item	Particulars	Unit	Type - S	Type-H	Type -T
5.1	**DIMENSIONS AND WEIGHT OF TOWER**				
	Overall height of standard tower (+0m)	m			
	Length of top conductor cross-arm	m			
	Length of bottom conductor cross-arm	m			
	Vertical spacing of conductor: Ground wire and top conductor Top conductor and middle conductors Top conductor and bottom conductors	 m m m			
	Width of tower body at: Top of tower Lowest cross-arm Ground level of standard tower (+0m)	 m m m			
	Weight of towers -3m body extension +0m body extension +3m body extension +6m body extension	 kg kg kg kg			
5.2	**LOAD ON FOUNDATION FROM TOWERS**				
5.2.1	Compression Load -3m body extension +0m body extension +3m body extension +6m body extension	 kg kg kg kg			
5.2.2	Uplifting Load -3m body extension +0m body extension +3m body extension +6m body extension	 kg kg kg kg			
5.3	**CONCRETE PAD FOUNDATION AND STUB LENGTH**				

Item	Particulars	Unit	Type - S	Type- H	Type -T
5.3.1	Depth of Foundations				
	-3m body extension	mm			
	+0m body extension	mm			
	+3m body extension	mm			
	+6m body extension	mm			
5.3.2	Width of Base Pad				
	-3m body extension	mm			
	+0m body extension	mm			
	+3m body extension	mm			
	+6m body extension	mm			
5.3.3	Thickness of Base Pad				
	-3m body extension	mm			
	+0m body extension	mm			
	+3m body extension	mm			
	+6m body extension	mm			
5.3.4	Top Width of Chimney				
	-3m body extension	mm			
	+0m body extension	mm			
	+3m body extension	mm			
	+6m body extension	mm			
5.3.5	Bottom Width of Chimney				
	-3m body extension	mm			
	+0m body extension	mm			
	+3m body extension	mm			
	+6m body extension	mm			
5.3.6	Volume of Excavation				
	-3m body extension	cu. m			
	+0m body extension	cu. m			
	+3m body extension	cu. m			
	+6m body extension	cu. m			
5.3.7	Volume of Concrete				
	-3m body extension	cu. m			
	+0m body extension	cu. m			
	+3m body extension	cu. m			
	+6m body extension	cu. m			
5.3.8	Length of Stubs: (stub length x cleat)				
	-3m body extension	mm			
	+0m body extension	mm			
	+3m body extension	mm			
	+6m body extension	mm			

14. SCHEDULES OF RATES AND PRICES

14.1 Schedule No. 1.: TOWER & LINE ACCESORIES

Item	Description	Unit	Qty. *(1)*	Rate *(2)*	Amount *(1) x (2)*
	TRANSMISSION LINE TOWERS				
	ESCARPMENT				
T01E	132kV Type H/T towers inclusive of all fittings & extensions	Lot	1		
	LAKE NAKURU				
T01	132kV Type H towers inclusive of all fittings & extensions	Lot	1		
T02	132kV Type T towers inclusive of all fittings & extensions	Lot	1		
T03	132kV Type S towers inclusive of all fittings & extensions	Lot	1		
T04	Tower earthing materials	Lot	1		
T05	Bitumastic paint	Lot	1		
	CONDUCTOR AND FITTINGS				
T06	175 mm^2 ACSR Lynx conductor	km	6		
T07	175 mm2 Vibration dampers	Lot	1		
T08	175 mm2 Midspan joints	Lot	1		
T09	175 mm2 Line termination fittings	Lot	1		
T10	273.6 mm^2 ACCC-Casablanca conductor	km	52		
T11	273.6 mm^2 Vibration dampers	Lot	1		
T12	273.6 mm^2 Midspan joints	Lot	1		
T13	273.6 mm^2 Line termination fittings	Lot	1		
	EARTH WIRE				
T14	Steel Earth wire - 7/14	Km	10		
T15	Vibration dampers	Lot	1		
T16	Tension and suspension clamps	Lot	1		
T17	Aircraft warning balls	Lot	1		
	OPGW EARTH WIRE				
T18	OPGW	Km	10		
T19	Vibration dampers	Lot	1		
T20	Tension and suspension clamps	Lot	1		

Item	Description	Unit	Qty. *(1)*	Rate *(2)*	Amount *(1) x (2)*
T21	Splicing boxes	Lot	1		
	INSULATORS AND FITTINGS				
T22	Suspension insulators with arcing rings and associated clamp and fittings for Lynx conductor.	Lot	1		
T23	Tension insulators with arcing rings and associated clamp and fittings for Lynx conductor	Lot	1		
T24	Suspension insulators with arcing rings and associated clamp and fittings for ACCC Casablanca conductor.	Lot	1		
T25	Tension insulators with arcing rings and associated clamp and fittings for ACCC Casablanca conductor.	Lot	1		
Name of Bidder;					
Signature of Bidder;					

14.2 Schedule No.2. MANDATORY SPARES

	MANDATORY SPARES				
Item	**Description**	**Unit**	**Qty. (1)**	**Rate (2)**	**Amount (1) x (2)**
	Towers Fittings				
S1	Mid-span Compression joints for Lynx with jumper lugs sets	Pc	20		
S2	Repair sleeve for Lynx	Pc	20		
S3	Dead-end compression (Complete) for Lynx	Pc	20		
S4	Vibration damper for Lynx	Pc	15		
S5	Vibration damper for overhead earth wire (OPGW)	Pc	15		
S6	LYNX jumper Lugs set	Pc	20		
S7	Mid-span Compression joints for ACCC-Casablanca with jumper lugs sets	Pc	20		
S8	Repair sleeve for ACCC-Casablanca	Pc	20		
S9	Dead-end compression (Complete) for ACCC-Casablanca	Pc	20		
S10	Vibration damper for ACCC-Casablanca.	Pc	15		
S11	ACCC-Casablanca jumper Lugs set	Pc	20		
	Insulators and Fittings				
S12	132kV Suspension insulator string with complete set of fittings	Pc	20		
S13	132kV Tension(120/210KN) insulator string with complete set of fittings	Pc	20		
S14	Suspension clamp (shoe clamps) for Lynx	Pc	10		
S15	Suspension clamp (shoe clamps) for ACCC-Casablanca.	Pc	10		
S16	273.6 mm^2 ACCC-Casablanca conductor.	Km	2.5		
S17	175 mm^2 Lynx conductor.	Km	3		

Name of Bidder;

Signature of Bidder/Stamp;

14.3 Schedule No. 3. DESIGN SERVICES

Item	Description	*Unit*	*Qty. (1)*	*Rate (2)*	*Amount (1) x (2)*
KD01	132 kV Transmission Line designs/redesign	Lot	1		
KD02	132 kV Transmission Line designs/redesign Tests	Lot	1		
KD03	Geotechnical investigations and studies	Lot	1		
KD04	Commissioning	Lot	1		
	TOTALS				

Name of Bidder:
Signature of Bidder/Stamp:

14.4 Schedule No. 4. INSTALLATION

Item	Description	Unit	Qty. (1)	Rate (2)	Amount (1) x (2)
	JUJA - NAIVASHA 132kV, ESCARPMENT/MAIMAHIU				
T300	Survey works (check survey, profile and plan surveys, setting out)	Lot	1		
T301	Civil works (Routes clearance, temporary works, access routes, safety, holding)	Lot	1		
T302	Foundations works, (foundation excavation, demolish existing stub where they obstruct new works, rebar's, stubs, earthing, formwork, concreting, curing, backfilling etc.)	Lot	1		
T303	Towers Erection.	Lot	1		
T304	Recover and replace damaged part sections at tower 1051 and T1053[1].	Lot	1		
T305	Stringing works, Conductors, OPGW (including OPGW fusion splicing), Earth wire, anchoring,	Lot	1		
T306	Site Restoration works, Foundation Protection/ Erosion Mitigation Gabions, trimming of existing stubs up to 1.5 Meter Depth below natural ground, sites clean up, transport of recovered towers to designated sites.	Lot	1		
	LANET - LESSOS 132KV L. NAKURU NATIONAL PARK				
T300	Survey works (check survey, profile and plan surveys, setting out)	Lot	1		
T301	Civil works (Routes clearance, temporary works, access routes, safety, holding)	Lot	1		
T302	Foundations[2] works, (foundation excavation, demolish existing stub where they obstruct new works,	Lot	1		

Item	Description	Unit	Qty. (1)	Rate (2)	Amount (1) x (2)
	rebar's, stubs, earthing, formwork, concreting, curing, backfilling etc.)				
T303	Towers recovery[3] and Erection	Lot	1		
T304	Stringing works, ACCC Casablanca Conductors, OPGW (including OPGW fusion splicing), steel earth wire, anchoring,	Lot	1		
T305	Site Restoration works, Foundation Protection/ Erosion Mitigation Gabions, trimming of existing stubs up to 1.5 Meter Depth below natural ground, sites clean up, recovered towers transport to designated sites.	Lot	1		

[1] T1051 & T1053- Damaged one leg section and T1053 has missing earth wire crossarm. (KPLC to provide the crossarm).
[2] Provide rates only for any requirement of special foundation.
[3] Includes Conductors recovery and submerged section.

14.5 Schedule No. 5. OTHER SERVICES

	OTHER SERVICES				
Item	**Description**	**Unit**	**Qty. (1)**	**Rate (2)**	**Amount (1) x (2)**
	SITES LIASON				
SO01	Administrative costs, Statutory legislation, DOSH, County Government	Lot	1		
SO02	Project Management facilitation; project enabled Laptops (5) and Mobile Phones (5)	Lot	1		
	FACTORY ACCEPTANCE TESTS (FATs)				
FAT01	Tower test; Full scale test at an internationally accredited testing facility. Test on H Type Section tower with the highest extension as designed for double circuit 132Kv towers.	Lot	1		
FAT02	Conductor-ACCC Casablanca	Lot	1		
FAT03	OPGW Fittings and accessories.	Lot	1		
FAT04	Insulator, conductor fittings and accessories.	Lot	1		
FT05	Facilitation for project personnel attending FATs.	Lot	1		
TD 06	Training (installation, operation and maintenance of ACCC)	Lot	1		
	Name of Bidder:				
	Signature of Bidder/Stamp:				

14.6 SCHEDULE NO. 6. GRAND SUMMARY

Item	Description	Total Price Currency (KShs.)
1	Total Schedule No. 1. Tower and line accessories	
2	Total Schedule No. 2. Mandatory maintenance spares	
3	Total Schedule No. 3. Design Services	
4	Total Schedule No. 4. Installation Services	
5	Total Schedule No. 5 Other Services	
	SUBTOTAL	
	0.03% PPCBL LEVY	
	16%VAT	
GRAND TOTAL (to Bid Form)		
Name of Bidder:		
Signature of Bidder/Stamp:		

MANDATORY SITE VISIT FORM

CONFIRMATION OF MANDATORY PRE-BID SITE VISIT

JUJA - NAIVASHA 132kV, ESCARPMENT COLLAPSED TOWER

Name of Tenderer……..

Site Visited…….

Date of Visit……

Name, position and signature of the Tenderer's staff visiting the site.

Name:……

Position…….

Qualification ……

Signature……..

Tenderer's Official Stamp

Site Visit conducted by Employer's Authorised Officer's

Name ……

Signature……

Employer's Official Stamp

MANDATORY SITE VISIT FORM

CONFIRMATION OF MANDATORY PRE-BID SITE VISIT

LANET - LESSSOS 132kV, L. NAKURU SUBMERGED TOWERS, LANET

Name of Tenderer……..

Site Visited…….

Date of Visit……

Name, position and signature of the Tenderer's staff visiting the site.

Name:……

Position…….

Qualification ……

Signature……..

Tenderer's Official Stamp

Site Visit conducted by Employer's Authorised Officer's

Name ……

Signature……

Employer's Official Stamp